

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0022000000-M	225	UNCLASSIFIED EXCAVATION	22,000 M3		
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (20+72.950-L-)	Lump Sum	L.S.	
0005	0038000000-M	SP	SHALLOW UNDERCUT	500 M3		
0006	0050000000-M	226	SUPPLEMENTARY CLEARING & GRUB- BING	0.4 HA		
0007	0057000000-M	226	UNDERCUT EXCAVATION	130 M3		
0008	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0009	0080000000-M	SP	CLASS IV SUBGRADE STABILIZA- TION	1,000 MTN		
0010	0134000000-M	240	DRAINAGE DITCH EXCAVATION	750 M3		
0011	0141000000-M	240	BERM DITCH CONSTRUCTION	225 M		
0012	0196000000-M	270	FABRIC FOR SOIL STABILIZATION	1,000 M2		
0013	0234000000-M	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	1,000 M3		
0014	0320000000-M	SP	FOUNDATION CONDITIONING FABRIC	2,160 M2		
0015	0330000000-M	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	740 MTN		
0016	0335100000-M	SP	300MM DRAINAGE PIPE	13.2 M		
0017	0335200000-M	SP	375MM DRAINAGE PIPE	406.8 M		
0018	0335300000-M	SP	450MM DRAINAGE PIPE	216 M		
0019	0335400000-M	SP	600MM DRAINAGE PIPE	49.2 M		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	0335500000-M	SP	750MM DRAINAGE PIPE	25.2	M	
0021	0335850000-M	SP	****MM DRAINAGE PIPE ELBOWS (300MM)	2	EA	
0022	0335850000-M	SP	****MM DRAINAGE PIPE ELBOWS (375MM)	6	EA	
0023	0335850000-M	SP	****MM DRAINAGE PIPE ELBOWS (450MM)	2	EA	
0024	0354000000-M	SP	****MM RC PIPE CULVERTS, CLASS ***** (300MM, IV)	24	M	
0025	0448200000-M	SP	375MM RC PIPE CULVERTS, CLASS IV	422.4	M	
0026	0448300000-M	SP	450MM RC PIPE CULVERTS, CLASS IV	193.2	M	
0027	0448400000-M	SP	600MM RC PIPE CULVERTS, CLASS IV	81.6	M	
0028	0448500000-M	SP	750MM RC PIPE CULVERTS, CLASS IV	36	M	
0029	0986000000-M	SP	GENERIC PIPE ITEM 300MM CORRUGATED STEEL PIPE CULVERTS, 1.63MM THICK	24	M	
0030	0986000000-M	SP	GENERIC PIPE ITEM 375MM SIDE DRAIN PIPE	202.8	M	
0031	0986000000-M	SP	GENERIC PIPE ITEM 400MM CORRUGATED STEEL PIPE CULVERTS, 1.63MM THICK	12	M	
0032	0986000000-M	SP	GENERIC PIPE ITEM 450MM SIDE DRAIN PIPE	56.4	M	
0033	0986000000-M	SP	GENERIC PIPE ITEM 600MM CORRUGATED STEEL PIPE CULVERTS, 1.63MM THICK	10.8	M	
0034	0986000000-M	SP	GENERIC PIPE ITEM 800MM CORRUGATED STEEL PIPE CULVERTS, 2.01MM THICK	24	M	

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	0992000000-M	SP	GENERIC PIPE ITEM 300MM CORRUGATED STEEL PIPE ELBOW, 1.63MM THICK	4 EA		
0036	0992000000-M	SP	GENERIC PIPE ITEM 600MM CORRUGATED STEEL PIPE ELBOW, 1.63MM THICK	2 EA		
0037	0995000000-M	340	PIPE REMOVAL	388.2 M		
0038	1110000000-M	510	STABILIZER AGGREGATE	500 MTN		
0039	1121000000-M	520	AGGREGATE BASE COURSE	2,000 MTN		
0040	1220000000-M	545	INCIDENTAL STONE BASE	300 MTN		
0041	1275000000-M	600	PRIME COAT	2,700 L		
0042	1330000000-M	607	INCIDENTAL MILLING	200 M2		
0043	1489000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	10,600 MTN		
0044	1498000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	10,500 MTN		
0045	1519000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	10,000 MTN		
0046	1560000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,550 MTN		
0047	1693000000-M	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	220 MTN		
0048	2022000000-M	815	SUBDRAIN EXCAVATION	414 M3		
0049	2033000000-M	815	SUBDRAIN FINE AGGREGATE	207 M3		
0050	2044000000-M	815	150MM PERFORATED SUBDRAIN PIPE	500 M		
0051	2055000000-M	815	150MM SUBDRAIN PIPE WYES, TEES, & ELBOWS	51 EA		
0052	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	4 EA		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	2077000000-M	815	150MM OUTLET PIPE (SUBDRAINS)	8 M		
0054	2209000000-M	838	ENDWALLS	6 M3		
0055	2253000000-M	840	PIPE COLLARS	1 M3		
0056	2264000000-M	840	PIPE PLUGS	0.5 M3		
0057	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	60 EA		
0058	2308000000-M	840	MASONRY DRAINAGE STRUCTURES	4 M		
0059	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	11 EA		
0060	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	13 EA		
0061	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	9 EA		
0062	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	4 EA		
0063	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	11 EA		
0064	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	11 EA		
0065	2396000000-N	840	FRAME WITH COVER, STD 840.54	2 EA		
0066	2462000000-M	SP	***MM SLUICE GATE (625MM)	2 EA		
0067	2462000000-M	SP	***MM SLUICE GATE (970MM)	1 EA		
0068	2535000000-M	846	*** X ***MM CONCRETE CURB (200MM X 450MM)	38 M		
0069	2535000000-M	846	*** X ***MM CONCRETE CURB (225MM X 450MM)	134 M		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0070	2542000000-M	846	450MM CONCRETE CURB & GUTTER	66 M		
0071	2549000000-M	846	750MM CONCRETE CURB & GUTTER	1,280 M		
0072	2556000000-M	846	SHOULDER BERM GUTTER	245 M		
0073	2577000000-M	846	CONCRETE EXPRESSWAY GUTTER	72 M		
0074	2591000000-M	848	100MM CONCRETE SIDEWALK	600 M2		
0075	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	3 EA		
0076	2612000000-M	848	150MM CONCRETE DRIVEWAY	1,440 M2		
0077	2655000000-M	852	125MM MONOLITHIC CONCRETE ISLANDS (KEYED IN)	100 M2		
0078	2738000000-M	SP	GENERIC PAVING ITEM 200MM CONCRETE TRUCK APRON	235 M2		
0079	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	6 EA		
0080	2893000000-N	SP	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX WITH MANHOLE COVER	1 EA		
0081	3030000000-M	862	STEEL BM GUARDRAIL	346.71 M		
0082	3045000000-M	862	STEEL BM GUARDRAIL, SHOP CURVED	19.05 M		
0083	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0084	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0085	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0086	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	9 EA		
0087	3360000000-M	863	REMOVE EXISTING GUARDRAIL	76 M		
0088	3380000000-M	862	TEMPORARY STEEL BM GUARDRAIL	41.91 M		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	4 EA		
0090	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4 EA		
0091	3628000000-M	876	RIP RAP, CLASS I	55 MTN		
0092	3649000000-M	876	RIP RAP, CLASS B	1,060 MTN		
0093	3656000000-M	876	FILTER FABRIC FOR DRAINAGE	4,200 M2		
0094	4072000000-M	903	SUPPORTS, 4.5-KG STEEL U-CHANN EL	302 M		
0095	4102000000-N	904	SIGN ERECTION, TYPE E	69 EA		
0096	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	6 EA		
0097	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	41 EA		
0098	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	2 EA		
0099	4238000000-N	907	DISPOSAL OF SIGN, D, E OR F	1 EA		
0100	4400000000-M	1110	WORK ZONE SIGNS (STATIONARY)	59 M2		
0101	4405000000-M	1110	WORK ZONE SIGNS (PORTABLE)	10 M2		
0102	4410000000-M	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	27 M2		
0103	4430000000-N	1130	DRUMS	430 EA		
0104	4435000000-N	1135	CONES	50 EA		
0105	4445000000-M	1145	BARRICADES (TYPE III)	40 M		
0106	4455000000-N	1150	FLAGGER	1,000 MD		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	325	EA	
0108	4685000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 2.3MM)	7,350	M	
0109	4686000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 3.1MM)	9,425	M	
0110	4695000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (200MM, 2.3MM)	458	M	
0111	4710000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (600MM, 3.1MM)	75	M	
0112	4725000000-M	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (2.3MM)	47	EA	
0113	4810000000-M	1205	PAINT PAVEMENT MARKING LINES (100MM)	67,700	M	
0114	4820000000-M	1205	PAINT PAVEMENT MARKING LINES (200MM)	920	M	
0115	4825000000-M	1205	PAINT PAVEMENT MARKING LINES (300MM)	40	M	
0116	4835000000-M	1205	PAINT PAVEMENT MARKING LINES (600MM)	170	M	
0117	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	102	EA	
0118	4850000000-M	1205	REMOVAL OF PAVEMENT MARKING LINES (100MM)	2,000	M	
0119	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	125	EA	
0120	5050000000-N	1404	LIGHT STANDARD, TYPE MTLT ***** (13.7M SA, 4.6M)	8	EA	
0121	5070000000-N	1405	STANDARD FOUNDATION ***** (R1)	8	EA	
0122	5080000000-N	1406	LIGHT STANDARD LUMINAIRES, TYPE ***** (RDW 250W HPS, MC3)	8	EA	

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0123	5120000000-N	1407	ELECTRIC SERVICE POLE **** ***** (9.1M CLASS 4)	1 EA		
0124	5125000000-M	1407	ELECTRIC SERVICE LATERAL ***** (3 #1/0 USE)	15 M		
0125	5160000000-M	1409	ELECTRICAL DUCT, TYPE JA, SIZE **** (TS3)	33 M		
0126	5205000000-M	1410	***#8 W/G FEEDER CIRCUIT IN SIZE *** CONDUIT (2, TS1.5)	308 M		
0127	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC18)	3 EA		
0128	5260000000-N	SP	GENERIC LIGHTING ITEM POWER SUPPLY TO ROADWAY LIGHTS	Lump Sum	L.S.	
0129	5325200000-M	1510	50MM WATER LINE	55 M		
0130	5325600000-M	1510	150MM WATER LINE	1,298 M		
0131	5325800000-M	1510	200MM WATER LINE	236 M		
0132	5326200000-M	1510	300MM WATER LINE	548 M		
0133	5327000000-M	1510	500MM WATER LINE	22 M		
0134	5536000000-M	1515	50MM VALVE	6 EA		
0135	5540000000-M	1515	150MM VALVE	5 EA		
0136	5546000000-M	1515	200MM VALVE	1 EA		
0137	5558000000-M	1515	300MM VALVE	4 EA		
0138	5559000000-M	1515	500MM VALVE	1 EA		
0139	5648000000-N	1515	RELOCATE WATER METER	47 EA		
0140	5672000000-N	1515	RELOCATE FIRE HYDRANT	8 EA		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0141	5709000000-M	1520	***MM FORCE MAIN SEWER (75MM)	13 M		
0142	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	2 EA		
0143	5775000000-M	1525	1200MM DIA UTILITY MANHOLE	1 EA		
0144	5804000000-M	1530	ABANDON 300MM UTILITY PIPE	497 M		
0145	5811000000-M	1530	ABANDON 450MM UTILITY PIPE	24 M		
0146	5828000000-N	1530	REMOVE UTILITY MANHOLE	1 EA		
0147	5882000000-N	SP	GENERIC UTILITY ITEM BREAKDOWN AND REBUILD MANHOLE	3 EA		
0148	5882000000-N	SP	GENERIC UTILITY ITEM WATER METER VAULT	1 EA		
0149	6000000000-M	1605	TEMPORARY SILT FENCE	6,500 M		
0150	6006000000-M	1610	STONE FOR EROSION CONTROL, CLASS A	1,900 MTN		
0151	6009000000-M	1610	STONE FOR EROSION CONTROL, CLASS B	3,000 MTN		
0152	6012000000-M	1610	SEDIMENT CONTROL STONE	1,400 MTN		
0153	6015000000-M	1615	TEMPORARY MULCHING	30 HA		
0154	6018000000-M	1620	SEED FOR TEMPORARY SEEDING	625 KG		
0155	6021000000-M	1620	FERTILIZER FOR TEMPORARY SEED- ING	4.75 MTN		
0156	6024000000-M	1622	TEMPORARY SLOPE DRAINS	225 M		
0157	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0158	6029000000-M	SP	SAFETY FENCE	850 M		
0159	6030000000-M	1630	SILT EXCAVATION	7,700 M3		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0160	6036000000-M	1631	MATTING FOR EROSION CONTROL	45,000 M2		
0161	6037000000-M	SP	COIR FIBER MAT	150 M2		
0162	6038000000-M	SP	PERMANENT SOIL REINFORCEMENT MAT	2,000 M2		
0163	6042000000-M	1632	6.4MM HARDWARE CLOTH	550 M		
0164	6071030000-M	SP	COIR FIBER BAFFLES	1,050 M		
0165	6071050000-M	SP	***MM SKIMMER (38MM)	14 EA		
0166	6084000000-M	1660	SEEDING & MULCHING	15 HA		
0167	6087000000-M	1660	MOWING	17 HA		
0168	6090000000-M	1661	SEED FOR REPAIR SEEDING	375 KG		
0169	6093000000-M	1661	FERTILIZER FOR REPAIR SEEDING	1.25 MTN		
0170	6096000000-M	1662	SEED FOR SUPPLEMENTAL SEEDING	400 KG		
0171	6108000000-M	1665	FERTILIZER TOPDRESSING	23 MTN		
0172	6111000000-M	SP	IMPERVIOUS DIKE	20 M		
0173	6114500000-N	SP	SPECIALIZED HAND MOWING	15 MHR		
0174	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	36 EA		
0175	6123000000-M	1670	REFORESTATION	0.5 HA		
0176	7060000000-M	1705	SIGNAL CABLE	200 M		
0177	7120000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 3 SECTION)	3 EA		
0178	7144000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 5 SECTION)	3 EA		
0179	7300000000-M	1715	UNPAVED TRENCHING (***** (2, 2")	215 M		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0180	7301000000-M	1715	DIRECTIONAL DRILL (***** (2, 2")	70 M		
0181	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	11 EA		
0182	7444000000-M	1725	INDUCTIVE LOOP SAWCUT	175 M		
0183	7456000000-M	1726	LEAD-IN CABLE (***** (14-2)	375 M		
0184	7588000000-N	SP	METAL POLE WITH SINGLE MAST ARM	1 EA		
0185	7590000000-N	SP	METAL POLE WITH DUAL MAST ARM	1 EA		
0186	7613000000-N	SP	SOIL TEST	2 EA		
0187	7614100000-M	SP	DRILLED PIER FOUNDATION	12 M3		
0188	7631000000-N	SP	MAST ARM WITH METAL POLE DE- SIGN	2 EA		
0189	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1 EA		
0190	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	1 EA		
0191	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	5 EA		
0192	7901000000-N	1753	CABINET BASE EXTENDER	1 EA		
STRUCTURE ITEMS						
0193	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (20+72.950-L-)	Lump Sum	L.S.	
0194	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (20+72.950-L-)	Lump Sum	L.S.	
0195	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (20+72.950-L-)	Lump Sum	L.S.	

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0196	8182000000-M	420	CLASS A CONCRETE (BRIDGE)	33.2 M3		
0197	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (20+72.950-L-)	Lump Sum	L.S.	
0198	8217000000-M	425	REINFORCING STEEL (BRIDGE)	3,094 KG		
0199	8364000000-M	SP	HP310X79 STEEL PILES	75 M		
0200	8391000000-N	SP	STEEL PILE POINTS	20 EA		
0201	8475000000-M	460	TWO BAR METAL RAIL	42.36 M		
0202	8517000000-M	460	*** X ****MM CONCRETE PARAPET (355MM X 800MM)	46.92 M		
0203	8608000000-M	876	RIP RAP CLASS II (600MM THICK)	230 MTN		
0204	8622000000-M	876	FILTER FABRIC FOR DRAINAGE	240 M2		
0205	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0206	8753100000-M	430	914MM X 838MM PRESTRESSED CONC BOX BEAMS	351.9 M		

1124/May11/Q252705.25/D836273730000/E206

Total Amount Of Bid For Entire Project :

Contract No: C201242

County: Burke

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General