

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB-BING	2 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	87,000 CY		
0006	0036000000-E	225	UNDERCUT EXCAVATION	3,000 CY		
0007	0038000000-E	SP	SHALLOW UNDERCUT	21,600 CY		
0008	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA-TION	40,000 TON		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	240 CY		
0010	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	44,000 SY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	41,850 SY		
0012	0199000000-E	SP	TEMPORARY SHORING	2,030 SF		
0013	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	2,000 CY		
0014	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	3,200 SY		
0015	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	1,020 TON		
0016	0354000000-E	SP	**** RC PIPE CULVERTS, CLASS ***** (15", III)	1,164 LF		
0017	0354000000-E	SP	**** RC PIPE CULVERTS, CLASS ***** (18", III)	568 LF		
0018	0354000000-E	SP	**** RC PIPE CULVERTS, CLASS ***** (24", III)	160 LF		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0354000000-E	SP	**** RC PIPE CULVERTS, CLASS ***** (30", III)	140 LF		
0020	0354000000-E	SP	**** RC PIPE CULVERTS, CLASS ***** (36", III)	44 LF		
0021	0448200000-E	SP	15" RC PIPE CULVERTS, CLASS IV	1,952 LF		
0022	0448300000-E	SP	18" RC PIPE CULVERTS, CLASS IV	268 LF		
0023	0448400000-E	SP	24" RC PIPE CULVERTS, CLASS IV	4 LF		
0024	0973100000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE ** IN SOIL (18", 0.5", B)	32 LF		
0025	0973300000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE ** NOT IN SOIL (18", 0.5", B)	32 LF		
0026	0986000000-E	SP	GENERIC PIPE ITEM 15" CS PIPE CULVERTS, 0.064" THICK	852 LF		
0027	0986000000-E	SP	GENERIC PIPE ITEM 15" SIDE DRAIN PIPE	3,970 LF		
0028	0986000000-E	SP	GENERIC PIPE ITEM 18" CS PIPE CULVERTS, 0.064" THICK	104 LF		
0029	0986000000-E	SP	GENERIC PIPE ITEM 18" SIDE DRAIN PIPE	356 LF		
0030	0992000000-E	SP	GENERIC PIPE ITEM 15" CS PIPE ELBOWS, 0.064" THICK	33 EA		
0031	0992000000-E	SP	GENERIC PIPE ITEM 18" CS PIPE ELBOWS, 0.064" THICK	4 EA		
0032	0995000000-E	340	PIPE REMOVAL	1,959 LF		
0033	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0034	1110000000-E	510	STABILIZER AGGREGATE	500 TON		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	1121000000-E	520	AGGREGATE BASE COURSE	15,400 TON		
0036	1231000000-E	560	SHOULDER BORROW	21,600 CY		
0037	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	3,900 SY		
0038	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 3")	16,200 SY		
0039	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	4,400 TON		
0040	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	64,600 TON		
0041	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	2,800 TON		
0042	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	25,600 TON		
0043	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	6,000 TON		
0044	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	66,600 TON		
0045	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4,665 TON		
0046	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	4,000 TON		
0047	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	167,000 LF		
0048	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
0049	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		
0050	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0051	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0053	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0054	2253000000-E	840	PIPE COLLARS	45.146 CY		
0055	2264000000-E	840	PIPE PLUGS	0.09 CY		
0056	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	205 EA		
0057	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	144.54 LF		
0058	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	96 EA		
0059	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	37 EA		
0060	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0061	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	2 EA		
0062	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	1 EA		
0063	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	1 EA		
0064	2396000000-N	840	FRAME WITH COVER, STD 840.54	6 EA		
0065	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	71 EA		
0066	2495000000-E	SP	GENERIC DRAINAGE ITEM CONCRETE APRON FOR GDI	0.79 CY		
0067	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	700 LF		
0068	2556000000-E	846	SHOULDER BERM GUTTER	12,800 LF		
0069	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	17,600 LF		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0070	2619000000-E	850	4" CONCRETE PAVED DITCH	170 SY		
0071	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	700 SY		
0072	2703000000-E	854	CONCRETE BARRIER, TYPE ***** (T)	10,030 LF		
0073	2710000000-N	854	CONCRETE BARRIER TRANSITION SECTION	10 EA		
0074	2717000000-E	854	VARIABLE HEIGHT CONCRETE BAR- RIER, TYPE ***** (T1)	1,520 LF		
0075	2717000000-E	854	VARIABLE HEIGHT CONCRETE BAR- RIER, TYPE ***** (T2)	370 LF		
0076	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	2,030 LF		
0077	2875000000-N	859	CONVERT EXISTING CATCH BASIN TO DROP INLET	11 EA		
0078	2893000000-N	SP	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX WITH MANHOLE COVER	11 EA		
0079	2938000000-N	SP	CONVERT EXISTING DROP INLET TO JUNCTION BOX WITH MANHOLE COVER	5 EA		
0080	3030000000-E	862	STEEL BM GUARDRAIL	31,000 LF		
0081	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	550 LF		
0082	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	2 EA		
0083	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	20 EA		
0084	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0085	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	46 EA		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0086	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
0087	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	66	EA	
0088	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	4	EA	
0089	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	35	EA	
0090	3319000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-83	3	EA	
0091	3345000000-E	864	REMOVE & RESET EXISTING GUARDRAIL	44,400	LF	
0092	3360000000-E	863	REMOVE EXISTING GUARDRAIL	54,791	LF	
0093	3435000000-N	SP	GENERIC GUARDRAIL ITEM REPLACE EXISTING GUARDRAIL OFFSET BLOCKS	1,000	EA	
0094	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	42,900	LF	
0095	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	2,720	EA	
0096	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	640	EA	
0097	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	4,700	LF	
0098	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	390	EA	
0099	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	35	EA	
0100	3554000000-E	866	METAL GATE POSTS FOR *** CHAIN LINK FENCE, DOUBLE GATE (48")	12	EA	
0101	3557000000-E	866	ADDITIONAL BARBED WIRE	2,000	LF	
0102	3564000000-E	866	SINGLE GATES, *** HIGH, *** WIDE, *** OPENING (47", 10', 10')	5	EA	

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0103	3565000000-E	866	DOUBLE GATES, *** HIGH, *** WIDE, *** OPENING (48", 5', 10')	6 EA		
0104	3628000000-E	876	RIP RAP, CLASS I	100 TON		
0105	3649000000-E	876	RIP RAP, CLASS B	160 TON		
0106	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	3,250 SY		
0107	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	4 EA		
0108	4048000000-E	902	REINFORCED CONCRETE SIGN FOUNDATIONS	61 CY		
0109	4054000000-E	902	PLAIN CONCRETE SIGN FOUNDATIONS	5 CY		
0110	4057000000-E	SP	OVERHEAD FOOTING	120 CY		
0111	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	32,765 LB		
0112	4066000000-E	903	SUPPORTS, SIMPLE STEEL BEAM	15,110 LB		
0113	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	5,350 LF		
0114	4078000000-E	903	SUPPORTS, 2-LB STEEL U-CHANNEL	16 EA		
0115	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (275+00 -L- NBL)	Lump Sum	L.S.	
0116	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (299+00 -L- SBL)	Lump Sum	L.S.	
0117	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (30+00 -L1- SBL)	Lump Sum	L.S.	
0118	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (317+80 -L- NBL)	Lump Sum	L.S.	
0119	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (355+00 -L2- NBL)	Lump Sum	L.S.	

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0120	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (381+00 -L3- SBL)	Lump Sum	L.S.	
0121	4096000000-N	904	SIGN ERECTION, TYPE D	24 EA		
0122	4102000000-N	904	SIGN ERECTION, TYPE E	74 EA		
0123	4108000000-N	904	SIGN ERECTION, TYPE F	56 EA		
0124	4109000000-N	904	SIGN ERECTION, TYPE *** (OVER-HEAD) (A)	21 EA		
0125	4109000000-N	904	SIGN ERECTION, TYPE *** (OVER-HEAD) (B)	9 EA		
0126	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	43 EA		
0127	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	20 EA		
0128	4114000000-N	904	SIGN ERECTION, MILEMARKERS	16 EA		
0129	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (A)	14 EA		
0130	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	6 EA		
0131	4138000000-N	907	DISPOSAL OF SUPPORT, STEEL BEAM	12 EA		
0132	4141000000-N	907	DISPOSAL OF SUPPORT, WOOD	2 EA		
0133	4149000000-N	907	DISPOSAL OF SIGN SYSTEM, OVER-HEAD	6 EA		
0134	4152000000-N	907	DISPOSAL OF SIGN SYSTEM, STEEL BEAM	27 EA		
0135	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	160 EA		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0136	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	7 EA		
0137	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	6 EA		
0138	4370000000-N	SP	GENERIC SIGNING ITEM SUPPORTS, OVERHEAD SIGN STR- UCTURE AT "EB US 64 20' +/- IN FRONT OF EXISTING"	Lump Sum	L.S.	
0139	4370000000-N	SP	GENERIC SIGNING ITEM SUPPORTS, OVERHEAD SIGN STR- UCTURE AT "WB US 64 20' +/- IN FRONT OF EXISTING"	Lump Sum	L.S.	
0140	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	632 SF		
0141	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	1,741 SF		
0142	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	130 SF		
0143	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	7 EA		
0144	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0145	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	42 DAY		
0146	4430000000-N	1130	DRUMS	1,100 EA		
0147	4435000000-N	1135	CONES	70 EA		
0148	4445000000-E	1145	BARRICADES (TYPE III)	104 LF		
0149	4455000000-N	1150	FLAGGER	18 MD		
0150	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	11 EA		
0151	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	6 EA		
0152	4480000000-N	1165	TMIA	2 EA		
0153	4485000000-E	1170	PORTABLE CONCRETE BARRIER	18,480 LF		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0154	4510000000-N	SP	LAW ENFORCEMENT	40 HR		
0155	4575000000-E	SP	MOVABLE CONCRETE BARRIER	18,480 LF		
0156	4580000000-E	SP	RESET MOVABLE CONCRETE BARRIER	18,480 LF		
0157	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRANSFER & TRANSPORT VEHICLE FOR MOVABLE CONCRETE BARRIER	1 EA		
0158	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	1,750 EA		
0159	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	193,644 LF		
0160	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	23,307 LF		
0161	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	13,526 LF		
0162	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	30 EA		
0163	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	94,413 LF		
0164	4775000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (III)	1,080 LF		
0165	4780000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (8") (IV)	2,400 LF		
0166	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	299,601 LF		
0167	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	14,900 LF		
0168	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	33 EA		
0169	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	700 LF		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0170	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	1,400	LF	
0171	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	3	EA	
0172	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	2,150	EA	
0173	5000000000-E	1401	**** HIGH MOUNT STANDARD (60')	7	EA	
0174	5005000000-E	1401	80' HIGH MOUNT STANDARD	6	EA	
0175	5010000000-E	1401	100' HIGH MOUNT STANDARD	3	EA	
0176	5015000000-E	1401	120' HIGH MOUNT STANDARD	3	EA	
0177	5020000000-N	1401	PORTABLE DRIVE UNIT	1	EA	
0178	5025000000-E	1402	HIGH MOUNT FOUNDATIONS	96	CY	
0179	5030000000-N	1403	HIGH MOUNT LUMINAIRES ***** (400W HPS)	76	EA	
0180	5030000000-N	1403	HIGH MOUNT LUMINAIRES ***** (750W HPS)	42	EA	
0181	5120000000-N	1407	ELECTRIC SERVICE POLE **** ***** (30' CLASS 4)	1	EA	
0182	5125000000-E	1407	ELECTRIC SERVICE LATERAL ***** (3 #1/0 USE IN 2"C)	300	LF	
0183	5145000000-N	1408	LIGHT CONTROL EQUIPMENT, TYPE RW ***** (240/480 V, 150A)	3	EA	
0184	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (2")	790	LF	
0185	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (3")	115	LF	

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0186	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (2")	650	LF	
0187	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (3")	175	LF	
0188	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (4")	515	LF	
0189	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (6")	35	LF	
0190	5170000000-E	1410	** #8 W/G FEEDER CIRCUIT (2)	1,282	LF	
0191	5175000000-E	1410	** #6 W/G FEEDER CIRCUIT (2)	280	LF	
0192	5180000000-E	1410	** #4 W/G FEEDER CIRCUIT (2)	1,158	LF	
0193	5185000000-E	1410	** #2 W/G FEEDER CIRCUIT (2)	246	LF	
0194	5205000000-E	1410	** #8 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	5,550	LF	
0195	5210000000-E	1410	** #6 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	1,263	LF	
0196	5215000000-E	1410	** #4 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	4,910	LF	
0197	5220000000-E	1410	** #2 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	571	LF	
0198	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC18)	33	EA	
0199	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC36)	7	EA	

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0200	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0201	6000000000-E	1605	TEMPORARY SILT FENCE	45,000 LF		
0202	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	6,750 TON		
0203	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	4,150 TON		
0204	6012000000-E	1610	SEDIMENT CONTROL STONE	6,300 TON		
0205	6015000000-E	1615	TEMPORARY MULCHING	166 ACR		
0206	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	3,400 LB		
0207	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	13.5 TON		
0208	6024000000-E	1622	TEMPORARY SLOPE DRAINS	470 LF		
0209	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	6 EA		
0210	6029000000-E	SP	SAFETY FENCE	4,850 LF		
0211	6030000000-E	1630	SILT EXCAVATION	9,855 CY		
0212	6036000000-E	1631	MATTING FOR EROSION CONTROL	93,100 SY		
0213	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	125 SY		
0214	6042000000-E	1632	1/4" HARDWARE CLOTH	10,500 LF		
0215	6071010000-E	SP	WATTLE	5,450 LF		
0216	6071020000-E	SP	POLYACRYLAMIDE (PAM)	1,335 LB		
0217	6071030000-E	SP	COIR FIBER BAFFLES	875 LF		
0218	6084000000-E	1660	SEEDING & MULCHING	93 ACR		
0219	6087000000-E	1660	MOWING	102 ACR		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0220	6090000000-E	1661	SEED FOR REPAIR SEEDING	1,300 LB		
0221	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	3.25 TON		
0222	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	2,325 LB		
0223	6108000000-E	1665	FERTILIZER TOPDRESSING	69.25 TON		
0224	6114500000-N	SP	SPECIALIZED HAND MOWING	125 MHR		
0225	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27 EA		
0945/May14/Q1873730.566/D787320360000/E225			Total Amount Of Bid For Entire Project :			

Contract No **C202472**

County (ies): **Randolph**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General