

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (14+20.00)	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (21+37.00)	Lump Sum	L.S.	
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (25+45.00)	Lump Sum	L.S.	
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0057000000-E	226	UNDERCUT EXCAVATION	900 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	10 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	6,200 SY		
0010	0199000000-E	SP	TEMPORARY SHORING	165 SF		
0011	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	900 CY		
0012	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	530 SY		
0013	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	160 TON		
0014	0335200000-E	SP	15" DRAINAGE PIPE	52 LF		
0015	0986000000-E	SP	GENERIC PIPE ITEM 18" SIDE DRAIN PIPE	20 LF		
0016	0995000000-E	340	PIPE REMOVAL	24 LF		
0017	1121000000-E	520	AGGREGATE BASE COURSE	2,350 TON		
0018	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1275000000-E	600	PRIME COAT	1,729 GAL		
0020	1330000000-E	607	INCIDENTAL MILLING	50 SY		
0021	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,260 TON		
0022	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	740 TON		
0023	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,800 TON		
0024	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	200 TON		
0025	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0026	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0027	2556000000-E	846	SHOULDER BERM GUTTER	220 LF		
0028	3030000000-E	862	STEEL BM GUARDRAIL	1,550 LF		
0029	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
0030	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0031	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0032	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	9 EA		
0033	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	12 EA		
0034	3360000000-E	863	REMOVE EXISTING GUARDRAIL	2,000 LF		
0035	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	1,512.5 LF		
0036	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	12 EA		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	8 EA		
0038	3649000000-E	876	RIP RAP, CLASS B	5 TON		
0039	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,515 SY		
0040	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0041	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	42 LF		
0042	4102000000-N	904	SIGN ERECTION, TYPE E	3 EA		
0043	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	8 EA		
0044	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	2 EA		
0045	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	148 SF		
0046	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0047	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	36 SF		
0048	4430000000-N	1130	DRUMS	50 EA		
0049	4435000000-N	1135	CONES	50 EA		
0050	4445000000-E	1145	BARRICADES (TYPE III)	50 LF		
0051	4450000000-N	1150	FLAGGER	528 HR		
0052	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4 EA		
0053	4480000000-N	1165	TMIA	1 EA		
0054	4485000000-E	1170	PORTABLE CONCRETE BARRIER	700 LF		
0055	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	80 LF		
0056	4516000000-N	1180	SKINNY DRUM	50 EA		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	162	EA	
0058	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,558	LF	
0059	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3,558	LF	
0060	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	1,284	LF	
0061	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	38,252	LF	
0062	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	3,200	LF	
0063	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	26	EA	
0064	5325800000-E	1510	8" WATER LINE	1,495	LF	
0065	5326000000-E	1510	10" WATER LINE	550	LF	
0066	5546000000-E	1515	8" VALVE	2	EA	
0067	5589200000-E	1515	2" AIR RELEASE VALVE	1	EA	
0068	5801000000-E	1530	ABANDON 8" UTILITY PIPE	2,121	LF	
0069	5871600000-E	1550	TRENCHLESS INSTALLATION OF 10" IN SOIL	550	LF	
0070	6000000000-E	1605	TEMPORARY SILT FENCE	14,000	LF	
0071	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	675	TON	
0072	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	725	TON	
0073	6012000000-E	1610	SEDIMENT CONTROL STONE	550	TON	
0074	6015000000-E	1615	TEMPORARY MULCHING	10	ACR	

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	250 LB		
0076	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2 TON		
0077	6024000000-E	1622	TEMPORARY SLOPE DRAINS	1,350 LF		
0078	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	12 EA		
0079	6029000000-E	SP	SAFETY FENCE	6,000 LF		
0080	6030000000-E	1630	SILT EXCAVATION	585 CY		
0081	6036000000-E	1631	MATTING FOR EROSION CONTROL	9,000 SY		
0082	6037000000-E	SP	COIR FIBER MAT	10 SY		
0083	6042000000-E	1632	1/4" HARDWARE CLOTH	1,150 LF		
0084	6071010000-E	SP	WATTLE	600 LF		
0085	6071020000-E	SP	POLYACRYLAMIDE (PAM)	175 LB		
0086	6071030000-E	SP	COIR FIBER BAFFLES	1,150 LF		
0087	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0088	6084000000-E	1660	SEEDING & MULCHING	12 ACR		
0089	6087000000-E	1660	MOWING	6 ACR		
0090	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0091	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0092	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	225 LB		
0093	6108000000-E	1665	FERTILIZER TOPDRESSING	6.75 TON		
0094	6114500000-N	SP	SPECIALIZED HAND MOWING	20 MHR		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0095	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	15 EA		
0096	6129000000-E	1670	WETLAND REFORESTATION	4.6 ACR		
0097	6135000000-E	SP	GENERIC EROSION CONTROL ITEM DISKING	4.6 ACR		
0098	6135000000-E	SP	GENERIC EROSION CONTROL ITEM RIPPING	4.6 ACR		
STRUCTURE ITEMS						
0099	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (14+20.00-L-)	Lump Sum	L.S.	
0100	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (21+37.00-L-)	Lump Sum	L.S.	
0101	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (25+45.00-L-)	Lump Sum	L.S.	
0102	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+20.00-L-)	Lump Sum	L.S.	
0103	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (21+37.00-L-)	Lump Sum	L.S.	
0104	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (25+45.00-L-)	Lump Sum	L.S.	
0105	8112730000-N	SP	PDA TESTING	2 EA		
0106	8112740000-N	SP	PDA ASSISTANCE	2 EA		
0107	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (14+20.00-L-)	Lump Sum	L.S.	

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0108	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (21+37.00-L-)	Lump Sum	L.S.	
0109	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (25+45.00-L-)	Lump Sum	L.S.	
0110	8156000000-E	SP	CONCRETE WEARING SURFACE	11,160 SF		
0111	8161000000-E	420	GROOVING BRIDGE FLOORS	14,893 SF		
0112	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	135.8 CY		
0113	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+20.00-L-)	Lump Sum	L.S.	
0114	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (21+37.00-L-)	Lump Sum	L.S.	
0115	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (25+45.00-L-)	Lump Sum	L.S.	
0116	8217000000-E	425	REINFORCING STEEL (BRIDGE)	22,332 LB		
0117	8364000000-E	SP	HP12X53 STEEL PILES	1,750 LF		
0118	8365000000-E	SP	HP12X53 GALVANIZED STEEL PILES	1,640 LF		
0119	8384200000-E	SP	HP14X73 GALVANIZED STEEL PILES	550 LF		
0120	8393000000-N	SP	PILE REDRIVES	39 EA		
0121	8503000000-E	460	CONCRETE BARRIER RAIL	629.23 LF		
0122	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,270 TON		
0123	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,410 SY		
0124	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0125	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0126	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	4,078.48 LF		

0954/May12/Q177358.81/D609563280000/E126

Total Amount Of Bid For Entire Project :

Contract No **C202549**

County (ies): **Robeson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General