

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (13 + 15.00)	Lump Sum	L.S.	
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (15 + 47.00)	Lump Sum	L.S.	
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	2 ACR		
0007	0057000000-E	226	UNDERCUT EXCAVATION	400 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	600 SY		
0009	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	600 CY		
0010	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	30 SY		
0011	0330000000-E	SP	GENERIC DRAINAGE ITEM FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
0012	0335200000-E	SP	15" DRAINAGE PIPE	76 LF		
0013	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	280 TON		
0015	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	462 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	50 TON		
0017	2000000000-N	806	RIGHT OF WAY MARKERS	12 EA		

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2022000000-E	815	SUBDRAIN EXCAVATION	67.2 CY		
001E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	33.6 CY		
002C	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0021	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
002E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0024	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
002E	2556000000-E	846	SHOULDER BERM GUTTER	165 LF		
0027	3030000000-E	862	STEEL BM GUARDRAIL	475 LF		
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
002E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
003C	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	8 EA		
0031	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	7 EA		
003E	3649000000-E	876	RIP RAP, CLASS B	24 TON		
003E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	964 SY		
0034	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
003E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	4 EA		

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	2 EA		
0037	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	819 SF		
003E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	163 SF		
003E	4445000000-E	1145	BARRICADES (TYPE III)	160 LF		
004C	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	8,616 LF		
0041	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	10 EA		
0042	6000000000-E	1605	TEMPORARY SILT FENCE	1,200 LF		
004E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	450 TON		
0044	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	80 TON		
004E	6012000000-E	1610	SEDIMENT CONTROL STONE	85 TON		
004E	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0047	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
004E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	400 LF		
005C	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	8 EA		
0051	6029000000-E	SP	SAFETY FENCE	1,750 LF		
0052	6030000000-E	1630	SILT EXCAVATION	145 CY		
005E	6036000000-E	1631	MATTING FOR EROSION CONTROL	3,550 SY		

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6042000000-E	1632	1/4" HARDWARE CLOTH	350	LF	
005E	6071010000-E	SP	WATTLE	40	LF	
005E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	10	LB	
0057	6084000000-E	1660	SEEDING & MULCHING	8	ACR	
005E	6087000000-E	1660	MOWING	1	ACR	
005E	6090000000-E	1661	SEED FOR REPAIR SEEDING	100	LB	
006C	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5	TON	
0061	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100	LB	
0062	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25	TON	
006E	6114500000-N	SP	SPECIALIZED HAND MOWING	20	MHR	
0064	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	24	EA	
006E	6123000000-E	1670	REFORESTATION	0.2	ACR	

STRUCTURE ITEMS

006E	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15 + 47.00-L-)	Lump Sum	L.S.	
0067	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13 + 15.00-L-)	Lump Sum	L.S.	
006E	8112730000-N	SP	PDA TESTING	2	EA	
006E	8112740000-N	SP	PDA ASSISTANCE	2	EA	
007C	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (13 + 15.00-L-)	Lump Sum	L.S.	

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (15 + 47.00-L-)	Lump Sum	L.S.	
0072	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	84.2 CY		
0073	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (13 + 15.00-L-)	Lump Sum	L.S.	
0074	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15 + 47.00-L-)	Lump Sum	L.S.	
007E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	14,376 LB		
007F	8364000000-E	SP	HP12X53 STEEL PILES	955 LF		
0077	8365000000-E	SP	HP12X53 GALVANIZED STEEL PILES	1,530 LF		
007E	8393000000-N	SP	PILE REDRIVES	37 EA		
007E	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	595.25 LF		
008C	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	937 TON		
0081	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,032 SY		
0082	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0083	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	2,971.25 LF		

1139/Apr29/Q45339.45/D381967700000/E83

Total Amount Of Bid For Entire Project :

Contract No **C202236**

County (ies): **Wilson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General