

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	175	LF	
0003	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	4	EA	
0004	2738000000-E	SP	GENERIC PAVING ITEM 4" CONCRETE SIDEWALK	250	SY	
0005	2761000000-E	848	GENERIC PAVING ITEM 9" CONCRETE BORDER	105	SY	
0006	3575000000-E	SP	GENERIC FENCING ITEM TEMPORARY 72" CHAIN LINK FENCE	800	LF	
0007	3578000000-N	SP	GENERIC FENCING ITEM TEMPORARY DOUBLE GATES, 72" HIGH, 8' WIDE, 16' OPENING	2	EA	
0008	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	75	SY	
0009	6000000000-E	1605	TEMPORARY SILT FENCE	500	LF	
0010	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	40	TON	
0011	6012000000-E	1610	SEDIMENT CONTROL STONE	20	TON	
0012	6015000000-E	1615	TEMPORARY MULCHING	0.25	ACR	
0013	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	15	LB	
0014	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.05	TON	
0015	6036000000-E	1631	MATTING FOR EROSION CONTROL	100	SY	
0016	6042000000-E	1632	1/4" HARDWARE CLOTH	100	LF	
0017	6084000000-E	1660	SEEDING & MULCHING	4	ACR	
0018	6087000000-E	1660	MOWING	0.5	ACR	

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	6090000000-E	1661	SEED FOR REPAIR SEEDING	10 LB		
0020	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.05 TON		
0021	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	10 LB		
0022	6108000000-E	1665	FERTILIZER TOPDRESSING	0.1 TON		
0023	6114500000-N	SP	SPECIALIZED HAND MOWING	15 MHR		
0024	6141000000-E	SP	GENERIC EROSION CONTROL ITEM SODDING	340 SY		
0025	6655000000-E	1670	WATER FOR PLANTING	11 M/G		
0026	6665000000-E	1670	POSTEMERGENT HERBICIDAL TREAT- MENT FOR PLANT BEDS	1,625 SY		
0027	6670000000-E	1670	PREEMERGENT HERBICIDAL TREAT- MENT FOR PLANT BEDS	1,625 SY		
0028	6674000000-N	SP	GENERIC PLANTING ITEM (LS) LANDSCAPE PLANTING (EBL)	Lump Sum	L.S.	
0029	6674000000-N	SP	GENERIC PLANTING ITEM (LS) LANDSCAPE PLANTING (WBL)	Lump Sum	L.S.	
0030	6677000000-E	SP	GENERIC PLANTING ITEM RIVERSTONE	6 TON		
0031	6890000000-E	SP	CONCRETE STEPS	13 CY		
0032	6895000000-E	SP	HANDRAIL ON STEPS	52 LF		
0033	6900000000-E	SP	TOPSOIL	120 CY		
0034	6915000000-N	SP	OUTDOOR PARK STOVE	2 EA		
0035	6970000000-N	SP	GENERIC REST AREA ITEM 1" GATE VALVE AND BOX	1 EA		
0036	6970000000-N	SP	GENERIC REST AREA ITEM 3" GATE VALVE AND BOX	2 EA		

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	6970000000-N	SP	GENERIC REST AREA ITEM 4" SANITARY SEWER CLEAN-OUT	1 EA		
003E	6970000000-N	SP	GENERIC REST AREA ITEM 6' PARK BENCH	4 EA		
003E	6970000000-N	SP	GENERIC REST AREA ITEM BOULDER	12 EA		
004C	6970000000-N	SP	GENERIC REST AREA ITEM CONNECTION TO SEWER MANHOLE/ SEWER LINE	1 EA		
0041	6970000000-N	SP	GENERIC REST AREA ITEM FLAGPOLE	2 EA		
0042	6970000000-N	SP	GENERIC REST AREA ITEM RELOCATED PICNIC SHELTER	1 EA		
004E	6970000000-N	SP	GENERIC REST AREA ITEM STEPPING STONE	12 EA		
0044	6970000000-N	SP	GENERIC REST AREA ITEM WASTE CONTAINER	11 EA		
004E	6975000000-N	SP	GENERIC REST AREA ITEM ELECTRICAL INSTALLATION REST AREA SERVICE BLDG EBL/WBL (NEW BLDGS)	Lump Sum	L.S.	
004E	6975000000-N	SP	GENERIC REST AREA ITEM ELECTRICAL INSTALLATION VEND- ING BUILDING EBL (EXISTING BLDG)	Lump Sum	L.S.	
0047	6975000000-N	SP	GENERIC REST AREA ITEM ELECTRICAL INSTALLATION VEND- ING BUILDING WBL (NEW SMALL BLDG)	Lump Sum	L.S.	
004E	6975000000-N	SP	GENERIC REST AREA ITEM GENERAL CONSTRUCTION REST AREA SERVICE BLDG EBL/WBL (NEW BL DGS)	Lump Sum	L.S.	
004E	6975000000-N	SP	GENERIC REST AREA ITEM GENERAL CONSTRUCTION VENDING BUILDING EBL (EXISTING BLDG)	Lump Sum	L.S.	

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005C	6975000000-N	SP	GENERIC REST AREA ITEM GENERAL CONSTRUCTION VENDING BUILDING WBL (NEW SMALL BLDG)	Lump Sum	L.S.	
0051	6975000000-N	SP	GENERIC REST AREA ITEM HVAC INSTALLATION REST AREA SERVICE BLDG EBL/WBL (NEW BLD GS)	Lump Sum	L.S.	
0052	6975000000-N	SP	GENERIC REST AREA ITEM HVAC INSTALLATION VENDING BUILDING EBL (EXISTING BLDG)	Lump Sum	L.S.	
0053	6975000000-N	SP	GENERIC REST AREA ITEM HVAC INSTALLATION VENDING BUILDING WBL (NEW SMALL BLDG)	Lump Sum	L.S.	
0054	6975000000-N	SP	GENERIC REST AREA ITEM LANDSCAPE & SITE GRADING EBL	Lump Sum	L.S.	
005E	6975000000-N	SP	GENERIC REST AREA ITEM LANDSCAPE & SITE GRADING WBL	Lump Sum	L.S.	
005E	6975000000-N	SP	GENERIC REST AREA ITEM LANDSCAPE IRRIGATION - EBL	Lump Sum	L.S.	
0057	6975000000-N	SP	GENERIC REST AREA ITEM LANDSCAPE IRRIGATION - WBL	Lump Sum	L.S.	
005E	6975000000-N	SP	GENERIC REST AREA ITEM PLUMBING INSTALLATION REST AREA SERVICE BLDG EBL/WBL (NEW BLDGS)	Lump Sum	L.S.	
005E	6975000000-N	SP	GENERIC REST AREA ITEM PLUMBING INSTALLATION VENDING BUILDING EBL (EXISTING BLDG)	Lump Sum	L.S.	
006C	6975000000-N	SP	GENERIC REST AREA ITEM PLUMBING INSTALLATION VENDING BUILDING WBL (NEW SMALL BLDG)	Lump Sum	L.S.	
0061	6975000000-N	SP	GENERIC REST AREA ITEM PONDLESS WATERFALL	Lump Sum	L.S.	
0062	6975000000-N	SP	GENERIC REST AREA ITEM POWERWASH EXISTING SIDEWALKS - EBL	Lump Sum	L.S.	

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0063	6975000000-N	SP	GENERIC REST AREA ITEM POWERWASH EXISTING SIDEWALKS - WBL	Lump Sum	L.S.	
0064	6975000000-N	SP	GENERIC REST AREA ITEM SITE DEMOLITION EBL	Lump Sum	L.S.	
0065	6975000000-N	SP	GENERIC REST AREA ITEM SITE DEMOLITION WBL	Lump Sum	L.S.	
0066	6975000000-N	SP	GENERIC REST AREA ITEM STORMWATER COLLECTION SYSTEM - EBL	Lump Sum	L.S.	
0067	6975000000-N	SP	GENERIC REST AREA ITEM STORMWATER COLLECTION SYSTEM - WBL	Lump Sum	L.S.	
0068	6975000000-N	SP	GENERIC REST AREA ITEM STORMWATER DRAINAGE SYSTEM - EBL	Lump Sum	L.S.	
0069	6975000000-N	SP	GENERIC REST AREA ITEM STORMWATER DRAINAGE SYSTEM - WBL	Lump Sum	L.S.	
0070	6980000000-E	SP	GENERIC REST AREA ITEM 1" PVC WATER PIPE (SCH 80)	50 LF		
0071	6980000000-E	SP	GENERIC REST AREA ITEM 3" PVC GRAVITY SEWER (SCH80)	100 LF		
0072	6980000000-E	SP	GENERIC REST AREA ITEM 3" PVC SLEEVE	100 LF		
0073	6980000000-E	SP	GENERIC REST AREA ITEM 3" PVC WATER PIPE (SCH 80)	370 LF		
0074	6980000000-E	SP	GENERIC REST AREA ITEM 6" PVC GRAVITY SEWER (SCH80)	175 LF		
0075	6980000000-E	SP	GENERIC REST AREA ITEM ELECTRIC LINE INSTALL/REPAIR	250 LF		
0076	6980000000-E	SP	GENERIC REST AREA ITEM LANDSCAPE METAL EDGING	900 LF		

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0077	6980000000-E	SP	GENERIC REST AREA ITEM ORNAMENTAL WELDED WIRE FENCE	300 LF		
0078	6980000000-E	SP	GENERIC REST AREA ITEM PHONE LINE INSTALL/REPAIR	250 LF		
0079	6980000000-E	SP	GENERIC REST AREA ITEM PVC WATER PIPE SCH. 80 REPAIR	25 LF		
0080	6980000000-E	SP	GENERIC REST AREA ITEM SPLIT RAIL FENCE RELOCATION	200 LF		
0081	6980000000-E	SP	GENERIC REST AREA ITEM TREE PROTECTION FENCE	650 LF		
0082	6982000000-E	SP	GENERIC REST AREA ITEM PERMEABLE PAVERS	3,800 SF		
0083	6982000000-E	SP	GENERIC REST AREA ITEM SEGMENTED RETAINING WALL	560 SF		
0084	6985000000-E	SP	GENERIC REST AREA ITEM MULCH FOR PLANTING	227 CY		

1621/Jul09/Q14051.95/D53482460000/E84

Total Amount Of Bid For Entire Project :

Contract No **C202206**

County (ies): **McDowell**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General