

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	32 CY		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	1.6 SMI		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	25,323 SY		
0005	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1-1/2" TO 3")	121,543 SY		
0006	1330000000-E	607	INCIDENTAL MILLING	167 SY		
0007	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	13,137 TON		
0008	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	789 TON		
0009	1704000000-E	SP	PATCHING EXISTING PAVEMENT	5,200 TON		
0010	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	2 EA		
0011	2830000000-N	858	ADJUSTMENT OF MANHOLES	224 EA		
0012	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	28 EA		
0013	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
0014	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	33,722 LF		
0015	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	89,748 LF		
0016	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,155 LF		
0017	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	5,234 LF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	300 LF		
001E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	2,404 LF		
002C	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	92 EA		
0021	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	258 EA		
0022	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	113,973 LF		
0023	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	6,720 LF		
0024	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	300 LF		
002E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	2,551 LF		
002E	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	76 EA		
0027	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	189 EA		
002E	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	6,168 LF		
002E	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	260 LF		
003C	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	102 LF		
0031	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	23 EA		
0032	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	1,169 EA		
003E	6084000000-E	1660	SEEDING & MULCHING	0.96 ACR		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	10,897 LF		

1118/Aug11/Q441790.56/D127425100000/E34

Total Amount Of Bid For Entire Project :

Contract No **C202613**

County (ies): **Durham**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General