

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (56 + 12.00 -L-)	Lump Sum	L.S.	
0004	0036000000-E	225	UNDERCUT EXCAVATION	30,250 CY		
0005	0038000000-E	SP	SHALLOW UNDERCUT	150 CY		
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0008	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	250 TON		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	5,205 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	30,650 SY		
0011	0234000000-E	SP	GENERIC GRADING ITEM BORROW EXCAVATION	46,950 CY		
0012	0241000000-E	SP	GENERIC GRADING ITEM PERMANENT TURF REINFORCEMENT MAT	380 SY		
0013	0241000000-E	SP	GENERIC GRADING ITEM PRIMARY GEOGRID REINFORCEMENT	1,420 SY		
0014	0241000000-E	SP	GENERIC GRADING ITEM SECONDARY GEOGRID REINFORCE- MENT	520 SY		
0015	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	310 TON		
0016	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	960 SY		
0017	0335200000-E	SP	15" DRAINAGE PIPE	464 LF		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0335300000-E	SP	18" DRAINAGE PIPE	240 LF		
001E	0335400000-E	SP	24" DRAINAGE PIPE	8 LF		
002C	0335850000-E	SP	*** DRAINAGE PIPE ELBOWS (15")	4 EA		
0021	0335850000-E	SP	*** DRAINAGE PIPE ELBOWS (18")	2 EA		
0022	0343000000-E	SP	15" SIDE DRAIN PIPE	180 LF		
0023	0344000000-E	SP	18" SIDE DRAIN PIPE	128 LF		
0024	0448200000-E	SP	15" RC PIPE CULVERTS, CLASS IV	1,764 LF		
002E	0448400000-E	SP	24" RC PIPE CULVERTS, CLASS IV	96 LF		
002E	0986000000-E	SP	GENERIC PIPE ITEM 6" HDPE PIPE	12 LF		
0027	0986000000-E	SP	GENERIC PIPE ITEM 6" PERFORATED HDPE PIPE	92 LF		
002E	0992000000-E	SP	GENERIC PIPE ITEM 6" HDPE CAPS	2 EA		
002E	0992000000-E	SP	GENERIC PIPE ITEM 6" HDPE ELBOWS	4 EA		
003C	0995000000-E	340	PIPE REMOVAL	523 LF		
0031	1121000000-E	520	AGGREGATE BASE COURSE	1,660 TON		
0032	1220000000-E	545	INCIDENTAL STONE BASE	1,000 TON		
003E	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	15,335 TON		
0034	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	8,310 TON		
003E	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	6,100 TON		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,050 TON		
0037	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	366 TON		
003E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
003E	2022000000-E	SP	SUBDRAIN EXCAVATION	1,092 CY		
004C	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	546 CY		
0041	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	3,250 LF		
0042	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	7 EA		
004E	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	42 LF		
0044	2253000000-E	840	PIPE COLLARS	1.3 CY		
004E	2275000000-E	SP	FLOWABLE FILL	3.5 CY		
004E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	30 EA		
0047	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	6.6 LF		
004E	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	8 EA		
004E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	5 EA		
005C	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0051	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	2 EA		
0052	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	3 EA		
005E	2396000000-N	840	FRAME WITH COVER, STD 840.54	2 EA		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	14 EA		
005E	2473000000-N	SP	GENERIC DRAINAGE ITEM NARROW DROP INLET FRAME AND GRATE	4 EA		
005E	2474000000-N	SP	GENERIC DRAINAGE ITEM DRY DETENTION BASIN STA 55 + 43.3	Lump Sum	L.S.	
0057	2474000000-N	SP	GENERIC DRAINAGE ITEM DRY DETENTION BASIN STA 57 + 34.6	Lump Sum	L.S.	
005E	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	6,000 LF		
005E	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	790 LF		
006C	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	475 LF		
0061	2612000000-E	848	6" CONCRETE DRIVEWAY	264 SY		
0062	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	70 SY		
0063	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	440 SY		
0064	2739000000-E	852	GENERIC PAVING ITEM 5" MONOLITHIC CONCRETE ISLAND (KEYED IN-MODIFIED)	280 SY		
006E	2950000000-N	SP	CONVERT EXISTING JUNCTION BOX TO DROP INLET	2 EA		
006E	3030000000-E	862	STEEL BM GUARDRAIL	425 LF		
0067	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
006E	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
006E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	3 EA		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007C	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2	EA	
0071	3628000000-E	876	RIP RAP, CLASS I	105	TON	
0072	3649000000-E	876	RIP RAP, CLASS B	13	TON	
0073	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	192	SY	
0074	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1	EA	
007E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	354	SF	
007E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	192	SF	
0077	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	100	SF	
007E	4430000000-N	1130	DRUMS	175	EA	
007E	4455000000-N	1150	FLAGGER	540	MD	
008C	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2	EA	
0081	4485000000-E	1170	PORTABLE CONCRETE BARRIER	500	LF	
0082	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	113	EA	
0083	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	9,560	LF	
0084	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	5,474	LF	
008E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	76	LF	
008E	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	8	EA	
0087	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	27	EA	

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	1,266	LF	
008E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	67,025	LF	
009C	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	436	LF	
0091	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	80	LF	
0092	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	10	EA	
0093	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	805	LF	
0094	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	1,038	LF	
009E	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	9	EA	
009E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	261	EA	
0097	5325600000-E	1510	6" WATER LINE	62	LF	
009E	5326200000-E	1510	12" WATER LINE	4,539	LF	
009E	5538000000-E	1515	4" VALVE	1	EA	
010C	5540000000-E	1515	6" VALVE	2	EA	
0101	5546000000-E	1515	8" VALVE	1	EA	
0102	5552000000-E	1515	10" VALVE	1	EA	
0103	5558000000-E	1515	12" VALVE	8	EA	
0104	5571800000-E	1515	8" TAPPING VALVE	1	EA	
010E	5572200000-E	1515	12" TAPPING VALVE	1	EA	

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010E	5588000000-E	1515	** AIR RELEASE VALVE (10")	3 EA		
0107	5666000000-E	1515	FIRE HYDRANT	3 EA		
010E	5672000000-N	1515	RELOCATE FIRE HYDRANT	1 EA		
010E	5709300000-E	1520	6" FORCE MAIN SEWER	98 LF		
011C	5709500000-E	1520	10" FORCE MAIN SEWER	4,651 LF		
0111	5776000000-E	1525	5' DIA UTILITY MANHOLE	4 EA		
0112	5798000000-E	1530	ABANDON *** UTILITY PIPE (4")	5,090 LF		
0113	5800000000-E	1530	ABANDON 6" UTILITY PIPE	3,988 LF		
0114	5801000000-E	1530	ABANDON 8" UTILITY PIPE	30 LF		
011E	5802000000-E	1530	ABANDON 10" UTILITY PIPE	4,675 LF		
011E	5804000000-E	1530	ABANDON 12" UTILITY PIPE	4,584 LF		
0117	5828000000-N	1530	REMOVE UTILITY MANHOLE	2 EA		
011E	5871400000-E	1550	TRENCHLESS INSTALLATION OF 6" IN SOIL	400 LF		
011E	5871700000-E	1550	TRENCHLESS INSTALLATION OF 12" IN SOIL	400 LF		
012C	5871800000-E	1550	TRENCHLESS INSTALLATION OF 14" IN SOIL	400 LF		
0121	5879200000-E	SP	2" GAS LINE	106 LF		
0122	5879400000-E	SP	4" GAS LINE	137 LF		
0123	5879600000-E	SP	6" GAS LINE	4,931 LF		
0124	5880400000-E	SP	4" GAS VALVE	1 EA		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
012E	5880600000-E	SP	6" GAS VALVE	1	EA	
012E	5882000000-N	SP	GENERIC UTILITY ITEM 6" SEWER FORCE MAIN CHECK VALVE	1	EA	
0127	5882000000-N	SP	GENERIC UTILITY ITEM RECONNECT 3/4" GAS SERVICE	9	EA	
012E	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE EXISTING WATER METER	17	EA	
012E	6000000000-E	1605	TEMPORARY SILT FENCE	3,480	LF	
013C	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	50	TON	
0131	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	190	TON	
0132	6012000000-E	1610	SEDIMENT CONTROL STONE	190	TON	
013E	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	
0134	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
013E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25	TON	
013E	6029000000-E	SP	SAFETY FENCE	800	LF	
0137	6030000000-E	1630	SILT EXCAVATION	645	CY	
013E	6036000000-E	1631	MATTING FOR EROSION CONTROL	15,890	SY	
013E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,470	SY	
014C	6042000000-E	1632	1/4" HARDWARE CLOTH	580	LF	
0141	6045000000-E	SP	*** TEMPORARY PIPE (18")	160	LF	
0142	6070000000-N	SP	SPECIAL STILLING BASINS	1	EA	

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0143	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0144	6087000000-E	1660	MOWING	1 ACR		
0145	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0146	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0147	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0148	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0149	6111000000-E	SP	IMPERVIOUS DIKE	100 LF		
015C	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0151	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
0152	6123000000-E	1670	REFORESTATION	0.5 ACR		
0153	6126000000-E	SP	STREAMBANK REFORESTATION	0.5 ACR		
STRUCTURE ITEMS						
0154	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (56 + 12.00 -L-)	Lump Sum	L.S.	
015E	8112730000-N	SP	PDA TESTING	2 EA		
015E	8112740000-N	SP	PDA ASSISTANCE	2 EA		
0157	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	3,870 CY		
015E	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	15,610 SF		
015E	8161000000-E	420	GROOVING BRIDGE FLOORS	10,228 SF		
016C	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	245.2 CY		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0161	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (56 + 12.00 -L-)	Lump Sum	L.S.	
0162	8217000000-E	425	REINFORCING STEEL (BRIDGE)	35,595 LB		
0163	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	1,760 LF		
0164	8364000000-E	SP	HP12X53 STEEL PILES	3,641 LF		
0165	8384200000-E	SP	HP14X73 GALVANIZED STEEL PILES	3,529 LF		
0166	8393000000-N	SP	PILE REDRIVES	41 EA		
0167	8475000000-E	460	TWO BAR METAL RAIL	341.98 LF		
0168	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 3'-2 3/4")	358.32 LF		
0169	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,575 TON		
0170	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,755 SY		
0171	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0172	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0173	8741000000-N	SP	STRUCTURE DRAINAGE SYSTEM AT STA***** (56 + 12.00 -L-)	Lump Sum	L.S.	

1135/Oct04/Q393060.15/D721796070000/E173

Total Amount Of Bid For Entire Project :

Contract No **C202636**

County (ies): **Pitt**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General