

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	3 ACR		
0005	0015000000-N	205	SEALING ABANDONED WELLS	16 EA		
0006	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (280 + 13.00 -L-LT)	Lump Sum	L.S.	
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (280 + 13.00 -L-RT)	Lump Sum	L.S.	
0008	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (298 + 34.21 -L-LT)	Lump Sum	L.S.	
0009	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (298 + 34.21 -L-RT)	Lump Sum	L.S.	
0010	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (560 + 00.35 -L-C/L)	Lump Sum	L.S.	
0011	0036000000-E	225	UNDERCUT EXCAVATION	12,500 CY		
0012	0038000000-E	SP	SHALLOW UNDERCUT	5,000 CY		
0013	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	10,000 TON		
0014	0134000000-E	240	DRAINAGE DITCH EXCAVATION	6,300 CY		
0015	0141000000-E	240	BERM DITCH CONSTRUCTION	710 LF		
0016	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	8,000 SY		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	12,000 SY		
001E	0192000000-N	260	PROOF ROLLING	60 HR		
001E	0195000000-E	SP	SELECT GRANULAR MATERIAL	7,000 CY		
002C	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	15,000 SY		
0021	0199000000-E	SP	TEMPORARY SHORING	1,910 SF		
0022	0223000000-E	SP	ROCK PLATING	250 SY		
0023	0318000000-E	SP	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	3,350 TON		
0024	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	10,550 SY		
002E	0987000000-E	310	GENERIC PIPE ITEM 12" CS PIPE CULVERTS, 0.064" THICK	24 LF		
002E	0987000000-E	310	GENERIC PIPE ITEM 15" CS PIPE CULVERTS, 0.064" THICK	4,936 LF		
0027	0987000000-E	310	GENERIC PIPE ITEM 15" SIDE DRAIN PIPE	1,440 LF		
002E	0987000000-E	310	GENERIC PIPE ITEM 18" CS PIPE CULVERTS, 0.064" THICK	448 LF		
002E	0987000000-E	310	GENERIC PIPE ITEM 18" SIDE DRAIN PIPE	188 LF		
003C	0987000000-E	310	GENERIC PIPE ITEM 24" RC PIPE CULVERTS, CLASS IV	184 LF		
0031	0987000000-E	310	GENERIC PIPE ITEM 30" CS PIPE CULVERTS, 0.079" THICK	168 LF		
0032	0987000000-E	310	GENERIC PIPE ITEM 36" CS PIPE CULVERTS, 0.079" THICK	48 LF		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0033	0987000000-E	310	GENERIC PIPE ITEM 36" RC PIPE CULVERTS, CLASS IV	212 LF		
0034	0987000000-E	310	GENERIC PIPE ITEM 42" CS PIPE CULVERTS, 0.109" THICK	36 LF		
0035	0987000000-E	310	GENERIC PIPE ITEM 72" CS PIPE CULVERTS, 0.138" THICK	136 LF		
0036	0988000000-E	310	GENERIC PIPE ITEM 15" CS PIPE ELBOWS, 0.064" THICK	16 EA		
0037	0988000000-E	310	GENERIC PIPE ITEM 18" CS PIPE ELBOWS, 0.064" THICK	10 EA		
0038	0988000000-E	310	GENERIC PIPE ITEM 30" CS PIPE ELBOWS, 0.079" THICK	4 EA		
0039	0988000000-E	310	GENERIC PIPE ITEM 36" CS PIPE ELBOWS, 0.079" THICK	2 EA		
004C	0988000000-E	310	GENERIC PIPE ITEM 72" CS PIPE ELBOWS, 0.138" THICK	2 EA		
0041	0995000000-E	340	PIPE REMOVAL	10,944 LF		
0042	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0043	1044000000-E	501	LIME TREATED SOIL (SLURRY METHOD)	100,000 SY		
0044	1066000000-E	501	LIME FOR LIME TREATED SOIL	1,000 TON		
004E	1110000000-E	510	STABILIZER AGGREGATE	15,000 TON		
0046	1176000000-E	542	SOIL CEMENT BASE	100,000 SY		
0047	1187000000-E	542	PORTLAND CEMENT FOR SOIL CE- MENT BASE	2,800 TON		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
004E	1209000000-E	543	ASPHALT CURING SEAL	30,000 GAL		
004E	1220000000-E	545	INCIDENTAL STONE BASE	2,285 TON		
005C	1275000000-E	600	PRIME COAT	5,000 GAL		
0051	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	55,000 SY		
0052	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 3")	625 SY		
0053	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,800 TON		
0054	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,700 TON		
005E	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	70,000 TON		
005E	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,200 TON		
0057	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	50,700 TON		
005E	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	4,200 TON		
005E	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	3,045 TON		
006C	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	800 TON		
0061	1881000000-E	SP	GENERIC PAVING ITEM MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	71,000 LF		
0062	2000000000-N	806	RIGHT OF WAY MARKERS	442 EA		
0063	2022000000-E	SP	SUBDRAIN EXCAVATION	672 CY		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0064	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	336 CY		
006E	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	2,000 LF		
006E	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	4 EA		
0067	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	24 LF		
006E	2143000000-E	818	BLOTTING SAND	30 TON		
006E	2209000000-E	838	ENDWALLS	6.1 CY		
007C	2253000000-E	840	PIPE COLLARS	5.184 CY		
0071	2264000000-E	840	PIPE PLUGS	0.594 CY		
0072	2275000000-E	SP	FLOWABLE FILL	95 CY		
007E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	239 EA		
0074	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	5.8 CY		
007E	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	203 LF		
007E	2354000000-N	840	FRAME WITH GRATE, STD 840.22	6 EA		
0077	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	7 EA		
007E	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	74 EA		
007E	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	123 EA		
008C	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	14 EA		
0081	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	7 EA		
0082	2396000000-N	840	FRAME WITH COVER, STD 840.54	19 EA		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0083	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	54 EA		
0084	2535000000-E	846	***X*** CONCRETE CURB (8" X 18")	2,150 LF		
0085	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	2,850 LF		
0086	2556000000-E	846	SHOULDER BERM GUTTER	1,200 LF		
0087	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	725 LF		
0088	2619000000-E	850	4" CONCRETE PAVED DITCH	99 SY		
0089	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	15,500 SY		
009C	2815000000-N	858	ADJUSTMENT OF DROP INLETS	6 EA		
0091	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	2 EA		
0092	3030000000-E	862	STEEL BM GUARDRAIL	13,000 LF		
0093	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	500 LF		
0094	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	10 EA		
009E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
009E	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	23 EA		
0097	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	26 EA		
009E	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	8 EA		
009E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	18 EA		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010C	3319000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-83	1	EA	
0101	3360000000-E	863	REMOVE EXISTING GUARDRAIL	2,750	LF	
0102	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	7,000	LF	
0103	3382000000-E	862	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)	50	LF	
0104	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (CAT-1)	1	EA	
010E	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	40	EA	
010E	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	50,000	LF	
0107	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	2,900	EA	
010E	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	1,250	EA	
010E	3595000000-E	869	RELAPPING GUARDRAIL	500	LF	
011C	3628000000-E	876	RIP RAP, CLASS I	1,070	TON	
0111	3649000000-E	876	RIP RAP, CLASS B	1,890	TON	
0112	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	26,860	SY	
0113	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	13	EA	
0114	4054000000-E	902	PLAIN CONCRETE SIGN FOUNDATIONS	1	CY	
011E	4066000000-E	903	SUPPORTS, SIMPLE STEEL BEAM	842	LB	
011E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	6,884	LF	
0117	4096000000-N	904	SIGN ERECTION, TYPE D	11	EA	

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
011E	4102000000-N	904	SIGN ERECTION, TYPE E	327	EA	
011E	4108000000-N	904	SIGN ERECTION, TYPE F	23	EA	
012C	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	3	EA	
0121	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	6	EA	
0122	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	128	EA	
0123	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	6	EA	
0124	4238000000-N	907	DISPOSAL OF SIGN, D, E OR F	1	EA	
012E	4360000000-N	SP	GENERIC SIGNING ITEM DISPOSAL OF FLASHER SYSTEM	3	EA	
012E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	4,173	SF	
0127	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	704	SF	
012E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	138	SF	
012E	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2	EA	
013C	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2	EA	
0131	4430000000-N	1130	DRUMS	750	EA	
0132	4435000000-N	1135	CONES	75	EA	
013E	4445000000-E	1145	BARRICADES (TYPE III)	1,400	LF	
0134	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	6	EA	
013E	4480000000-N	1165	TMIA	2	EA	

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0136	4485000000-E	1170	PORTABLE CONCRETE BARRIER	1,600 LF		
0137	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	850 LF		
013E	4510000000-N	SP	LAW ENFORCEMENT	160 HR		
0139	4516000000-N	1180	SKINNY DRUM	100 EA		
014C	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM FLAGGER	Lump Sum	L.S.	
0141	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	1,507 EA		
0142	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	148,300 LF		
0143	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	37,049 LF		
0144	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	146 LF		
014E	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	37,500 LF		
0146	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	420 LF		
0147	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	20 EA		
014E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	219 EA		
0149	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	2,151 LF		
015C	4780000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (8") (II)	50 LF		
0151	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	566,220 LF		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0152	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	6,000	LF	
0153	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,720	LF	
0154	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	126	EA	
015E	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	24,000	LF	
0156	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	400	LF	
0157	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	352	EA	
015E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	2,240	EA	
0159	4915000000-E	1264	7' U-CHANNEL POSTS	12	EA	
016C	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	12	EA	
0161	5325600000-E	1510	6" WATER LINE	395	LF	
0162	5325800000-E	1510	8" WATER LINE	775	LF	
0163	5326200000-E	1510	12" WATER LINE	2,234	LF	
0164	5327000000-E	1510	20" WATER LINE	2,535	LF	
016E	5540000000-E	1515	6" VALVE	4	EA	
016E	5546000000-E	1515	8" VALVE	6	EA	
0167	5558000000-E	1515	12" VALVE	1	EA	
016E	5559000000-E	1515	20" VALVE	2	EA	
016E	5571600000-E	1515	6" TAPPING VALVE	9	EA	
017C	5571800000-E	1515	8" TAPPING VALVE	2	EA	

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0171	5589100000-E	1515	1" AIR RELEASE VALVE	1 EA		
0172	5648000000-N	1515	RELOCATE WATER METER	52 EA		
0173	5649000000-N	1515	RECONNECT WATER METER	25 EA		
0174	5666000000-E	1515	FIRE HYDRANT	13 EA		
0175	5672000000-N	1515	RELOCATE FIRE HYDRANT	10 EA		
0176	5709200000-E	1520	4" FORCE MAIN SEWER	1,623 LF		
0177	5804000000-E	1530	ABANDON 12" UTILITY PIPE	2,160 LF		
0178	5812000000-E	1530	ABANDON 20" UTILITY PIPE	2,383 LF		
0179	5815000000-N	1530	REMOVE WATER METER	12 EA		
018C	5815500000-N	1530	REMOVE FIRE HYDRANT	1 EA		
0181	6000000000-E	1605	TEMPORARY SILT FENCE	20,000 LF		
0182	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	13,000 TON		
0183	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	21,000 TON		
0184	6012000000-E	1610	SEDIMENT CONTROL STONE	12,000 TON		
018E	6015000000-E	1615	TEMPORARY MULCHING	150 ACR		
0186	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	6,300 LB		
0187	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	27 TON		
018E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	6,000 LF		
0189	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	100 EA		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
019C	6029000000-E	SP	SAFETY FENCE	1,500 LF		
0191	6030000000-E	1630	SILT EXCAVATION	43,000 CY		
0192	6036000000-E	1631	MATTING FOR EROSION CONTROL	140,000 SY		
0193	6037000000-E	SP	COIR FIBER MAT	1,100 SY		
0194	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	9,000 SY		
019E	6042000000-E	1632	1/4" HARDWARE CLOTH	6,000 LF		
019E	6069000000-E	1638	STILLING BASINS	90 CY		
0197	6070000000-N	SP	SPECIAL STILLING BASINS	16 EA		
019E	6071010000-E	SP	WATTLE	4,425 LF		
019E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	8,100 LB		
020C	6071030000-E	SP	COIR FIBER BAFFLES	17,800 LF		
0201	6071050000-E	SP	*** SKIMMER (1-1/2")	72 EA		
0202	6084000000-E	1660	SEEDING & MULCHING	150 ACR		
0203	6087000000-E	1660	MOWING	100 ACR		
0204	6090000000-E	1661	SEED FOR REPAIR SEEDING	2,250 LB		
020E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	6 TON		
020E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	2,925 LB		
0207	6108000000-E	1665	FERTILIZER TOPDRESSING	87.5 TON		
020E	6111000000-E	SP	IMPERVIOUS DIKE	120 LF		
020E	6114500000-N	SP	SPECIALIZED HAND MOWING	100 MHR		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
021C	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	70	EA	
0211	6123000000-E	1670	REFORESTATION	10	ACR	
0212	7060000000-E	1705	SIGNAL CABLE	2,120	LF	
0213	7108000000-E	1705	VEHICLE SIGNAL HEAD (12", 1 SECTION)	4	EA	
0214	7300000000-E	1715	UNPAVED TRENCHING (*****) (2, 2")	960	LF	
021E	7301000000-E	1715	DIRECTIONAL DRILL (*****) (2, 2")	200	LF	
021E	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	6	EA	
0217	7360000000-N	1720	WOOD POLE	1	EA	
021E	7636000000-N	1745	SIGN FOR SIGNALS	5	EA	
021E	7912000000-N	1755	BEACON CONTROLLER ASSEMBLY & CABINET (*****) (F3)	1	EA	
<div style="border: 1px solid black; padding: 5px;"> <p>***** BEGIN SCHEDULE AB ***** ***** (3 ALTERNATES) *****</p> </div>						
022C	0987000000-E	310	GENERIC PIPE ITEM 15" RC PIPE CULVERTS, CLASS III	10,172	LF	
AB1						
0221	0987000000-E	310	GENERIC PIPE ITEM 18" RC PIPE CULVERTS, CLASS III	7,388	LF	
AB1						
0222	0987000000-E	310	GENERIC PIPE ITEM 24" RC PIPE CULVERTS, CLASS III	3,236	LF	
AB1						
0223	0987000000-E	310	GENERIC PIPE ITEM 30" RC PIPE CULVERTS, CLASS III	1,632	LF	
AB1						

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0224 AB1	0987000000-E	310	GENERIC PIPE ITEM 36" RC PIPE CULVERTS, CLASS III	1,408 LF		
*** OR ***						
0225 AB2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	3,868 LF		
0226 AB2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", 0.064")	2,648 LF		
0227 AB2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", 0.064")	356 LF		
0228 AB2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (30", 0.079")	132 LF		
0229 AB2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (36", 0.079")	704 LF		
023C AB2	0987000000-E	310	GENERIC PIPE ITEM 15" RC PIPE CULVERTS, CLASS III	6,304 LF		
0231 AB2	0987000000-E	310	GENERIC PIPE ITEM 18" RC PIPE CULVERTS, CLASS III	4,740 LF		
0232 AB2	0987000000-E	310	GENERIC PIPE ITEM 24" RC PIPE CULVERTS, CLASS III	2,880 LF		
0233 AB2	0987000000-E	310	GENERIC PIPE ITEM 30" RC PIPE CULVERTS, CLASS III	1,500 LF		
0234 AB2	0987000000-E	310	GENERIC PIPE ITEM 36" RC PIPE CULVERTS, CLASS III	704 LF		
*** OR ***						

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
023E AB3	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	3,868 LF		
023E AB3	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	2,648 LF		
0237 AB3	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	356 LF		
023E AB3	0536000000-E	SP	**** HDPE PIPE CULVERTS (30")	132 LF		
023E AB3	0536000000-E	SP	**** HDPE PIPE CULVERTS (36")	704 LF		
024C AB3	0987000000-E	310	GENERIC PIPE ITEM 15" RC PIPE CULVERTS, CLASS III	6,304 LF		
0241 AB3	0987000000-E	310	GENERIC PIPE ITEM 18" RC PIPE CULVERTS, CLASS III	4,740 LF		
0242 AB3	0987000000-E	310	GENERIC PIPE ITEM 24" RC PIPE CULVERTS, CLASS III	2,880 LF		
024E AB3	0987000000-E	310	GENERIC PIPE ITEM 30" RC PIPE CULVERTS, CLASS III	1,500 LF		
0244 AB3	0987000000-E	310	GENERIC PIPE ITEM 36" RC PIPE CULVERTS, CLASS III	704 LF		
***** END SCHEDULE AB *****						
***** BEGIN SCHEDULE BA ***** (2 ALTERNATES) *****						
024E BA1	0022000000-E	225	UNCLASSIFIED EXCAVATION	535,000 CY		
024E BA1	0106000000-E	230	BORROW EXCAVATION	56,000 CY		
0247 BA1	1121000000-E	520	AGGREGATE BASE COURSE	110,200 TON		
024E BA1	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	30,000 TON		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
024E BA1	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	5,085 TON		
----- *** OR *** -----						
025C BA2	0022000000-E	225	UNCLASSIFIED EXCAVATION	530,000 CY		
0251 BA2	0106000000-E	230	BORROW EXCAVATION	68,000 CY		
0252 BA2	1121000000-E	520	AGGREGATE BASE COURSE	19,000 TON		
025E BA2	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	70,000 TON		
0254 BA2	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	6,805 TON		

***** END SCHEDULE BA *****

CULVERT ITEMS

025E	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (534 + 79.00 -L-)	Lump Sum	L.S.	
025E	8126000000-N	414	CULVERT EXCAVATION, STA ***** (534 + 79.00 -L-)	Lump Sum	L.S.	
0257	8133000000-E	414	FOUNDATION CONDITIONING MATER- IAL, BOX CULVERT	252 TON		
025E	8196000000-E	420	CLASS A CONCRETE (CULVERT)	404.1 CY		
025E	8245000000-E	425	REINFORCING STEEL (CULVERT)	58,437 LB		

STRUCTURE ITEMS

026C	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (280 + 13.00 -L-LT)	Lump Sum	L.S.	
0261	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (298 + 34.21 -L-LT)	Lump Sum	L.S.	

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0262	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (560+00.35 -L-)	Lump Sum	L.S.	
0263	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1, 560+00.35 -L-)	Lump Sum	L.S.	
0264	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (2, 560+00.35 -L-)	Lump Sum	L.S.	
026E	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (3, 560+00.35 -L-)	Lump Sum	L.S.	
026E	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	149.83 LF		
0267	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	65 LF		
026E	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	24.42 LF		
026E	8112730000-N	SP	PDA TESTING	4 EA		
027C	8112740000-N	SP	PDA ASSISTANCE	4 EA		
0271	8113000000-N	SP	SID INSPECTION	3 EA		
0272	8114000000-N	SP	SPT TESTING	4 EA		
027E	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0274	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (280+13.00 -L-LT)	Lump Sum	L.S.	
027E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (280+13.00 -L-RT)	Lump Sum	L.S.	
027E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (298+34.21 -L-LT)	Lump Sum	L.S.	

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0277	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	36,205 SF		
027E	8161000000-E	420	GROOVING BRIDGE FLOORS	36,882 SF		
027S	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	697.4 CY		
028C	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (280 + 13.00 -L-LT)	Lump Sum	L.S.	
0281	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (280 + 13.00 -L-RT)	Lump Sum	L.S.	
0282	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (298 + 34.21 -L-LT)	Lump Sum	L.S.	
0283	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (298 + 34.21 -L-RT)	Lump Sum	L.S.	
0284	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (560 + 00.35 -L-)	Lump Sum	L.S.	
028E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	115,389 LB		
028E	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	10,046 LB		
0287	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	287.57 LF		
028E	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	2,113.38 LF		
028S	8274000000-E	430	MODIFIED 63" PRESTRESSED CONC GIRDERS	2,150 LF		
029C	8364000000-E	SP	HP12X53 STEEL PILES	6,325 LF		
0291	8387000000-E	SP	PP 18 X 0.50 GALVANIZED STEEL PILES	1,700 LF		
0292	8503000000-E	460	CONCRETE BARRIER RAIL	1,805.3 LF		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0293	8524000000-E	SP	*** CHAIN LINK FENCE (60")	650 LF		
0294	8531000000-E	462	4" SLOPE PROTECTION	1,000 SY		
029E	8590000000-E	876	RIP RAP, CLASS ** (II)	78 TON		
029E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,375 TON		
0297	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,786 SY		
029E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0299	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
030C	8706000000-N	SP	EXPANSION JOINT SEALS	Lump Sum	L.S.	

1209/Oct11/Q3719599.178/D1170448360000/E300

Total Amount Of Bid For Entire Project :

Contract No **C202265**

County (ies): **Rutherford**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)