

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	6,123 TON		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	21.54 SMI		
0004	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	70 SY		
0005	1330000000-E	607	INCIDENTAL MILLING	4,914 SY		
0006	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	13,591 TON		
0007	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	10,028 TON		
0008	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	42,538 TON		
0009	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	3,952 TON		
0010	1775000000-E	660	ASPHALT SURFACE TREATMENT, MAT COAT, #78M STONE	401,723 SY		
0011	1839000000-E	660	GENERIC PAVING ITEM ASPHALT SURFACE TREATMENT, MAT COAT, #67 STONE	194,349 SY		
0012	1880000000-E	SP	GENERIC PAVING ITEM 3" PATCHING OF EXISTING PAVE- MENT	2,348 TON		
0013	1880000000-E	SP	GENERIC PAVING ITEM 7" PATCHING OF EXISTING PAVE- MENT	4,079 TON		
0014	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	5 EA		
0015	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
0016	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	241,331 LF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	214,650 LF		
0018	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	78 LF		
0019	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	1,729 LF		
0020	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	937 LF		
0021	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	913 LF		
0022	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	604 LF		
0023	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	10 EA		
0024	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	93 EA		
0025	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	985,586 LF		
0026	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	902 LF		
0027	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	36 LF		
0028	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	2,328 EA		
0029	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	755 EA		
0030	6000000000-E	1605	TEMPORARY SILT FENCE	1,400 LF		
0031	6071010000-E	SP	WATTLE	448 LF		
0032	6084000000-E	1660	SEEDING & MULCHING	3.95 ACR		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0033	6110000000-E	SP	RESIDENTIAL SEEDING	3.95	ACR	

1418/Nov15/Q2135551.44/D116836110000/E33

Total Amount Of Bid For Entire Project :

**Contract No**     **C202644**

**County (ies):**   **Guilford**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General