

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

BEVERLY EAVES PERDUE
GOVERNOR

EUGENE A. CONTI, JR. SECRETARY

January 12, 2011

Addendum No. 2

RE: Contract ID C202331
WBS # 34431.3.7
Lee County (R-2417AA)
US-421 and NC-87 (Sanford Bypass) From West of SR-1400 To
West of US-1/15/501

January 18, 2011 Letting

To Whom It May Concern:

Reference is made to the plans and proposal furnished to you on this project.

The following revision has been made to the Roadway plans:

Sheet No. 3 (1 of 2) has been revised to increase the quantity of "Unclassified Excavation". Please void Sheet No. 3 (1 of 2) in your plans and staple the revised Sheet No. 3 (1 of 2) thereto.

Sheet No. 3-J has been revised to increase the quantity of "Unclassified Excavation" to account for the "Dry Detention Basin". Please void Sheet No. 3-J in your plans and staple the revised Sheet No. 3-J thereto.

The following revision has been made to the Roadway Sub-Surface Plans:

Sheet No. 3 has been revised to increase the quantity of "Unclassified Excavation". Please void Sheet No. 3 in your plans and staple the revised Sheet No. 3 thereto.

The following revision has been made to the proposal form:

On Page No. 52, the last paragraph of the project special provision entitled "Dry Detention Basin" has been revised. Please void Page No. 52 in your proposal and staple the revised Page No. 52 thereto.

On Page No. 1 of the item sheets by copy of this addendum the following pay item quantity is hereby revised:

<u>Item</u> <u>Description</u> <u>Old Quantity</u> <u>New Quantity</u> 4-0022000000-E-225 Unclassified Excavation 1,270,000 CY 1,287,700 Cy

TELEPHONE: 919-250-4128 FAX: 919-250-4119 WEBSITE: WWW.NCDOT.ORG The Contractor's bid must be based on this revised pay item quantity. The contract will be prepared accordingly.

The Expedite File has been updated to reflect this revision. Please download the Expedite Addendum File and follow the instructions for applying the addendum. Bid Express will not accept your bid unless the addendum has been applied.

Sincerely,

R. A. Garris, PE **Contract Officer**

RAG/jag Attachments

4	^	^	۰

Mr. Jon Nance, PE

Mr. Ron Hancock, PE

Mr. Tim Johnson, PE

Ms. D. M. Barbour, PE

Mr. Art McMillan, PE

Mr. J. V. Barbour, PE

Ms. Lori Strickland

Project File (2)

Mr. R.E. Davenport, PE

Ms. Natalie Roskam, PE

Mr. Larry Strickland

Ms. Penny Higgins

Ms. Jaci Kincaid

Mr. Ronnie Higgins

52



Measurement and Payment

Filter Fabric for Drainage will be measured and paid for in accordance with Article 876-4 of the Standard Specifications.

Rip Rap, Class I will be measured and paid for in accordance with Article 876-4 of the Standard Specifications.

Outlet Control Structure will be measured and paid for in accordance with Article 840-4 of the *Standard Specifications* for *Masonry Drainage Structure*. No separate payment will be made for Trash Racks as the cost of such is considered incidental to the outlet control structure.

Pipe will be measured and paid for in accordance with the contract documents.

_" Draw Down Pipe will be measured and paid for per each. Such price and payment shall be full compensation for all fittings, hardware and incidentals necessary for the satisfactory construction and installation of the _"Draw Down Pipe.

Sluice Gates will be measured and paid as described elsewhere in this contract document.

Payment for earthwork related to construction of dry detention basins will be made at the contract unit price for "Unclassified Excavation".

SELECT GRANULAR MATERIAL:

(3-16-10)

SP2 R80

Revise the Standard Specifications as follows:

Page 2-29, Delete Section 265 SELECT GRANULAR MATERIAL and replace it with the following:

SECTION 265 SELECT GRANULAR MATERIAL

265-1 Description

Furnish and place select granular material in accordance with the contract or as directed by the Engineer.

265-2 Materials

Refer to Division 10 of the Standard Specifications.

Item	Section
Select Material, Class II	1016
Select Material, Class III	1016