

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0038000000-E	SP	SHALLOW UNDERCUT	100 CY		
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	350 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	200 TON		
0008	0106000000-E	230	BORROW EXCAVATION	2,020 CY		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	336 CY		
001C	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	950 SY		
0011	0318000000-E	SP	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	10 TON		
0012	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	30 SY		
0013	0335200000-E	SP	15" DRAINAGE PIPE	64 LF		
0014	0995000000-E	340	PIPE REMOVAL	60 LF		
001E	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	200 TON		
0017	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	190 TON		
001E	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	320 TON		

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	40	TON	
002C	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25	TON	
0021	2022000000-E	SP	SUBDRAIN EXCAVATION	45	CY	
0022	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	34	CY	
0023	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	200	LF	
0024	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1	EA	
002E	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6	LF	
002E	3030000000-E	862	STEEL BM GUARDRAIL	150	LF	
0027	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
002E	3628000000-E	876	RIP RAP, CLASS I	50	TON	
003C	3635000000-E	876	RIP RAP, CLASS II	20	TON	
0031	3649000000-E	876	RIP RAP, CLASS B	56	TON	
0032	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	730	SY	
0033	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	28	LF	
0034	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	2	EA	
003E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	7	EA	
003E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	361	SF	

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94	SF	
003E	4445000000-E	1145	BARRICADES (TYPE III)	80	LF	
003E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,090	LF	
004C	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,090	LF	
0041	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	9	EA	
0042	6000000000-E	1605	TEMPORARY SILT FENCE	1,100	LF	
004E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225	TON	
0044	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	120	TON	
004E	6012000000-E	1610	SEDIMENT CONTROL STONE	70	TON	
004E	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
0047	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25	TON	
004E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	315	LF	
005C	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
0051	6029000000-E	SP	SAFETY FENCE	400	LF	
0052	6030000000-E	1630	SILT EXCAVATION	240	CY	
005E	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,400	SY	
0054	6037000000-E	SP	COIR FIBER MAT	400	SY	

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6042000000-E	1632	1/4" HARDWARE CLOTH	150 LF		
005E	6069000000-E	1638	STILLING BASINS	170 CY		
0057	6071010000-E	SP	WATTLE	500 LF		
005E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	300 LB		
005E	6071030000-E	SP	COIR FIBER BAFFLES	350 LF		
006C	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0061	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0062	6087000000-E	1660	MOWING	1 ACR		
0063	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0064	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
006E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
006E	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0067	6111000000-E	SP	IMPERVIOUS DIKE	210 LF		
006E	6114500000-N	SP	SPECIALIZED HAND MOWING	20 MHR		
006E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
007C	6120000000-E	SP	CULVERT DIVERSION CHANNEL	150 CY		
0071	6123000000-E	1670	REFORESTATION	0.2 ACR		

---

**CULVERT ITEMS**


---

0072	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+52.00-L-)	Lump Sum	L.S.	
------	--------------	-----	--	----------	------	--

---

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	8126000000-N	414	CULVERT EXCAVATION, STA ***** (13+52.00-L)	Lump Sum	L.S.	
0074	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	147 TON		
0075	8196000000-E	420	CLASS A CONCRETE (CULVERT)	319.7 CY		
0076	8245000000-E	425	REINFORCING STEEL (CULVERT)	52,650 LB		
0077	8818000000-E	SP	GENERIC CULVERT ITEM BOULDERS	110 TON		
0078	8822000000-E	SP	GENERIC CULVERT ITEM COIR FIBER MAT (STRUCTURES)	420 SY		

1526/Dec03/Q70003.15/D326008410000/E78

Total Amount Of Bid For Entire Project :

**Contract No**     **C202577**

**County (ies):**   **Catawba**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General