

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	3,006 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	1,690 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	67.4 SMI		
0005	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,375 TON		
0006	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	4,525 TON		
0007	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	16,230 TON		
0008	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	53,760 TON		
0009	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	5,925 TON		
0010	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,632 TON		
0011	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	3,226 TON		
0012	1704000000-E	SP	PATCHING EXISTING PAVEMENT	1,325 TON		
0013	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	176,986 LF		
0014	1880000000-E	SP	GENERIC PAVING ITEM JOINT REPAIR	400 TON		
0015	1891000000-E	SP	GENERIC PAVING ITEM INCIDENTAL MILLING	3,940 SY		
0016	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	1 EA		
0017	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	8 EA		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
001E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	101,574 LF		
002C	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	105,504 LF		
0021	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	92,180 LF		
0022	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	114,304 LF		
0023	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	2,100 LF		
0024	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	200 LF		
002E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	240 LF		
002E	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	13 EA		
0027	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	22 EA		
002E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	358,310 LF		
002E	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	198,270 LF		
003C	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	1 EA		
0031	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	1,981 EA		
0032	6000000000-E	1605	TEMPORARY SILT FENCE	3,683 LF		
0033	6071010000-E	SP	WATTLE	590 LF		
0034	6084000000-E	1660	SEEDING & MULCHING	46.82 ACR		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	6090000000-E	1661	SEED FOR REPAIR SEEDING	2,360 LB		
0036	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	13.75 TON		
0037	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	400 LF		

0810/Dec09/Q1255890.97/D130256110000/E37

Total Amount Of Bid For Entire Project :

Contract No **C202669**

County (ies): **Chatham**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General