

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0004	0022000000-E	225	UNCLASSIFIED EXCAVATION	217,500 CY		
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	3,400 CY		
0007	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	440 CY		
0009	0141000000-E	240	BERM DITCH CONSTRUCTION	2,180 LF		
0010	0195000000-E	SP	SELECT GRANULAR MATERIAL	800 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,300 SY		
0012	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	130 TON		
0013	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	400 SY		
0014	0987000000-E	310	GENERIC PIPE ITEM 15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	8 LF		
0015	0987000000-E	310	GENERIC PIPE ITEM 15" SIDE DRAIN PIPE	72 LF		
0016	0987000000-E	310	GENERIC PIPE ITEM 18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	12 LF		
0017	0987000000-E	310	GENERIC PIPE ITEM 18" RC PIPE CULVERTS, CLASS III	374 LF		
0018	0987000000-E	310	GENERIC PIPE ITEM 18" SIDE DRAIN PIPE	48 LF		
0019	0987000000-E	310	GENERIC PIPE ITEM 24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	72 LF		

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	0987000000-E	310	GENERIC PIPE ITEM 24" RC PIPE CULVERTS, CLASS III	292	LF	
0021	0987000000-E	310	GENERIC PIPE ITEM 30" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK	128	LF	
0022	0987000000-E	310	GENERIC PIPE ITEM 30" RC PIPE CULVERTS, CLASS III	128	LF	
0023	0987000000-E	310	GENERIC PIPE ITEM 36" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK	36	LF	
0024	0987000000-E	310	GENERIC PIPE ITEM 42" BIT COAT CS PIPE CULVERTS, TYPE B 0.109" THICK	20	LF	
0025	0987000000-E	310	GENERIC PIPE ITEM 48" RC PIPE CULVERTS, CLASS III	64	LF	
0026	0987000000-E	310	GENERIC PIPE ITEM 54" RC PIPE CULVERTS, CLASS III	64	LF	
0027	0988000000-E	310	GENERIC PIPE ITEM 15" PIPE END SECTIONS	4	EA	
0028	0988000000-E	310	GENERIC PIPE ITEM 18" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2	EA	
0029	0988000000-E	310	GENERIC PIPE ITEM 18" PIPE END SECTIONS	5	EA	
0030	0988000000-E	310	GENERIC PIPE ITEM 24" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4	EA	
0031	0988000000-E	310	GENERIC PIPE ITEM 30" BIT COAT CS PIPE ELBOWS, TYPE B 0.079" THICK	2	EA	
0032	0995000000-E	340	PIPE REMOVAL	902	LF	
0033	1022000000-E	SP	SEALING EXISTING PAVEMENT CRACKS	500	LB	
0034	,1121000000-E	520	AGGREGATE BASE COURSE	6,300	TON	

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
0036	1330000000-E	607	INCIDENTAL MILLING	1,000 SY		
0037	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	680 TON		
0038	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	3,520 TON		
0039	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	3,620 TON		
0040	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	415 TON		
0041	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	200 TON		
0042	1704000000-E	SP	PATCHING EXISTING PAVEMENT	100 TON		
0043	2209000000-E	838	ENDWALLS	6 CY		
0044	2220000000-E	838	REINFORCED ENDWALLS	5 CY		
0045	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	9 EA		
0046	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	6 EA		
0047	2619000000-E	850	4" CONCRETE PAVED DITCH	140 SY		
0048	3030000000-E	862	STEEL BM GUARDRAIL	2,500 LF		
0049	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	37.5 LF		
0050	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0051	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	3 EA		
0052	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	11 EA		
0053	3569000000-E	867	BARBED WIRE FENCE RESET	2,375 LF		

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	3628000000-E	876	RIP RAP, CLASS I	95 TON		
0055	3642000000-E	876	RIP RAP, CLASS A	1,500 TON		
0056	3649000000-E	876	RIP RAP, CLASS B	692 TON		
0057	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	3,457 SY		
0058	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	240 SF		
0059	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	248 SF		
0060	4430000000-N	1130	DRUMS	150 EA		
0061	4445000000-E	1145	BARRICADES (TYPE III)	200 LF		
0062	4450000000-N	1150	FLAGGER	4,560 HR		
0063	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	18,044 LF		
0064	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	54,132 LF		
0065	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	150 EA		
0066	6000000000-E	1605	TEMPORARY SILT FENCE	22,300 LF		
0067	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	1,150 TON		
0068	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	4,000 TON		
0069	6012000000-E	1610	SEDIMENT CONTROL STONE	2,100 TON		
0070	6015000000-E	1615	TEMPORARY MULCHING	27.5 ACR		
0071	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	650 LB		
0072	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	2.75 TON		
0073	6024000000-E	1622	TEMPORARY SLOPE DRAINS	6,250 LF		

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	126	EA	
0075	6029000000-E	SP	SAFETY FENCE	500	LF	
0076	6030000000-E	1630	SILT EXCAVATION	5,000	CY	
0077	6036000000-E	1631	MATTING FOR EROSION CONTROL	78,100	SY	
0078	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,900	SY	
0079	6042000000-E	1632	1/4" HARDWARE CLOTH	1,450	LF	
0080	6070000000-N	SP	SPECIAL STILLING BASINS	8	EA	
0081	6071010000-E	SP	WATTLE	2,100	LF	
0082	6071020000-E	SP	POLYACRYLAMIDE (PAM)	500	LB	
0083	6071030000-E	SP	COIR FIBER BAFFLES	5,550	LF	
0084	6084000000-E	1660	SEEDING & MULCHING	33	ACR	
0085	6087000000-E	1660	MOWING	21	ACR	
0086	6090000000-E	1661	SEED FOR REPAIR SEEDING	250	LB	
0087	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1	TON	
0088	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	775	LB	
0089	6108000000-E	1665	FERTILIZER TOPDRESSING	23	TON	
0090	6114500000-N	SP	SPECIALIZED HAND MOWING	10	MHR	
0091	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	
0092	6123000000-E	1670	REFORESTATION	1	ACR	
0093	8802015100-N	SP	SOIL NAIL VERIFICATION TESTS	1	EA	

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0094	8802015110-N	SP	SOIL NAIL PROOF TESTS	4 EA		
0095	8834000000-N	SP	GENERIC RETAINING WALL ITEM SUPPLEMENTAL SOIL NAILS	10 EA		
0096	8848000000-E	SP	GENERIC RETAINING WALL ITEM SOIL NAIL SLOPE STABILIZATION	500 SY		
<b>1605/Feb08/Q467150.75/D315271690210/E94</b>			<b>Total Amount Of Bid For Entire Project :</b>			

**Contract No**     **C202173**

**County (ies):**   **Cherokee**

**ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION**

---

**Contract Officer**

---

**Date**

**Execution of Contract and Bonds  
Approved as to Form:**

---

**Attorney General**