

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	1,954 CY		
0003	0255000000-E	SP	GENERIC GRADING ITEM AGGREGATE SHOULDER BORROW	750 TON		
0004	1220000000-E	545	INCIDENTAL STONE BASE	440 TON		
0005	1245000000-E	SP	SHOULDER RECONSTRUCTION	21.22 SMI		
0006	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	13,727 SY		
0007	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1-1/2" TO 3")	75,664 SY		
0008	1330000000-E	607	INCIDENTAL MILLING	1,950 SY		
0009	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	5,274 TON		
0010	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	20,582 TON		
0011	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,461 TON		
0012	1704000000-E	SP	PATCHING EXISTING PAVEMENT	7,200 TON		
0013	2830000000-N	858	ADJUSTMENT OF MANHOLES	154 EA		
0014	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	8 EA		
0015	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	114,163 LF		
0016	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	142,607 LF		
0017	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	260 LF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	4,169 LF		
001S	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	2,628 LF		
002C	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	72 EA		
0021	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	210 EA		
0022	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	800 LF		
0023	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (III)	6 EA		
0024	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	42,350 LF		
002E	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	3,849 LF		
002E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	2,030 LF		
0027	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	60 EA		
002E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	162 EA		
002S	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	800 LF		
003C	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	931 EA		
0031	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	638 EA		
0032	6084000000-E	1660	SEEDING & MULCHING	15.41 ACR		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0033	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	5,900		
				LF		

1513/Jan12/Q450836.63/D113535100000/E33

Total Amount Of Bid For Entire Project :

Contract No **C202713**

County (ies): **Durham**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General