

County : Franklin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0036000000-E	225	UNDERCUT EXCAVATION	60 CY		
0003	0106000000-E	230	BORROW EXCAVATION	350 CY		
0004	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	100 SY		
0005	0318000000-E	SP	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	10 TON		
0006	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	30 SY		
0007	0366000000-E	SP	15" RC PIPE CULVERTS, CLASS III	50 LF		
0008	0372000000-E	SP	18" RC PIPE CULVERTS, CLASS III	20 LF		
0009	0390000000-E	SP	36" RC PIPE CULVERTS, CLASS III	12 LF		
0010	0576000000-E	SP	*** CS PIPE CULVERTS, ***** THICK (48", 0.109")	70 LF		
0011	1220000000-E	545	INCIDENTAL STONE BASE	225 TON		
0012	1245000000-E	SP	SHOULDER RECONSTRUCTION	9.68 SMI		
0013	1297000000-E	607	MILLING ASPHALT PAVEMENT, ***** DEPTH (1-1/2")	6,460 SY		
0014	1330000000-E	607	INCIDENTAL MILLING	740 SY		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	9,016 TON		
0016	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	8,112 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	874 TON		

County : Franklin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
001E	1704000000-E	SP	PATCHING EXISTING PAVEMENT	300 TON		
002C	2253000000-E	840	PIPE COLLARS	2 CY		
0021	2612000000-E	848	6" CONCRETE DRIVEWAY	215 SY		
0022	3649000000-E	876	RIP RAP, CLASS B	46 TON		
0023	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	112 SY		
0024	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	107 SF		
002E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	492 SF		
002E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	78 SF		
0027	4435000000-N	1135	CONES	130 EA		
002E	4445000000-E	1145	BARRICADES (TYPE III)	104 LF		
002E	4450000000-N	1150	FLAGGER	1,960 HR		
003C	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	52,078 LF		
0031	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	51,675 LF		
0032	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	360 LF		
003C	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	86 LF		
0034	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	17 EA		
003E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	445 EA		

County : Franklin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	6000000000-E	1605	TEMPORARY SILT FENCE	50	LF	
0037	6012000000-E	1610	SEDIMENT CONTROL STONE	30	TON	
0038	6029000000-E	SP	SAFETY FENCE	240	LF	
0039	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	50	SY	
0040	6070000000-N	SP	SPECIAL STILLING BASINS	2	EA	
0041	6071010000-E	SP	WATTLE	80	LF	
0042	6084000000-E	1660	SEEDING & MULCHING	6.8	ACR	
0043	6111000000-E	SP	IMPERVIOUS DIKE	48	LF	
0044	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	6	EA	

0812/Jan03/Q134909.48/D137350110000/E44

Total Amount Of Bid For Entire Project :

Contract No **C202584**

County (ies): **Franklin**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General