

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (20+07.30)	Lump Sum	L.S.	
0003	0038000000-E	SP	SHALLOW UNDERCUT	150 CY		
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	750 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	300 TON		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,050 SY		
0009	0199000000-E	SP	TEMPORARY SHORING	3,350 SF		
0010	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	60 TON		
0011	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	160 SY		
0012	0335200000-E	SP	15" DRAINAGE PIPE	128 LF		
0013	0343000000-E	SP	15" SIDE DRAIN PIPE	72 LF		
0014	0344000000-E	SP	18" SIDE DRAIN PIPE	36 LF		
0015	0448000000-E	SP	***** RC PIPE CULVERTS, CLASS IV (15")	164 LF		
0016	0582000000-E	SP	15" CS PIPE CULVERTS, 0.064" THICK	214 LF		
0017	0588000000-E	SP	18" CS PIPE CULVERTS, 0.064" THICK	24 LF		

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0636000000-E	SP	*** CS PIPE ELBOWS, ***** THICK (15", 0.064)	4	EA	
001S	0995000000-E	340	PIPE REMOVAL	374	LF	
002C	1121000000-E	520	AGGREGATE BASE COURSE	1,040	TON	
0021	1220000000-E	545	INCIDENTAL STONE BASE	150	TON	
002Z	1264000000-E	SP	DITCHING	140	LF	
002Z	1275000000-E	600	PRIME COAT	865	GAL	
0024	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	510	TON	
002E	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	340	TON	
002E	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,020	TON	
0027	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	100	TON	
002E	2022000000-E	SP	SUBDRAIN EXCAVATION	84	CY	
002S	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	42	CY	
003C	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	250	LF	
0031	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1	EA	
003Z	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6	LF	
003Z	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	8	EA	
0034	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	4	EA	
003E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3	EA	

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	2396000000-N	840	FRAME WITH COVER, STD 840.54	1		
				EA		
0037	2556000000-E	846	SHOULDER BERM GUTTER	155		
				LF		
003E	2995000000-N	SP	GENERIC DRAINAGE ITEM CONVERT EXISTING DROP INLET TO TBJB	1		
				EA		
003E	3030000000-E	862	STEEL BM GUARDRAIL	275		
				LF		
004C	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	62.5		
				LF		
0041	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5		
				EA		
0042	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350 TL-2)	2		
				EA		
0043	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2		
				EA		
0044	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4		
				EA		
004E	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	300		
				LF		
004E	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	4		
				EA		
0047	3389000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (350 TL-2)	4		
				EA		
004E	3649000000-E	876	RIP RAP, CLASS B	5		
				TON		
004E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,010		
				SY		
005C	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1		
				EA		
0051	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	73		
				LF		
0052	4096000000-N	904	SIGN ERECTION, TYPE D	1		
				EA		

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	4102000000-N	904	SIGN ERECTION, TYPE E	3 EA		
0054	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	1 EA		
005E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	10 EA		
005E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	164 SF		
0057	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	60 SF		
005E	4430000000-N	1130	DRUMS	110 EA		
005E	4445000000-E	1145	BARRICADES (TYPE III)	120 LF		
006C	4450000000-N	1150	FLAGGER	1,280 HR		
0061	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0062	4485000000-E	1170	PORTABLE CONCRETE BARRIER	380 LF		
0063	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	125 EA		
0064	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	832 LF		
006E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,028 LF		
006E	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	740 LF		
0067	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	22,800 LF		
006E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	7 EA		
006E	6000000000-E	1605	TEMPORARY SILT FENCE	2,100 LF		

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007C	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	315 TON		
0071	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	485 TON		
0072	6012000000-E	1610	SEDIMENT CONTROL STONE	465 TON		
0073	6015000000-E	1615	TEMPORARY MULCHING	12 ACR		
0074	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	400 LB		
007E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2.5 TON		
007E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	500 LF		
0077	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	10 EA		
007E	6029000000-E	SP	SAFETY FENCE	650 LF		
007E	6030000000-E	1630	SILT EXCAVATION	1,020 CY		
008C	6036000000-E	1631	MATTING FOR EROSION CONTROL	10,000 SY		
0081	6037000000-E	SP	COIR FIBER MAT	200 SY		
0082	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	275 SY		
0083	6042000000-E	1632	1/4" HARDWARE CLOTH	275 LF		
0084	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
008E	6071010000-E	SP	WATTLE	650 LF		
008E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	180 LB		
0087	6071030000-E	SP	COIR FIBER BAFFLES	500 LF		
008E	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	6084000000-E	1660	SEEDING & MULCHING	12 ACR		
009C	6087000000-E	1660	MOWING	5 ACR		
0091	6090000000-E	1661	SEED FOR REPAIR SEEDING	150 LB		
0092	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0093	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	300 LB		
0094	6108000000-E	1665	FERTILIZER TOPDRESSING	9 TON		
009E	6114500000-N	SP	SPECIALIZED HAND MOWING	40 MHR		
009E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	20 EA		
0097	6123000000-E	1670	REFORESTATION	1 ACR		
<b>STRUCTURE ITEMS</b>						
009E	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (20+07.03-L-)	Lump Sum	L.S.	
009E	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (20+07.03-L-)	Lump Sum	L.S.	
010C	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (20+07.03-L-)	Lump Sum	L.S.	
0101	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SO IL	64.5 LF		
0102	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	71 LF		
0103	8111200000-E	SP	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	72.4 LF		

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0104	8113000000-N	SP	SID INSPECTION	1 EA		
0105	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0106	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	8,323 SF		
0107	8161000000-E	420	GROOVING BRIDGE FLOORS	6,626 SF		
0108	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	167 CY		
0109	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (20+07.03-L-)	Lump Sum	L.S.	
0110	8217000000-E	425	REINFORCING STEEL (BRIDGE)	33,997 LB		
0111	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,879 LB		
0112	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	894.9 LF		
0113	8364000000-E	SP	HP12X53 STEEL PILES	475 LF		
0114	8482000000-E	460	THREE BAR METAL RAIL	348.614 LF		
0115	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,410 TON		
0116	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,570 SY		
0117	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0118	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1530/Jan04/Q117463.664/D510876350000/E118

Total Amount Of Bid For Entire Project :

**Contract No**     **C202579**

**County (ies):**   **Lincoln**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General