

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0234000000-E	SP	GENERIC GRADING ITEM BORROW EXCAVATION (STATE FURNISHED SOURCES)	4,628 CY		
0004	0241000000-E	SP	GENERIC GRADING ITEM REMOVE & REPLACE 5' SIDEWALK	175 SY		
0005	0241000000-E	SP	GENERIC GRADING ITEM REMOVE & REPLACE DRIVEWAY TURN OUT	250 SY		
0006	0257000000-E	SP	GENERIC GRADING ITEM REMOVE AND REPLACE 2'-6" CURB & GUTTER	660 LF		
0007	0257000000-E	SP	GENERIC GRADING ITEM REMOVE AND REPLACE CONC VALLEY GUTTER	100 LF		
0008	0264000000-E	SP	GENERIC GRADING ITEM GRADING PER SHOULDER MILE	0.08 SMI		
0009	1220000000-E	545	INCIDENTAL STONE BASE	385 TON		
001C	1245000000-E	SP	SHOULDER RECONSTRUCTION	9.1 SMI		
0011	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	10,360 SY		
0012	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	79,882 SY		
0013	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	40,038 SY		
0014	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (4")	10,626 SY		

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (2-1/2" TO 4")	32,102 SY		
001E	1330000000-E	607	INCIDENTAL MILLING	10,344 SY		
0017	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	75 TON		
001E	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	19,680 TON		
0019	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	22,149 TON		
002C	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	33,679 TON		
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	2,258 TON		
0022	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	2,021 TON		
0023	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (FULL DEPTH)	145 TON		
0024	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (MILL)	1,650 TON		
002E	1891000000-E	SP	GENERIC PAVING ITEM INCIDENTAL CONCRETE	800 SY		
002E	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	78 LF		
0027	2591000000-E	848	4" CONCRETE SIDEWALK	272 SY		
002E	2600000000-N	SP	RETROFIT EXISTING WHEELCHAIR RAMPS	39 EA		
002E	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	33 EA		
003C	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	315 SY		

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0031	2759000000-N	SP	GENERIC PAVING ITEM DETECTABLE WARNINGS	4 EA		
0032	2830000000-N	858	ADJUSTMENT OF MANHOLES	32 EA		
0033	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	50 EA		
0034	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
003E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	71,944 LF		
003E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	165,452 LF		
0037	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,493 LF		
003E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	4,344 LF		
003E	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	32 EA		
004C	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	588 EA		
0041	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	275,219 LF		
0042	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	1,493 LF		
0043	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	4,544 LF		
0044	4840000000-N	1205	PAINT PAVEMENT MARKING CHARAC- TER	32 EA		
004E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	588 EA		
004E	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,200 LF		

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0047	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	550 LF		
004E	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	450 LF		
004E	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	26 EA		
005C	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	57 EA		
0051	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	4,225 EA		
0052	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
005E	6000000000-E	1605	TEMPORARY SILT FENCE	1,224 LF		
0054	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	245 TON		
005E	6012000000-E	1610	SEDIMENT CONTROL STONE	245 TON		
005E	6015000000-E	1615	TEMPORARY MULCHING	9.74 ACR		
0057	6036000000-E	1631	MATTING FOR EROSION CONTROL	90 SY		
005E	6042000000-E	1632	1/4" HARDWARE CLOTH	488 LF		
005E	6071010000-E	SP	WATTLE	170 LF		
006C	6084000000-E	1660	SEEDING & MULCHING	6.88 ACR		
0061	6090000000-E	1661	SEED FOR REPAIR SEEDING	488 LB		
0062	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	2.45 TON		
006E	7000000000-E	1705	PEDESTRIAN SIGNAL HEAD (***, ** SECTION) (16", 1 SECTION)	8 EA		
0064	7060000000-E	1705	SIGNAL CABLE	3,260 LF		

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
006E	7288000000-E	1715	PAVED TRENCHING (***** (1, 2")	20 LF		
006E	7288000000-E	1715	PAVED TRENCHING (***** (2, 2")	50 LF		
0067	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	455 LF		
006E	7300000000-E	1715	UNPAVED TRENCHING (***** (2, 2")	75 LF		
006E	7301000000-E	1715	DIRECTIONAL DRILL (***** (1, 2")	80 LF		
007C	7301000000-E	1715	DIRECTIONAL DRILL (***** (3, 2")	245 LF		
0071	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	43 EA		
0072	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEA- VY DUTY)	4 EA		
007E	7420000000-E	1722	2" RISER WITH WEATHERHEAD	6 EA		
0074	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	14,750 LF		
007E	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	10,684 LF		
007E	7624000000-N	1743	SIGNAL PEDESTAL WITH FOUNDA- TION	8 EA		
0077	7980000000-N	SP	GENERIC SIGNAL ITEM PUSH BUTTON POST	2 EA		

1515/Jan07/Q837739.25/D310423110000/E77

Total Amount Of Bid For Entire Project :

Contract No **C202688**

County (ies): **Onslow**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General