

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+85.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0007	0195000000-E	SP	SELECT GRANULAR MATERIAL	300 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	598 SY		
0009	0223000000-E	SP	ROCK PLATING	860 SY		
0010	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	194 TON		
0011	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	240 SY		
0012	0335200000-E	SP	15" DRAINAGE PIPE	84 LF		
0013	0448200000-E	SP	15" RC PIPE CULVERTS, CLASS IV	616 LF		
0014	1121000000-E	520	AGGREGATE BASE COURSE	38 TON		
0015	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	970 TON		
0017	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	140 TON		
0018	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	700 TON		
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	95 TON		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	2022000000-E	SP	SUBDRAIN EXCAVATION	22.4 CY		
0021	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	16.8 CY		
0022	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	100 LF		
0023	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1 EA		
0024	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0025	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	6 EA		
0026	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	6 EA		
0027	2556000000-E	846	SHOULDER BERM GUTTER	684 LF		
0028	3030000000-E	862	STEEL BM GUARDRAIL	912.5 LF		
0029	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0030	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III, SHOP CURVED)	2 EA		
0031	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	2 EA		
0032	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0033	3649000000-E	876	RIP RAP, CLASS B	4 TON		
0034	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	515 SY		
0035	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	400 SF		
0036	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0037	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	90 SF		
0038	4435000000-N	1135	CONES	20 EA		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	4445000000-E	1145	BARRICADES (TYPE III)	40 LF		
0040	4450000000-N	1150	FLAGGER	60 HR		
0041	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,176 LF		
0042	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,176 LF		
0043	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	14 EA		
0044	5325600000-E	1510	6" WATER LINE	1,074 LF		
0045	5540000000-E	1515	6" VALVE	2 EA		
0046	5800000000-E	1530	ABANDON 6" UTILITY PIPE	1,080 LF		
0047	5871400000-E	1550	TRENCHLESS INSTALLATION OF 6" IN SOIL	470 LF		
0048	5871410000-E	1550	TRENCHLESS INSTALLATION OF 6" NOT IN SOIL	470 LF		
0049	6000000000-E	1605	TEMPORARY SILT FENCE	1,175 LF		
0050	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
0051	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	160 TON		
0052	6012000000-E	1610	SEDIMENT CONTROL STONE	210 TON		
0053	6015000000-E	1615	TEMPORARY MULCHING	2 ACR		
0054	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0055	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0056	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0057	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	6029000000-E	SP	SAFETY FENCE	450 LF		
0059	6030000000-E	1630	SILT EXCAVATION	160 CY		
0060	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,530 SY		
0061	6042000000-E	1632	1/4" HARDWARE CLOTH	800 LF		
0062	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	365 SY		
0063	6071010000-E	SP	WATTLE	50 LF		
0064	6071020000-E	SP	POLYACRYLAMIDE (PAM)	35 LB		
0065	6071030000-E	SP	COIR FIBER BAFFLES	100 LF		
0066	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0067	6087000000-E	1660	MOWING	3 ACR		
0068	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0069	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0070	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0071	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		
0072	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
0073	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
0074	6123000000-E	1670	REFORESTATION	0.1 ACR		
STRUCTURE ITEMS						
0075	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+85.00-L-)	Lump Sum	L.S.	

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	8112730000-N	SP	PDA TESTING	2 EA		
0077	8112740000-N	SP	PDA ASSISTANCE	2 EA		
0078	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (16+85.00-L-)	Lump Sum	L.S.	
0079	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	68 CY		
0080	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+85.00-L-)	Lump Sum	L.S.	
0081	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	12,784 LB		
0082	8333000000-E	SP	16" PRESTRESSED CONC PILES	2,925 LF		
0083	8393000000-N	SP	PILE REDRIVES	40 EA		
0084	8475000000-E	460	TWO BAR METAL RAIL	380.5 LF		
0085	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (1'-2"X2'-9")	395.5 LF		
0086	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	400 TON		
0087	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	440 SY		
0088	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0089	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	2,565.88 LF		

0928/Feb02/Q41703.68/D403251340000/E89

Total Amount Of Bid For Entire Project :

Contract No **C202376**

County (ies): **Beaufort**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General