

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0000700000-N	SP	FIELD OFFICE	Lump Sum	L.S.	
0004	0015000000-N	205	SEALING ABANDONED WELLS	5 EA		
000E	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (222 + 30.14-L-RT)	Lump Sum	L.S.	
000E	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (222 + 72.86-L-LT)	Lump Sum	L.S.	
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (54 + 13.70-L-LT)	Lump Sum	L.S.	
000E	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (54 + 54.12-L-RT)	Lump Sum	L.S.	
0009	0038000000-E	SP	SHALLOW UNDERCUT	11,650 CY		
001C	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0011	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	15,500 TON		
0012	0134000000-E	240	DRAINAGE DITCH EXCAVATION	6,900 CY		
0013	0194000000-E	SP	SELECT GRANULAR MATERIAL, CLASS III	7,500 CY		
0014	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	114,200 SY		
001E	0199000000-E	SP	TEMPORARY SHORING	2,100 SF		
001E	0223000000-E	SP	ROCK PLATING	70 SY		
0017	0234000000-E	SP	GENERIC GRADING ITEM UNDERCUT EXCAVATION	84,500 CY		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0255000000-E	SP	GENERIC GRADING ITEM EXCAVATION & STOCKPILING OF CONTAMINATED SOIL	200 TON		
001S	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	3,270 TON		
002C	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	73,220 SY		
0021	0343000000-E	SP	15" SIDE DRAIN PIPE	3,492 LF		
0022	0344000000-E	SP	18" SIDE DRAIN PIPE	476 LF		
0023	0345000000-E	SP	24" SIDE DRAIN PIPE	528 LF		
0024	0366000000-E	SP	15" RC PIPE CULVERTS, CLASS III	2,316 LF		
002E	0372000000-E	SP	18" RC PIPE CULVERTS, CLASS III	296 LF		
002E	0378000000-E	SP	24" RC PIPE CULVERTS, CLASS III	712 LF		
0027	0384000000-E	SP	30" RC PIPE CULVERTS, CLASS III	744 LF		
002E	0390000000-E	SP	36" RC PIPE CULVERTS, CLASS III	348 LF		
002S	0448200000-E	SP	15" RC PIPE CULVERTS, CLASS IV	1,740 LF		
003C	0448300000-E	SP	18" RC PIPE CULVERTS, CLASS IV	104 LF		
0031	0448400000-E	SP	24" RC PIPE CULVERTS, CLASS IV	136 LF		
0032	0448500000-E	SP	30" RC PIPE CULVERTS, CLASS IV	164 LF		
0033	0448600000-E	SP	36" RC PIPE CULVERTS, CLASS IV	172 LF		
0034	0453000000-E	SP	*** PIPE END SECTION (15")	5 EA		
003E	0453000000-E	SP	*** PIPE END SECTION (18")	1 EA		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	0453000000-E	SP	*** PIPE END SECTION (30")	2 EA		
0037	0453000000-E	SP	*** PIPE END SECTION (36")	2 EA		
003E	0546000000-E	SP	*** CAA PIPE CULVERTS, ***** THICK (24", 0.064")	76 LF		
003E	0564000000-E	SP	*** CAA PIPE ELBOWS, ***** THICK (24", 0.064")	2 EA		
004C	0986000000-E	SP	GENERIC PIPE ITEM 103" X 71" CAA PIPE ARCH CULVERTS, 0.135" THICK	222 LF		
0041	0986000000-E	SP	GENERIC PIPE ITEM 95" X 67" CAA PIPE ARCH CULVERTS, 0.109" THICK	300 LF		
0042	0995000000-E	340	PIPE REMOVAL	5,440 LF		
004E	1110000000-E	510	STABILIZER AGGREGATE	3,000 TON		
0044	1220000000-E	545	INCIDENTAL STONE BASE	3,500 TON		
004E	1330000000-E	607	INCIDENTAL MILLING	1,220 SY		
004E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,320 TON		
0047	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	270 TON		
004E	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,120 TON		
004E	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	41,970 TON		
005C	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	2,520 TON		
0051	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	516 TON		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	85,000	LF	
0053	2022000000-E	SP	SUBDRAIN EXCAVATION	1,602	CY	
0054	2026000000-E	SP	FILTER FABRIC FOR SUBSURFACE DRAINS	4,400	SY	
005E	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	462	CY	
005E	2036000000-E	SP	SUBDRAIN COARSE AGGREGATE	740	CY	
0057	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	4,400	LF	
005E	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	15	EA	
005E	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	90	LF	
006C	2187000000-E	SP	SEEPS	5	SY	
0061	2209000000-E	838	ENDWALLS	17	CY	
0062	2220000000-E	838	REINFORCED ENDWALLS	35	CY	
0063	2253000000-E	840	PIPE COLLARS	4	CY	
0064	2264000000-E	840	PIPE PLUGS	1	CY	
006E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	67	EA	
006E	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	3	LF	
0067	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	9	EA	
006E	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	1	EA	
006E	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	23	EA	
007C	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	33	EA	

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	1 EA		
0072	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	9 EA		
0073	2556000000-E	846	SHOULDER BERM GUTTER	120 LF		
0074	2570000000-N	SP	MODIFIED CONCRETE FLUME	4 EA		
0075	2612000000-E	848	6" CONCRETE DRIVEWAY	660 SY		
0076	2619000000-E	850	4" CONCRETE PAVED DITCH	20 SY		
0077	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	4,390 SY		
0078	2815000000-N	858	ADJUSTMENT OF DROP INLETS	1 EA		
0079	3030000000-E	862	STEEL BM GUARDRAIL	2,350 LF		
0080	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	62.5 LF		
0081	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0082	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0083	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	2 EA		
0084	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	5 EA		
0085	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	8 EA		
0086	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	12 EA		
0087	3360000000-E	863	REMOVE EXISTING GUARDRAIL	680 LF		
0088	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	1,837.5 LF		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (B-77)	3 EA		
009C	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (B-83)	1 EA		
0091	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	10 EA		
0092	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	41,200 LF		
009E	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	2,520 EA		
0094	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	790 EA		
009E	3557000000-E	866	ADDITIONAL BARBED WIRE	1,100 LF		
009E	3628000000-E	876	RIP RAP, CLASS I	120 TON		
0097	3649000000-E	876	RIP RAP, CLASS B	200 TON		
009E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	4,155 SY		
009E	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
010C	3691000000-N	SP	GENERIC EROSION CONTROL ITEM LEVEL SPREADER	4 EA		
0101	3691000000-N	SP	GENERIC EROSION CONTROL ITEM RIP-RAPPED ENERGY DISSIPATOR BASIN	1 EA		
0102	3972000000-E	SP	#57 STONE BACKFILL	260 TON		
010E	4048000000-E	902	REINFORCED CONCRETE SIGN FOUN- DATIONS	1 CY		
0104	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	495 LB		
010E	4082000000-E	903	SUPPORTS, WOOD	3,099 LF		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010E	4096000000-N	904	SIGN ERECTION, TYPE D	11 EA		
0107	4102000000-N	904	SIGN ERECTION, TYPE E	213 EA		
010E	4108000000-N	904	SIGN ERECTION, TYPE F	26 EA		
010E	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	1 EA		
011C	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	2 EA		
0111	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (F)	1 EA		
0112	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	50 EA		
011E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	914 SF		
0114	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	244 SF		
011E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	200 SF		
011E	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0117	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
011E	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	60 DAY		
011E	4430000000-N	1130	DRUMS	600 EA		
012C	4435000000-N	1135	CONES	50 EA		
0121	4445000000-E	1145	BARRICADES (TYPE III)	420 LF		
0122	4455000000-N	1150	FLAGGER	500 MD		
012E	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	3 EA		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0124	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	4	EA	
0125	4485000000-E	1170	PORTABLE CONCRETE BARRIER	700	LF	
0126	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	1,135	LF	
0127	4510000000-N	SP	LAW ENFORCEMENT	120	HR	
0128	4516000000-N	1180	SKINNY DRUM	50	EA	
0129	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	746	EA	
0130	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,427	LF	
0131	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	5,324	LF	
0132	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	92,617	LF	
0133	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	22,121	LF	
0134	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	14,265	LF	
0135	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	278	LF	
0136	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	71	EA	
0137	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	4,500	LF	
0138	4775000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (II)	1,564	LF	
0139	4780000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (8") (II)	435	LF	

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
014C	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (II)	1	EA	
0141	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	117,294	LF	
0142	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	13,500	LF	
0143	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	250	LF	
0144	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	121	EA	
014E	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	3,600	LF	
014E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	679	EA	
0147	5325400000-E	1510	4" WATER LINE	152	LF	
014E	5325600000-E	1510	6" WATER LINE	3,558	LF	
014E	5325800000-E	1510	8" WATER LINE	15,183	LF	
015C	5326200000-E	1510	12" WATER LINE	721	LF	
0151	5538000000-E	1515	4" VALVE	3	EA	
0152	5540000000-E	1515	6" VALVE	3	EA	
0153	5546000000-E	1515	8" VALVE	18	EA	
0154	5558000000-E	1515	12" VALVE	2	EA	
015E	5648000000-N	1515	RELOCATE WATER METER	23	EA	
015E	5649000000-N	1515	RECONNECT WATER METER	7	EA	
0157	5672000000-N	1515	RELOCATE FIRE HYDRANT	6	EA	
015E	5800000000-E	1530	ABANDON 6" UTILITY PIPE	3,277	LF	

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
015E	5801000000-E	1530	ABANDON 8" UTILITY PIPE	11,204 LF		
016C	5804000000-E	1530	ABANDON 12" UTILITY PIPE	422 LF		
0161	5871400000-E	1550	TRENCHLESS INSTALLATION OF 6" IN SOIL	275 LF		
0162	5871410000-E	1550	TRENCHLESS INSTALLATION OF 6" NOT IN SOIL	275 LF		
0163	5871500000-E	1550	TRENCHLESS INSTALLATION OF 8" IN SOIL	1,036 LF		
0164	5871510000-E	1550	TRENCHLESS INSTALLATION OF 8" NOT IN SOIL	1,036 LF		
016E	5871700000-E	1550	TRENCHLESS INSTALLATION OF 12" IN SOIL	24 LF		
016E	5871710000-E	1550	TRENCHLESS INSTALLATION OF 12" NOT IN SOIL	24 LF		
0167	6000000000-E	1605	TEMPORARY SILT FENCE	20,000 LF		
016E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	2,825 TON		
016E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	10,035 TON		
017C	6012000000-E	1610	SEDIMENT CONTROL STONE	5,750 TON		
0171	6015000000-E	1615	TEMPORARY MULCHING	100 ACR		
0172	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	3,250 LB		
0173	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	14 TON		
0174	6024000000-E	1622	TEMPORARY SLOPE DRAINS	5,000 LF		
017E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	100 EA		
017E	6029000000-E	SP	SAFETY FENCE	6,000 LF		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0177	6030000000-E	1630	SILT EXCAVATION	14,400 CY		
0178	6036000000-E	1631	MATTING FOR EROSION CONTROL	40,000 SY		
0179	6037000000-E	SP	COIR FIBER MAT	1,100 SY		
0180	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,415 SY		
0181	6042000000-E	1632	1/4" HARDWARE CLOTH	5,900 LF		
0182	6045000000-E	SP	*** TEMPORARY PIPE (18")	300 LF		
0183	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	500 SY		
0184	6070000000-N	SP	SPECIAL STILLING BASINS	10 EA		
0185	6071012000-E	SP	COIR FIBER WATTLE	3,000 LF		
0186	6071020000-E	SP	POLYACRYLAMIDE (PAM)	4,000 LB		
0187	6071030000-E	SP	COIR FIBER BAFFLES	2,000 LF		
0188	6071050000-E	SP	*** SKIMMER (1-1/2")	53 EA		
0189	6071050000-E	SP	*** SKIMMER (2")	1 EA		
0190	6084000000-E	1660	SEEDING & MULCHING	100 ACR		
0191	6087000000-E	1660	MOWING	100 ACR		
0192	6090000000-E	1661	SEED FOR REPAIR SEEDING	1,750 LB		
0193	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	5.5 TON		
0194	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	2,750 LB		
0195	6108000000-E	1665	FERTILIZER TOPDRESSING	82.25 TON		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0196	6111000000-E	SP	IMPERVIOUS DIKE	100 LF		
0197	6114500000-N	SP	SPECIALIZED HAND MOWING	100 MHR		
0198	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	75 EA		
0199	6123000000-E	1670	REFORESTATION	10 ACR		
0200	6138000000-E	SP	GENERIC EROSION CONTROL ITEM BORROW PIT DEWATERING BASIN	15,000 CY		

***** BEGIN SCHEDULE AB *****
***** (2 ALTERNATES) *****

0201 AB1	0043000000-N	226	GRADING	Lump Sum	L.S.	
0202 AB1	1121000000-E	520	AGGREGATE BASE COURSE	55,500 TON		
0203 AB1	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	43,990 TON		
0204 AB1	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	30,430 TON		
0205 AB1	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	3,460 TON		
*** OR ***						
0206 AB2	0043000000-N	226	GRADING	Lump Sum	L.S.	
0207 AB2	1121000000-E	520	AGGREGATE BASE COURSE	14,279 TON		
0208 AB2	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	52,940 TON		
0209 AB2	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	38,090 TON		
0210 AB2	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4,205 TON		

***** END SCHEDULE AB *****

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0211	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (54 + 34.00-L-LT)	Lump Sum	L.S.	
0212	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (54 + 34.00-L-RT)	Lump Sum	L.S.	
0213	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (222 + 51.50-L-RT)	Lump Sum	L.S.	
0214	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (54 + 34.00-L-LT)	Lump Sum	L.S.	
021E	8112730000-N	SP	PDA TESTING	1 EA		
021E	8112740000-N	SP	PDA ASSISTANCE	3 EA		
0217	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (222 + 51.50-L-LT)	Lump Sum	L.S.	
021E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (222 + 51.50-L-RT)	Lump Sum	L.S.	
021E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (54 + 34.00-L-LT)	Lump Sum	L.S.	
022C	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	30,516 SF		
0221	8161000000-E	420	GROOVING BRIDGE FLOORS	32,982 SF		
0222	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	480.8 CY		
0223	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (222 + 51.50-L-LT)	Lump Sum	L.S.	
0224	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (222 + 51.50-L-RT)	Lump Sum	L.S.	

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0225	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (54 + 34.00-L-LT)	Lump Sum	L.S.	
0226	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (54 + 34.00-L-RT)	Lump Sum	L.S.	
0227	8217000000-E	425	REINFORCING STEEL (BRIDGE)	67,733 LB		
0228	8259000000-E	430	36" PRESTRESSED CONCRETE GIR- DERS	1,432.81 LF		
0229	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	2,160.31 LF		
0230	8336000000-E	SP	20" PRESTRESSED CONC PILES	3,630 LF		
0231	8364000000-E	SP	HP12X53 STEEL PILES	2,465 LF		
0232	8384200000-E	SP	HP14X73 GALVANIZED STEEL PILES	2,240 LF		
0233	8393000000-N	SP	PILE REDRIVES	62 EA		
0234	8503000000-E	460	CONCRETE BARRIER RAIL	1,384.86 LF		
0235	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,175 TON		
0236	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,300 SY		
0237	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0238	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1231/Feb01/Q1412528.53/D930598262000/E238

Total Amount Of Bid For Entire Project :

Contract No **C202242**

County (ies): **Beaufort**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General