

County Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0038000000-E	SP	SHALLOW UNDERCUT	3,000 CY		
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	2 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	7,800 TON		
0008	0195000000-E	SP	SELECT GRANULAR MATERIAL	500 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	13,300 SY		
0010	0255000000-E	SP	GENERIC GRADING ITEM EXCAVATION AND STOCKPILING CONTAMINATED SOIL	700 TON		
0011	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	290 TON		
0012	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	890 SY		
0013	0366000000-E	SP	15" RC PIPE CULVERTS, CLASS III	1,366 LF		
0014	0372000000-E	SP	18" RC PIPE CULVERTS, CLASS III	356 LF		
0015	0378000000-E	SP	24" RC PIPE CULVERTS, CLASS III	188 LF		
0016	0390000000-E	SP	36" RC PIPE CULVERTS, CLASS III	732 LF		
0017	0995000000-E	340	PIPE REMOVAL	1,276 LF		
0018	0996000000-N	350	PIPE CLEAN-OUT	2 EA		

County Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1110000000-E	510	STABILIZER AGGREGATE	500 TON		
0020	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
0021	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 3")	12,880 SY		
0022	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,370 TON		
0023	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	7,370 TON		
0024	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	2,010 TON		
0025	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	2,730 TON		
0026	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4,560 TON		
0027	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	9,930 TON		
0028	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	960 TON		
0029	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	600 TON		
0030	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	180 TON		
0031	2022000000-E	SP	SUBDRAIN EXCAVATION	230 CY		
0032	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	170 CY		
0033	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
0034	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	2 EA		
0035	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	12 LF		

County Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	10 EA		
0037	2253000000-E	840	PIPE COLLARS	4 CY		
0038	2264000000-E	840	PIPE PLUGS	1 CY		
0039	2275000000-E	SP	FLOWABLE FILL	62 CY		
0040	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	71 EA		
0041	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	59.3 LF		
0042	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	6 EA		
0043	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	23 EA		
0044	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	2 EA		
0045	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0046	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0047	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	4 EA		
0048	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	14 EA		
0049	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	20 EA		
0050	2396000000-N	840	FRAME WITH COVER, STD 840.54	26 EA		
0051	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	3 EA		
0052	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	10,750 LF		

County Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	2556000000-E	846	SHOULDER BERM GUTTER	480 LF		
0054	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	6,120 LF		
0055	2591000000-E	848	4" CONCRETE SIDEWALK	2,460 SY		
0056	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	42 EA		
0057	2612000000-E	848	6" CONCRETE DRIVEWAY	90 SY		
0058	2627000000-E	852	4" CONCRETE ISLAND COVERS	200 SY		
0059	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	90 SY		
0060	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	1,120 SY		
0061	2703000000-E	854	CONCRETE BARRIER, TYPE ***** (III)	860 LF		
0062	2703000000-E	854	CONCRETE BARRIER, TYPE ***** (SINGLE FACED)	85 LF		
0063	2703000000-E	854	CONCRETE BARRIER, TYPE ***** (T-2)	70 LF		
0064	2710000000-N	854	CONCRETE BARRIER TRANSITION SECTION	11 EA		
0065	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	700 LF		
0066	2752000000-E	SP	GENERIC PAVING ITEM CONCRETE BARRIER, TYPE II WITH 18" GLARE SCREEN	580 LF		
0067	2759000000-N	SP	GENERIC PAVING ITEM EMERGENCY VEHICLE ACCESS	1 EA		
0068	2759000000-N	SP	GENERIC PAVING ITEM TRANS SECTION FROM CONC BAR- RIER TO MONO CONC ISLAND	2 EA		
0069	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	12 EA		
0070	2815000000-N	858	ADJUSTMENT OF DROP INLETS	2 EA		

County Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	2830000000-N	858	ADJUSTMENT OF MANHOLES	30 EA		
0072	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	71 EA		
0073	2860000000-N	859	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX	11 EA		
0074	2995000000-N	SP	GENERIC DRAINAGE ITEM CONVERT EXISTING CATCH BASIN TO TRAFF BEARING JTN BOX W/ MH COVER	7 EA		
0075	2995000000-N	SP	GENERIC DRAINAGE ITEM CONVERT EXISTING DROP INLET TO TRAFF BEARING JTN BOX W/ MH COVER	3 EA		
0076	2995000000-N	SP	GENERIC DRAINAGE ITEM CONVERT EXISTING DROP INLET TO TRAFFIC BEARING DROP INLET	3 EA		
0077	2995000000-N	SP	GENERIC DRAINAGE ITEM CONVERT EXISTING JUNCTION BOX TO CATCH BASIN	1 EA		
0078	2995000000-N	SP	GENERIC DRAINAGE ITEM CONVERT EXISTING JUNCTION BOX TO TRAFF BEARING JTN BOX W/ MH COVER	1 EA		
0079	2995000000-N	SP	GENERIC DRAINAGE ITEM CONVERT EXT OPEN THROAT CATCH BASIN TO TRAFFIC BEARING DROP INLET	1 EA		
0080	3030000000-E	862	STEEL BM GUARDRAIL	5,750 LF		
0081	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	150 LF		
0082	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	8 EA		
0083	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0084	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0085	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	21 EA		

County Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0086	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	24 EA		
0087	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	13 EA		
0088	3319000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-83	1 EA		
0089	3360000000-E	863	REMOVE EXISTING GUARDRAIL	2,720 LF		
0090	3533000000-E	866	CHAIN LINK FENCE, *** FABRIC (60")	605 LF		
0091	3533000000-E	866	CHAIN LINK FENCE, *** FABRIC (72")	2,170 LF		
0092	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	210 LF		
0093	3539000000-E	866	METAL LINE POSTS FOR *** CHAIN LINK FENCE (60")	55 EA		
0094	3539000000-E	866	METAL LINE POSTS FOR *** CHAIN LINK FENCE (72")	190 EA		
0095	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	20 EA		
0096	3545000000-E	866	METAL TERMINAL POSTS FOR *** CHAIN LINK FENCE (60")	20 EA		
0097	3545000000-E	866	METAL TERMINAL POSTS FOR *** CHAIN LINK FENCE (72")	25 EA		
0098	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	5 EA		
0099	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	2,000 SY		
0100	4048000000-E	902	REINFORCED CONCRETE SIGN FOUNDATIONS	10 CY		
0101	4057000000-E	SP	OVERHEAD FOOTING	120 CY		
0102	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	4,771 LB		

County Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0103	4066000000-E	903	SUPPORTS, SIMPLE STEEL BEAM	2,652 LB		
0104	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	2,942 LF		
0105	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (123+00 SBL)	Lump Sum	L.S.	
0106	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (132+00 SBL)	Lump Sum	L.S.	
0107	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (68+41NBL)	Lump Sum	L.S.	
0108	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (82+00 NBL)	Lump Sum	L.S.	
0109	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (86+00 SBL)	Lump Sum	L.S.	
0110	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (94+00 NBL)	Lump Sum	L.S.	
0111	4096000000-N	904	SIGN ERECTION, TYPE D	7 EA		
0112	4102000000-N	904	SIGN ERECTION, TYPE E	98 EA		
0113	4108000000-N	904	SIGN ERECTION, TYPE F	26 EA		
0114	4109000000-N	904	SIGN ERECTION, TYPE *** (OVERHEAD) (A)	4 EA		
0115	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	10 EA		
0116	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE ***** (GROUND MOUNTED) (B)	2 EA		
0117	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE ***** (GROUND MOUNTED) (D)	4 EA		

County Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0118	4138000000-N	907	DISPOSAL OF SUPPORT, STEEL BEAM	2 EA		
0119	4152000000-N	907	DISPOSAL OF SIGN SYSTEM, STEEL BEAM	18 EA		
0120	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	139 EA		
0121	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	5 EA		
0122	4234000000-N	907	DISPOSAL OF SIGN, A OR B (OVERHEAD)	6 EA		
0123	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	2,040 SF		
0124	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	1,528 SF		
0125	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	420 SF		
0126	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	11 EA		
0127	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	19 EA		
0128	4430000000-N	1130	DRUMS	611 EA		
0129	4445000000-E	1145	BARRICADES (TYPE III)	392 LF		
0130	4450000000-N	1150	FLAGGER	1,290 HR		
0131	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4 EA		
0132	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	3 EA		
0133	4480000000-N	1165	TMIA	2 EA		
0134	4485000000-E	1170	PORTABLE CONCRETE BARRIER	5,230 LF		
0135	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	1,033 LF		
0136	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	5,600 LF		

County Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0137	4507000000-E	SP	WATER FILLED BARRIER	200 LF		
0138	4508000000-E	SP	RESET WATER FILLED BARRIER	180 LF		
0139	4510000000-N	SP	LAW ENFORCEMENT	357 HR		
0140	4516000000-N	1180	SKINNY DRUM	180 EA		
0141	4590000000-E	SP	GENERIC TRAFFIC CONTROL ITEM SAFETY FENCE	1,160 LF		
0142	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	317 EA		
0143	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	295 LF		
0144	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	4,964 LF		
0145	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	140 EA		
0146	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	59,614 LF		
0147	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	1,095 LF		
0148	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	390 LF		
0149	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	38 EA		
0150	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (HIGHLY REFLECTIVE ELEMENTS)	24,318 LF		
0151	4847100000-E	1205	POLYUREA PAVEMENT MARKING LINES (6", *****) (HIGHLY REFLECTIVE ELEMENTS)	8,355 LF		
0152	4847120000-E	1205	POLYUREA PAVEMENT MARKING LINES (12", *****) (HIGHLY REFLECTIVE ELEMENTS)	1,265 LF		
0153	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	19,506 LF		

County Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0154	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	150	LF	
0155	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	34	EA	
0156	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	119	EA	
0157	4945000000-N	1267	FLEXIBLE DELINEATORS (CRYSTAL & RED)	5	EA	
0158	5020000000-N	1401	PORTABLE DRIVE UNIT	1	EA	
0159	5025000000-E	1402	HIGH MOUNT FOUNDATIONS	51	CY	
0160	5030000000-N	1403	HIGH MOUNT LUMINAIRES ***** (400W HPS)	60	EA	
0161	5030000000-N	1403	HIGH MOUNT LUMINAIRES ***** (750W HPS)	18	EA	
0162	5050000000-N	1404	LIGHT STANDARD, TYPE MTLT ***** (45' HIEGHT, "SA" 15' ARM)	4	EA	
0163	5080000000-N	1406	LIGHT STANDARD LUMINAIRES, TYPE ***** (250W HPS)	4	EA	
0164	5120000000-N	1407	ELECTRIC SERVICE POLE **** ***** (30' CLASS 4)	2	EA	
0165	5125000000-E	1407	ELECTRIC SERVICE LATERAL ***** (3,31/0 USE)	200	LF	
0166	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (2")	340	LF	
0167	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (3")	80	LF	
0168	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (3")	640	LF	

County Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0169	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (4")	265 LF		
0170	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (6")	35 LF		
0171	5175000000-E	1410	** #6 W/G FEEDER CIRCUIT (2)	430 LF		
0172	5180000000-E	1410	** #4 W/G FEEDER CIRCUIT (2)	870 LF		
0173	5205000000-E	1410	** #8 W/G FEEDER CIRCUIT IN ***** CONDUIT (CONDUIT 2, 1 1/2)	1,600 LF		
0174	5210000000-E	1410	** #6 W/G FEEDER CIRCUIT IN ***** CONDUIT (CONDUIT 2, 1 1/2)	3,900 LF		
0175	5215000000-E	1410	** #4 W/G FEEDER CIRCUIT IN ***** CONDUIT (CONDUIT 2, 1 1/2)	3,000 LF		
0176	5220000000-E	1410	** #2 W/G FEEDER CIRCUIT IN ***** CONDUIT (CONDUIT 2, 1 1/2)	150 LF		
0177	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC18)	34 EA		
0178	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC36)	3 EA		
0179	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0180	5270000000-N	SP	GENERIC LIGHTING ITEM 100' HIGH MOUNT STANDARD	3 EA		
0181	5270000000-N	SP	GENERIC LIGHTING ITEM 60' HIGH MOUNT STANDARD	1 EA		
0182	5270000000-N	SP	GENERIC LIGHTING ITEM 80' HIGH MOUNT STANDARD	7 EA		
0183	5270000000-N	SP	GENERIC LIGHTING ITEM LIGHT CONTROL EQUIPMENT, RW, 240/480V	2 EA		

County Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0184	5270000000-N	SP	GENERIC LIGHTING ITEM REMOVE LIGHT STANDARD	26 EA		
0185	6000000000-E	1605	TEMPORARY SILT FENCE	9,000 LF		
0186	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	1,765 TON		
0187	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	575 TON		
0188	6012000000-E	1610	SEDIMENT CONTROL STONE	2,500 TON		
0189	6015000000-E	1615	TEMPORARY MULCHING	20 ACR		
0190	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	600 LB		
0191	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2.5 TON		
0192	6024000000-E	1622	TEMPORARY SLOPE DRAINS	500 LF		
0193	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	10 EA		
0194	6030000000-E	1630	SILT EXCAVATION	1,080 CY		
0195	6036000000-E	1631	MATTING FOR EROSION CONTROL	15,000 SY		
0196	6042000000-E	1632	1/4" HARDWARE CLOTH	9,225 LF		
0197	6071010000-E	SP	WATTLE	450 LF		
0198	6071020000-E	SP	POLYACRYLAMIDE (PAM)	160 LB		
0199	6071030000-E	SP	COIR FIBER BAFFLES	100 LF		
0200	6084000000-E	1660	SEEDING & MULCHING	31 ACR		
0201	6087000000-E	1660	MOWING	15 ACR		
0202	6090000000-E	1661	SEED FOR REPAIR SEEDING	250 LB		
0203	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.75 TON		

County Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0204	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	475 LB		
0205	6108000000-E	1665	FERTILIZER TOPDRESSING	13.75 TON		
0206	6114500000-N	SP	SPECIALIZED HAND MOWING	20 MHR		
0207	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		
0208	7000000000-E	1705	PEDESTRIAN SIGNAL HEAD (**, ** SECTION) (16', 1 SECTION WITH COUNTDOWN)	62 EA		
0209	7060000000-E	1705	SIGNAL CABLE	15,275 LF		
0210	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	51 EA		
0211	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	10 EA		
0212	7216000000-N	SP	MODIFY EXISTING VEHICLE SIGNAL HEAD	7 EA		
0213	7252000000-E	1710	MESSENGER CABLE (1/4")	18,805 LF		
0214	7264000000-E	1710	MESSENGER CABLE (3/8")	1,900 LF		
0215	7279000000-E	1715	TRACER WIRE	47,700 LF		
0216	7288000000-E	1715	PAVED TRENCHING (***** (1, 2")	80 LF		
0217	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	1,700 LF		
0218	7300000000-E	1715	UNPAVED TRENCHING (***** (2, 2")	36,300 LF		
0219	7301000000-E	1715	DIRECTIONAL DRILL (***** (2, 2")	17,195 LF		
0220	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	40 EA		
0221	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEA- VY DUTY)	157 EA		

County · Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0222	7360000000-N	1720	WOOD POLE	23 EA		
0223	7372000000-N	1721	GUY ASSEMBLY	98 EA		
0224	7396000000-E	1722	1/2" RISER WITH WEATHERHEAD	30 EA		
0225	7408000000-E	1722	1" RISER WITH WEATHERHEAD	8 EA		
0226	7420000000-E	1722	2" RISER WITH WEATHERHEAD	36 EA		
0227	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	47 EA		
0228	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	11,900 LF		
0229	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	26,000 LF		
0230	7484000000-N	SP	MICROWAVE VEHICLE DETECTOR	77 EA		
0231	7504000000-E	SP	COMMUNICATIONS CABLE (** TWISTED-PAIR) (25)	2,680 LF		
0232	7516000000-E	1730	COMMUNICATIONS CABLE (**FIBER) (12)	100 LF		
0233	7516000000-E	1730	COMMUNICATIONS CABLE (**FIBER) (144)	28,900 LF		
0234	7516000000-E	1730	COMMUNICATIONS CABLE (**FIBER) (72)	60,400 LF		
0235	7528000000-E	1730	DROP CABLE	12,900 LF		
0236	7540000000-N	1731	SPLICE ENCLOSURE	56 EA		
0237	7552000000-N	1731	INTERCONNECT CENTER	55 EA		
0238	7566000000-N	1733	DELINEATOR MARKER	50 EA		
0239	7575142000-N	SP	900MHZ WIRELESS RADIO SYSTEM	16 EA		
0240	7575142100-N	SP	900MHZ WIRELESS REPEATER STANDALONE RADIO SYSTEM	2 EA		

County Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0241	7575142200-N	SP	NEW ELECTRICAL SERVICE	71 EA		
0242	7575160000-E	1734	REMOVE EXISTING COMMUNICATIONS CABLE	1,380 LF		
0243	7575180000-N	1735	CABLE TRANSFER	10 EA		
0244	7624000000-N	1743	SIGNAL PEDESTAL WITH FOUNDATION	9 EA		
0245	7636000000-N	1745	SIGN FOR SIGNALS	14 EA		
0246	7648000000-N	SP	RELOCATE EXISTING SIGN	12 EA		
0247	7684000000-N	1750	SIGNAL CABINET FOUNDATION	3 EA		
0248	7828000000-N	1751	CONTROLLER WITH CABINET (NEMA TS-2, TYPE 2 CONTROLLER, TYPE 1 CABINET, BASE MOUNTED)	5 EA		
0249	7840000000-N	1751	CONTROLLER WITH CABINET (NEMA TS-2, TYPE 2 CONTROLLER, TYPE 1 CABINET, POLE MOUNTED)	1 EA		
0250	7852000000-N	1751	DETECTOR CARD (NEMA TS-2)	25 EA		
0251	7948000000-N	SP	TRAFFIC SIGNAL REMOVAL	7 EA		
0252	7980000000-N	SP	GENERIC SIGNAL ITEM 2.4/5.8 GHZ WIRELESS RADIO SYSTEM	2 EA		
0253	7980000000-N	SP	GENERIC SIGNAL ITEM 2.4/5.8 GHZ WIRELESS REPEATER STANDALONE RADIO SYSTEM	3 EA		
0254	7980000000-N	SP	GENERIC SIGNAL ITEM CCTV CAMERA ASSEMBLY	18 EA		
0255	7980000000-N	SP	GENERIC SIGNAL ITEM CONDUIT ENTRANCE INTO EXISTING FOUNDATION	4 EA		
0256	7980000000-N	SP	GENERIC SIGNAL ITEM DMS ACCESS LADDER	4 EA		
0257	7980000000-N	SP	GENERIC SIGNAL ITEM ELECTRICAL SERVICE DIS- CONNECT	1 EA		

County Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0258	7980000000-N	SP	GENERIC SIGNAL ITEM ETHERNET CORE SWITCH	1 EA		
0259	7980000000-N	SP	GENERIC SIGNAL ITEM ETHERNET ROUTING SWITCH	1 EA		
0260	7980000000-N	SP	GENERIC SIGNAL ITEM FIELD EQUIPMENT CABINET	71 EA		
0261	7980000000-N	SP	GENERIC SIGNAL ITEM FIELD ETHERNET SWITCH	58 EA		
0262	7980000000-N	SP	GENERIC SIGNAL ITEM FIELD VIDEO CODEC UNIT	20 EA		
0263	7980000000-N	SP	GENERIC SIGNAL ITEM FRONT ACCESS ENCLOSURE DMS	6 EA		
0264	7980000000-N	SP	GENERIC SIGNAL ITEM FULL SPAN OVERHEAD STRUCTURE FOR WALK-IN DMS	2 EA		
0265	7980000000-N	SP	GENERIC SIGNAL ITEM MODIFY EXISTING SPLICE ENCLO- SURE	5 EA		
0266	7980000000-N	SP	GENERIC SIGNAL ITEM PEDESTAL TYPE STRUCTURE FOR FRONT ACCESS DMS	6 EA		
0267	7980000000-N	SP	GENERIC SIGNAL ITEM PEDESTAL TYPE STRUCTURE FOR WALK-IN DMS	2 EA		
0268	7980000000-N	SP	GENERIC SIGNAL ITEM WALK-IN ENCLOSURE DMS	5 EA		
0269	7980000000-N	SP	GENERIC SIGNAL ITEM WOOD POLE (CCTV)	16 EA		
0270	7980000000-N	SP	GENERIC SIGNAL ITEM WOOD POLE (MVD)	58 EA		
0271	7985000000-N	SP	GENERIC SIGNAL ITEM DIVISION 9 HARDWARE & SOFTWARE CONFIGURATION	Lump Sum	L.S.	
0272	7985000000-N	SP	GENERIC SIGNAL ITEM LAN INTEGRATION	Lump Sum	L.S.	

County Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0273	7985000000-N	SP	GENERIC SIGNAL ITEM TRAINING	Lump Sum	L.S.	
0274	7985000000-N	SP	GENERIC SIGNAL ITEM TRTMC HARDWARE & SOFTWARE CONFIGURATION	Lump Sum	L.S.	
0275	7985000000-N	SP	GENERIC SIGNAL ITEM TRUCK ROLLOVER SYSTEM	Lump Sum	L.S.	
0276	7990000000-E	SP	GENERIC SIGNAL ITEM ETHERNET CABLE (OUTDOOR RATED)	1,100 LF		
0277	7992000000-E	SP	GENERIC SIGNAL ITEM FOOTINGS FOR DMS STRUCTURE	80 CY		
0278	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (69+00.00-L-)	Lump Sum	L.S.	
0280	8839000000-E	SP	GENERIC RETAINING WALL ITEM CONCRETE BARRIER RAIL WITH MOMENT SLAB	242 LF		
0281	8847000000-E	SP	GENERIC RETAINING WALL ITEM CIP GRAVITY RETAINING WALLS	1,779 SF		
0282	8839000000-E	SP	GENERIC RETAINING WALL ITEM STEEL PIPE HANDRAIL	216 LF		
0859/Apr12/Q609153.3/D1320432046300/E281			Total Amount Of Bid For Entire Project			

Contract No **C202598**

County (ies): **Forsyth**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General