

County Duplin, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	4,033 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	300 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	12.68 SMI		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (4")	96,518 SY		
0006	1330000000-E	607	INCIDENTAL MILLING	550 SY		
0007	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	24,517 TON		
0008	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	12,242 TON		
0009	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,180 TON		
0010	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	722 TON		
0011	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	66,951 LF		
0012	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	75,187 LF		
0013	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,950 LF		
0014	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	100 LF		
0015	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	12 EA		
0016	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	45 EA		
0017	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	142,138 LF		

County Duplin, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	1,950	LF	
001E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	100	LF	
002C	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	12	EA	
0021	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	45	EA	
002Z	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	639	EA	
002E	6000000000-E	1605	TEMPORARY SILT FENCE	1,042	LF	
0024	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	260	TON	
002E	6012000000-E	1610	SEDIMENT CONTROL STONE	260	TON	
002E	6015000000-E	1615	TEMPORARY MULCHING	10	ACR	
0027	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	521	LB	
002E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	3	TON	
002E	6036000000-E	1631	MATTING FOR EROSION CONTROL	70	SY	
003C	6042000000-E	1632	1/4" HARDWARE CLOTH	521	LF	
0031	6071010000-E	SP	WATTLE	160	LF	
003Z	6084000000-E	1660	SEEDING & MULCHING	20	ACR	

1522/Mar24/Q432071.68/D128934110000/E32

Total Amount Of Bid For Entire Project :

Contract No **C202764**

County (ies): **Duplin, Sampson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General