

County Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0038000000-E	SP	SHALLOW UNDERCUT	2,100 CY		
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	4,100 TON		
0007	0195000000-E	SP	SELECT GRANULAR MATERIAL	500 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	7,600 SY		
0009	0199000000-E	SP	TEMPORARY SHORING	2,970 SF		
0010	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	853 TON		
0011	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	2,210 SY		
0012	0335000000-E	SP	*** DRAINAGE PIPE (10")	36 LF		
0013	0335200000-E	SP	15" DRAINAGE PIPE	176 LF		
0014	0335300000-E	SP	18" DRAINAGE PIPE	28 LF		
0015	0335400000-E	SP	24" DRAINAGE PIPE	12 LF		
0016	0335500000-E	SP	30" DRAINAGE PIPE	88 LF		
0017	0335600000-E	SP	36" DRAINAGE PIPE	44 LF		
0018	0335850000-E	SP	*** DRAINAGE PIPE ELBOWS (10")	2 EA		

County Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0448000000-E	SP	***** RC PIPE CULVERTS, CLASS IV (12")	4 LF		
0020	0448200000-E	SP	15" RC PIPE CULVERTS, CLASS IV	3,752 LF		
0021	0448300000-E	SP	18" RC PIPE CULVERTS, CLASS IV	824 LF		
0022	0448400000-E	SP	24" RC PIPE CULVERTS, CLASS IV	1,332 LF		
0023	0448500000-E	SP	30" RC PIPE CULVERTS, CLASS IV	340 LF		
0024	0995000000-E	340	PIPE REMOVAL	5,028 LF		
0025	1110000000-E	510	STABILIZER AGGREGATE	1,000 TON		
0026	1121000000-E	520	AGGREGATE BASE COURSE	45 TON		
0027	1220000000-E	545	INCIDENTAL STONE BASE	1,000 TON		
0028	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	24,220 SY		
0029	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	350 TON		
0030	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	12,800 TON		
0031	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	7,100 TON		
0032	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	6,400 TON		
0033	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	100 TON		
0034	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	910 TON		
0035	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	385 TON		

County Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0037	2022000000-E	SP	SUBDRAIN EXCAVATION	224 CY		
003E	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	168 CY		
003E	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
004C	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	2 EA		
0041	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0042	2253000000-E	840	PIPE COLLARS	3.4 CY		
004E	2264000000-E	840	PIPE PLUGS	0.232 CY		
0044	2275000000-E	SP	FLOWABLE FILL	10 CY		
004E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	74 EA		
004E	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	32.38 LF		
0047	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	8 EA		
004E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
004E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
005C	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	7 EA		
0051	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	27 EA		
0052	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	24 EA		
005E	2396000000-N	840	FRAME WITH COVER, STD 840.54	5 EA		

County Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	2440000000-N	852	CONCRETE TRANSITIONAL SECTION FOR CATCH BASIN	3 EA		
005E	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	320 LF		
005E	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	9,400 LF		
0057	2591000000-E	848	4" CONCRETE SIDEWALK	5,340 SY		
005E	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	27 EA		
005E	2612000000-E	848	6" CONCRETE DRIVEWAY	380 SY		
006C	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	110 SY		
0061	2759000000-N	SP	GENERIC PAVING ITEM DETECTABLE WARNINGS	4 EA		
0062	2995000000-N	SP	GENERIC DRAINAGE ITEM CONVERT EXISTING JB TOP TO TBJB W/ MH COVER	1 EA		
0063	3628000000-E	876	RIP RAP, CLASS I	30 TON		
0064	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,205 SY		
006E	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
006E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	550 LF		
0067	4102000000-N	904	SIGN ERECTION, TYPE E	56 EA		
006E	4108000000-N	904	SIGN ERECTION, TYPE F	1 EA		
006E	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	4 EA		
007C	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	24 EA		
0071	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	1 EA		

County Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	4	EA	
0073	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	240	SF	
0074	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	369	SF	
007E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	78	SF	
007E	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2	EA	
0077	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2	EA	
007E	4430000000-N	1130	DRUMS	325	EA	
007E	4445000000-E	1145	BARRICADES (TYPE III)	96	LF	
008C	4455000000-N	1150	FLAGGER	200	MD	
0081	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2	EA	
0082	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	2	EA	
0083	4480000000-N	1165	TMIA	2	EA	
0084	4485000000-E	1170	PORTABLE CONCRETE BARRIER	480	LF	
008E	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	480	LF	
008E	4507000000-E	SP	WATER FILLED BARRIER	500	LF	
0087	4508000000-E	SP	RESET WATER FILLED BARRIER	500	LF	
008E	4516000000-N	1180	SKINNY DRUM	30	EA	
008E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	1,000	EA	
009C	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	14,763	LF	

County Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	106 LF		
0092	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	958 LF		
0093	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	28 EA		
0094	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	91 EA		
009E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	55,129 LF		
009E	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	76 LF		
0097	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,084 LF		
009E	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	12 EA		
009E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	162 EA		
010C	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	23,960 LF		
0101	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	578 LF		
0102	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	90 LF		
0103	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	88 EA		
0104	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	186 EA		
010E	5325800000-E	1510	8" WATER LINE	26 LF		
010E	5326600000-E	1510	16" WATER LINE	1,100 LF		
0107	5546000000-E	1515	8" VALVE	1 EA		

County Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010E	5648000000-N	1515	RELOCATE WATER METER	18 EA		
010E	5672000000-N	1515	RELOCATE FIRE HYDRANT	6 EA		
011C	5691300000-E	1520	8" SANITARY GRAVITY SEWER	231 LF		
0111	5775000000-E	1525	4' DIA UTILITY MANHOLE	2 EA		
0112	5801000000-E	1530	ABANDON 8" UTILITY PIPE	300 LF		
0113	5810000000-E	1530	ABANDON 16" UTILITY PIPE	1,062 LF		
0114	5816000000-N	1530	ABANDON UTILITY MANHOLE	1 EA		
011E	5882000000-N	SP	GENERIC UTILITY ITEM ADJUST MANHOLE	5 EA		
011E	5882000000-N	SP	GENERIC UTILITY ITEM RECONNECT FIRE HYDRANT	1 EA		
0117	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	900 TON		
011E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	270 TON		
011E	6012000000-E	1610	SEDIMENT CONTROL STONE	1,000 TON		
012C	6015000000-E	1615	TEMPORARY MULCHING	9.5 ACR		
0121	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	250 LB		
0122	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1 TON		
0123	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0124	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
012E	6029000000-E	SP	SAFETY FENCE	1,300 LF		
012E	6030000000-E	1630	SILT EXCAVATION	650 CY		

County Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0127	6036000000-E	1631	MATTING FOR EROSION CONTROL	7,700 SY		
012E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	20 SY		
012S	6042000000-E	1632	1/4" HARDWARE CLOTH	4,100 LF		
013C	6071010000-E	SP	WATTLE	120 LF		
0131	6071020000-E	SP	POLYACRYLAMIDE (PAM)	20 LB		
013Z	6071030000-E	SP	COIR FIBER BAFFLES	150 LF		
013Z	6084000000-E	1660	SEEDING & MULCHING	9 ACR		
0134	6087000000-E	1660	MOWING	6 ACR		
013E	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
013E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0137	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	175 LB		
013E	6108000000-E	1665	FERTILIZER TOPDRESSING	5 TON		
013S	6114500000-N	SP	SPECIALIZED HAND MOWING	12 MHR		
014C	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0141	6123000000-E	1670	REFORESTATION	0.1 ACR		
014Z	7000000000-E	1705	PEDESTRIAN SIGNAL HEAD (***, ** SECTION) (16" 1 SECTION W/ COUNTDOWN)	6 EA		
014Z	7060000000-E	1705	SIGNAL CABLE	2,060 LF		
0144	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	7 EA		
014E	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	5 EA		

County Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
014E	7252000000-E	1710	MESSENGER CABLE (1/4")	725	LF	
0147	7264000000-E	1710	MESSENGER CABLE (3/8")	680	LF	
014E	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	1,625	LF	
014E	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	9	EA	
015C	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEAVY DUTY)	2	EA	
0151	7360000000-N	1720	WOOD POLE	4	EA	
0152	7372000000-N	1721	GUY ASSEMBLY	6	EA	
0153	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1	EA	
0154	7420000000-E	1722	2" RISER WITH WEATHERHEAD	3	EA	
015E	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	2,340	LF	
015E	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	5,580	LF	
0157	7528000000-E	1730	DROP CABLE	350	LF	
015E	7552000000-N	1731	INTERCONNECT CENTER	2	EA	
015E	7575180000-N	1735	CABLE TRANSFER	4	EA	
016C	7576000000-N	SP	METAL STRAIN SIGNAL POLE	4	EA	
0161	7613000000-N	SP	SOIL TEST	4	EA	
0162	7614100000-E	SP	DRILLED PIER FOUNDATION	20	CY	
0163	7636000000-N	1745	SIGN FOR SIGNALS	11	EA	
0164	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1	EA	

County Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
016E	7720000000-N	1751	CONTROLLER WITH CABINET (TYPE 170E, BASE MOUNTED)	1	EA	
016E	7744000000-N	1751	DETECTOR CARD (TYPE 170)	6	EA	
0167	7901000000-N	1753	CABINET BASE EXTENDER	1	EA	
016E	7980000000-N	SP	GENERIC SIGNAL ITEM SCHOOL FLASHER	2	EA	
016E	8802030000-E	SP	SEGMENTAL GRAVITY RETAINING WALLS	1,150	SF	

***** BEGIN SCHEDULE AA *****
 ***** (2 ALTERNATES) *****

017C	6000000000-E	1605	TEMPORARY SILT FENCE	6,900	LF	
AA1						

*** OR ***

0171	6147000000-E	SP	GENERIC EROSION CONTROL ITEM TEMPORARY SILT FENCE WITH WOODEN POSTS	6,900	LF	
AA2						

***** END SCHEDULE AA *****

0930/Apr04/Q255694.862/D715966020000/E171

Total Amount Of Bid For Entire Project :

Contract No **C202164**

County (ies): **Durham**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General