

County Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	1,490 CY		
0003	1110000000-E	510	STABILIZER AGGREGATE	925 TON		
0004	1220000000-E	545	INCIDENTAL STONE BASE	768 TON		
0005	1243000000-E	SP	SHOULDER CONSTRUCTION	5.7 SMI		
0006	1245000000-E	SP	SHOULDER RECONSTRUCTION	17.4 SMI		
0007	1264000000-E	SP	DITCHING	852 LF		
0008	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	40,250 SY		
0009	1330000000-E	607	INCIDENTAL MILLING	270 SY		
001C	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,700 TON		
0011	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0C	9,230 TON		
0012	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	7,925 TON		
0013	1520000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)	1,460 TON		
0014	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	11,640 TON		
0015	1524000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5C (LEVELING COURSE)	190 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,088 TON		
0017	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	707 TON		

County · Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1704000000-E	SP	PATCHING EXISTING PAVEMENT	4,690 TON		
001S	2612000000-E	848	6" CONCRETE DRIVEWAY	276 SY		
002C	2738000000-E	SP	GENERIC PAVING ITEM REMOVAL OF CONCRETE ISLAND	222 SY		
0021	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	3 EA		
0022	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
0023	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	91,300 LF		
0024	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	60,913 LF		
002E	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	460 LF		
0026	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	247 LF		
0027	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	29 EA		
002E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	12 EA		
002S	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	260,462 LF		
003C	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	460 LF		
0031	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	75 LF		
0032	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	1,476 EA		
0033	6000000000-E	1605	TEMPORARY SILT FENCE	2,151 LF		

County Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	236	TON	
003E	6012000000-E	1610	SEDIMENT CONTROL STONE	118	TON	
003E	6071010000-E	SP	WATTLE	1,725	LF	
0037	6071020000-E	SP	POLYACRYLAMIDE (PAM)	4	LB	
003E	6084000000-E	1660	SEEDING & MULCHING	2.8	ACR	

1331/Mar23/Q503381.9/D119344130000/E38

Total Amount Of Bid For Entire Project :

Contract No **C202766**

County (ies): **Union**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General