

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-M	200	CLEARING & GRUBBING .. HECTARE(S)	Lump Sum	L.S.	
0003	0008000000-M	200	SUPPLEMENTARY CLEARING & GRUB- BING	0.8 HA		
0004	0015000000-N	205	SEALING ABANDONED WELLS	15 EA		
0005	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (14+27.310 -Y1-REV)	Lump Sum	L.S.	
0006	0036000000-M	225	UNDERCUT EXCAVATION	3,000 M3		
0007	0038000000-M	SP	SHALLOW UNDERCUT	1,000 M3		
0008	0080000000-M	SP	CLASS IV SUBGRADE STABILIZA- TION	2,500 MTN		
0009	0134000000-M	240	DRAINAGE DITCH EXCAVATION	4,158 M3		
0010	0141000000-M	240	BERM DITCH CONSTRUCTION	770 M		
0011	0156000000-M	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	29,400 M2		
0012	0177000000-M	250	BREAKING OF EXISTING ASPHALT PAVEMENT	3,700 M2		
0013	0192000000-N	260	PROOF ROLLING	30 HR		
0014	0195000000-M	SP	SELECT GRANULAR MATERIAL	3,000 M3		
0015	0196000000-M	270	FABRIC FOR SOIL STABILIZATION	7,790 M2		
0016	0199000000-M	SP	TEMPORARY SHORING	1,722 M2		
0017	0255000000-M	SP	GENERIC GRADING ITEM EXCAVATING AND STOCKPILING CONTAMINATED SOIL	100 MTN		
0018	0318000000-M	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	1,700 MTN		

County Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0320000000-M	SP	FOUNDATION CONDITIONING FABRIC	5,110 M2		
0020	0342000000-M	SP	****MM SIDE DRAIN PIPE (750MM)	345.6 M		
0021	0342000000-M	SP	****MM SIDE DRAIN PIPE (900MM)	20.4 M		
0022	0343000000-M	SP	375MM SIDE DRAIN PIPE	1,177.2 M		
0023	0344000000-M	SP	450MM SIDE DRAIN PIPE	554.4 M		
0024	0345000000-M	SP	600MM SIDE DRAIN PIPE	616.8 M		
0025	0348000000-M	SP	***MM SIDE DRAIN PIPE ELBOWS (375MM)	16 EA		
0026	0348000000-M	SP	***MM SIDE DRAIN PIPE ELBOWS (450MM)	13 EA		
0027	0348000000-M	SP	***MM SIDE DRAIN PIPE ELBOWS (600MM)	7 EA		
0028	0366000000-M	SP	375MM RC PIPE CULVERTS, CLASS III	502.8 M		
0029	0372000000-M	SP	450MM RC PIPE CULVERTS, CLASS III	229.2 M		
0030	0378000000-M	SP	600MM RC PIPE CULVERTS, CLASS III	436.8 M		
0031	0384000000-M	SP	750MM RC PIPE CULVERTS, CLASS III	135.6 M		
0032	0396000000-M	SP	1050MM RC PIPE CULVERTS, CLASS III	39.6 M		
0033	0408000000-M	SP	1350MM RC PIPE CULVERTS, CLASS III	33.6 M		
0034	0420000000-M	SP	1650MM RC PIPE CULVERTS, CLASS III	55.2 M		
0035	0426000000-M	SP	1800MM RC PIPE CULVERTS, CLASS III	294 M		

County Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	0448200000-M	SP	375MM RC PIPE CULVERTS, CLASS IV	358.8 M		
0037	0448400000-M	SP	600MM RC PIPE CULVERTS, CLASS IV	36 M		
0038	0576000000-M	SP	***MM CS PIPE CULVERTS, ****MM THICK (1400MM, 2.77MM)	42 M		
0039	0576000000-M	SP	***MM CS PIPE CULVERTS, ****MM THICK (1500MM, 3.51MM)	18 M		
0040	0582000000-M	SP	400MM CS PIPE CULVERTS, 1.63MM THICK	28.8 M		
0041	0588000000-M	SP	450MM CS PIPE CULVERTS, 1.63MM THICK	444 M		
0042	0636000000-M	SP	***MM CS PIPE ELBOWS, ****MM THICK (400MM, 1.63MM)	2 EA		
0043	0995000000-M	340	PIPE REMOVAL	1,890 M		
0044	1000000000-M	462	150MM SLOPE PROTECTION	200 M2		
0045	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0046	1044000000-M	501	LIME TREATED SOIL (SLURRY METHOD)	24,400 M2		
0047	1066000000-M	501	LIME FOR LIME TREATED SOIL	270 MTN		
0048	1110000000-M	510	STABILIZER AGGREGATE	1,000 MTN		
0049	1176000000-M	542	SOIL CEMENT BASE	24,400 M2		
0050	1187000000-M	542	PORTLAND CEMENT FOR SOIL CEMENT BASE	740 MTN		
0051	1209000000-M	543	ASPHALT CURING SEAL	33,220 L		
0052	1220000000-M	545	INCIDENTAL STONE BASE	9,300 MTN		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	1297000000-M	607	MILLING ASPHALT PAVEMENT, **MM DEPTH (40MM)	200	M2	
0054	1503000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	18,730	MTN	
0055	1523000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	14,430	MTN	
0056	1565000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	870	MTN	
0057	1693000000-M	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	200	MTN	
0058	2022000000-M	SP	SUBDRAIN EXCAVATION	830	M3	
0059	2033000000-M	SP	SUBDRAIN FINE AGGREGATE	420	M3	
0060	2044000000-M	SP	150MM PERFORATED SUBDRAIN PIPE	1,000	M	
0061	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	7	EA	
0062	2077000000-M	SP	150MM OUTLET PIPE (SUBDRAINS)	14	M	
0063	2143000000-M	818	BLOTTING SAND	10	MTN	
0064	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	5	EA	
0065	2209000000-M	838	ENDWALLS	8	M3	
0066	2220000000-M	838	REINFORCED ENDWALLS	16	M3	
0067	2253000000-M	840	PIPE COLLARS	6	M3	
0068	2264000000-M	840	PIPE PLUGS	3	M3	
0069	2275000000-M	SP	FLOWABLE FILL	145	M3	
0070	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	99	EA	
0071	2297000000-M	840	MASONRY DRAINAGE STRUCTURES	18	M3	

County Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	2308000000-M	840	MASONRY DRAINAGE STRUCTURES	4.47 M		
0073	2354200000-N	840	FRAME WITH GRATE, STD 840.24	2 EA		
0074	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	9 EA		
0075	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	3 EA		
0076	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	58 EA		
0077	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	15 EA		
0078	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1 EA		
0079	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	5 EA		
0080	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	5 EA		
0081	2396000000-N	840	FRAME WITH COVER, STD 840.54	5 EA		
0082	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	7 EA		
0083	2549000000-M	846	750MM CONCRETE CURB & GUTTER	885 M		
0084	2556000000-M	846	SHOULDER BERM GUTTER	30 M		
0085	2591000000-M	848	100MM CONCRETE SIDEWALK	910 M2		
0086	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	12 EA		
0087	2612000000-M	848	150MM CONCRETE DRIVEWAY	360 M2		
0088	2619000000-M	850	100MM CONCRETE PAVED DITCH	177.3 M2		
0089	2647000000-M	852	125MM MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	830 M2		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	2724000000-M	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	68.8 M		
0091	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	21 EA		
0092	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	2 EA		
0093	3030000000-M	862	STEEL BM GUARDRAIL	1,805.94 M		
0094	3045000000-M	862	STEEL BM GUARDRAIL, SHOP CURVED	99.06 M		
0095	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	2 EA		
0096	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0097	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0098	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	8 EA		
0099	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	14 EA		
0100	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	6 EA		
0101	3345000000-M	864	REMOVE & RESET EXISTING GUARDRAIL	80 M		
0102	3360000000-M	863	REMOVE EXISTING GUARDRAIL	955 M		
0103	3380000000-M	862	TEMPORARY STEEL BM GUARDRAIL	1,165.86 M		
0104	3382000000-M	862	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)	198.12 M		
0105	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (AT-1)	3 EA		
0106	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (B-77)	2 EA		

County Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (W-BEAM)	2 EA		
0108	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	14 EA		
0109	3503000000-M	866	WOVEN WIRE FENCE, 1200MM FABRIC	252 M		
0110	3509000000-M	866	100MM TIMBER FENCE POSTS, 2.30M LONG	44 EA		
0111	3515000000-M	866	125MM TIMBER FENCE POSTS, 2.50M LONG	30 EA		
0112	3536000000-M	866	CHAIN LINK FENCE, 1200MM FABRIC	2,500 M		
0113	3542000000-M	866	METAL LINE POSTS FOR 1200MM CHAIN LINK FENCE	690 EA		
0114	3548000000-M	866	METAL TERMINAL POSTS FOR 1200MM CHAIN LINK FENCE	40 EA		
0115	3557000000-M	866	ADDITIONAL BARBED WIRE	50 M		
0116	3566000000-M	867	WOVEN WIRE FENCE RESET	130 M		
0117	3595000000-M	869	RELAPPING GUARDRAIL	200 M		
0118	3628000000-M	876	RIP RAP, CLASS I	580 MTN		
0119	3635000000-M	876	RIP RAP, CLASS II	1,010 MTN		
0120	3649000000-M	876	RIP RAP, CLASS B	1,300 MTN		
0121	3651000000-M	SP	BOULDERS	25 MTN		
0122	3656000000-M	876	FILTER FABRIC FOR DRAINAGE	14,830 M2		
0123	4048000000-M	902	REINFORCED CONCRETE SIGN FOUNDATIONS	5 M3		
0124	4054000000-M	902	PLAIN CONCRETE SIGN FOUNDATIONS	1 M3		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0125	4060000000-M	903	SUPPORTS, BREAKAWAY STEEL BEAM	1,868 KG		
0126	4072000000-M	903	SUPPORTS, 4.5-KG STEEL U-CHANN EL	595 M		
0127	4096000000-N	904	SIGN ERECTION, TYPE D	8 EA		
0128	4102000000-N	904	SIGN ERECTION, TYPE E	85 EA		
0129	4108000000-N	904	SIGN ERECTION, TYPE F	12 EA		
0130	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	6 EA		
0131	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	2 EA		
0132	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	2 EA		
0133	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	92 EA		
0134	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	1 EA		
0135	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	4 EA		
0136	4400000000-M	1110	WORK ZONE SIGNS (STATIONARY)	126 M2		
0137	4405000000-M	1110	WORK ZONE SIGNS (PORTABLE)	27 M2		
0138	4410000000-M	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	44 M2		
0139	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0140	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4 EA		
0141	4430000000-N	1130	DRUMS	410 EA		
0142	4435000000-N	1135	CONES	70 EA		

County Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0143	4445000000-M	1145	BARRICADES (TYPE III)	420 M		
0144	4450000000-N	1150	FLAGGER	2,735 HR		
0145	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4 EA		
0146	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	1 EA		
0147	4480000000-N	1165	TMIA	1 EA		
0148	4485000000-M	1170	PORTABLE CONCRETE BARRIER	570 M		
0149	4500000000-M	1170	RESET PORTABLE CONCRETE BARRIER	115 M		
0150	4510000000-N	SP	LAW ENFORCEMENT	32 HR		
0151	4516000000-N	1180	SKINNY DRUM	50 EA		
0152	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	894 EA		
0153	4685000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 2.3MM)	19,116 M		
0154	4686000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 3.1MM)	9,842 M		
0155	4695000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (200MM, 2.3MM)	2,126 M		
0156	4697000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (200MM, 3.1MM)	78 M		
0157	4710000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (600MM, 3.1MM)	432 M		
0158	4721000000-M	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (3.1MM)	20 EA		
0159	4725000000-M	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (2.3MM)	76 EA		
0160	4770000000-M	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (100MM) (I)	214 M		

County Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0161	4780000000-M	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (200MM) (I)	140 M		
0162	4810000000-M	1205	PAINT PAVEMENT MARKING LINES (100MM)	61,883 M		
0163	4820000000-M	1205	PAINT PAVEMENT MARKING LINES (200MM)	1,894 M		
0164	4835000000-M	1205	PAINT PAVEMENT MARKING LINES (600MM)	196 M		
0165	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	55 EA		
0166	4850000000-M	1205	REMOVAL OF PAVEMENT MARKING LINES (100MM)	6,320 M		
0167	4870000000-M	1205	REMOVAL OF PAVEMENT MARKING LINES (600MM)	65 M		
0168	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	635 EA		
0169	4915000000-M	1264	2.1M U-CHANNEL POSTS	3 EA		
0170	4935000000-N	1267	FLEXIBLE DELINEATORS (CRYSTAL)	67 EA		
0171	4940000000-N	1267	FLEXIBLE DELINEATORS (YELLOW)	34 EA		
0172	4945000000-N	1267	FLEXIBLE DELINEATORS (CRYSTAL & RED)	6 EA		
0173	4950000000-N	1267	FLEXIBLE DELINEATORS (YELLOW & RED)	5 EA		
0174	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	3 EA		
0175	5325600000-M	1510	150MM WATER LINE	203 M		
0176	5325800000-M	1510	200MM WATER LINE	861 M		
0177	5326200000-M	1510	300MM WATER LINE	54 M		
0178	5540000000-M	1515	150MM VALVE	1 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0179	5546000000-M	1515	200MM VALVE	3 EA		
0180	5643000000-M	1515	***MM WATER METER (25MM)	5 EA		
0181	5648000000-N	1515	RELOCATE WATER METER	12 EA		
0182	5666000000-M	1515	FIRE HYDRANT	3 EA		
0183	5672000000-N	1515	RELOCATE FIRE HYDRANT	5 EA		
0184	5709200000-M	1520	100MM FORCE MAIN SEWER	6 M		
0185	5801000000-M	1530	ABANDON 200MM UTILITY PIPE	688 M		
0186	6000000000-M	1605	TEMPORARY SILT FENCE	9,665 M		
0187	6006000000-M	1610	STONE FOR EROSION CONTROL, CLASS A	6,465 MTN		
0188	6009000000-M	1610	STONE FOR EROSION CONTROL, CLASS B	2,775 MTN		
0189	6012000000-M	1610	SEDIMENT CONTROL STONE	3,145 MTN		
0190	6015000000-M	1615	TEMPORARY MULCHING	37 HA		
0191	6018000000-M	1620	SEED FOR TEMPORARY SEEDING	1,550 KG		
0192	6021000000-M	1620	FERTILIZER FOR TEMPORARY SEED- ING	11.25 MTN		
0193	6024000000-M	1622	TEMPORARY SLOPE DRAINS	1,400 M		
0194	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	23 EA		
0195	6029000000-M	SP	SAFETY FENCE	1,400 M		
0196	6030000000-M	1630	SILT EXCAVATION	15,400 M3		
0197	6036000000-M	1631	MATTING FOR EROSION CONTROL	61,500 M2		
0198	6037000000-M	SP	COIR FIBER MAT	560 M2		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0199	6038000000-M	SP	PERMANENT SOIL REINFORCEMENT MAT	6,400 M2		
0200	6042000000-M	1632	6.4MM HARDWARE CLOTH	1,800 M		
0201	6069000000-M	1638	STILLING BASINS	780 M3		
0202	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
0203	6071012000-M	SP	COIR FIBER WATTLE	2,250 M		
0204	6071020000-M	SP	POLYACRYLAMIDE (PAM)	2,250 KG		
0205	6071030000-M	SP	COIR FIBER BAFFLES	2,500 M		
0206	6071050000-M	SP	***MM SKIMMER (38MM)	16 EA		
0207	6071050000-M	SP	***MM SKIMMER (51MM)	3 EA		
0208	6084000000-M	1660	SEEDING & MULCHING	59 HA		
0209	6087000000-M	1660	MOWING	37 HA		
0210	6090000000-M	1661	SEED FOR REPAIR SEEDING	1,150 KG		
0211	6093000000-M	1661	FERTILIZER FOR REPAIR SEEDING	4 MTN		
0212	6096000000-M	1662	SEED FOR SUPPLEMENTAL SEEDING	950 KG		
0213	6108000000-M	1665	FERTILIZER TOPDRESSING	56.5 MTN		
0214	6111000000-M	SP	IMPERVIOUS DIKE	780 M		
0215	6114500000-N	SP	SPECIALIZED HAND MOWING	35 MHR		
0216	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	75 EA		
0217	6120000000-M	SP	CULVERT DIVERSION CHANNEL	712 M3		
0218	6123000000-M	1670	REFORESTATION	4 HA		

County Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0219	7060000000-M	1705	SIGNAL CABLE	450 M		
0220	7120000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 3 SECTION)	11 EA		
0221	7132000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 4 SECTION)	1 EA		
0222	7144000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 5 SECTION)	1 EA		
0223	7264000000-M	1710	MESSENGER CABLE (9.52MM)	180 M		
0224	7300000000-M	1715	UNPAVED TRENCHING (***** (1, 50MM)	225 M		
0225	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	6 EA		
0226	7360000000-N	1720	WOOD POLE	4 EA		
0227	7372000000-N	1721	GUY ASSEMBLY	8 EA		
0228	7408000000-M	1722	25MM RISER WITH WEATHERHEAD	1 EA		
0229	7420000000-M	1722	50MM RISER WITH WEATHERHEAD	4 EA		
0230	7444000000-M	1725	INDUCTIVE LOOP SAWCUT	870 M		
0231	7456000000-M	1726	LEAD-IN CABLE (***** (14-2)	1,350 M		
0232	7636000000-N	1745	SIGN FOR SIGNALS	3 EA		
0233	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1 EA		
0234	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	1 EA		
0235	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	10 EA		
0236	7901000000-N	1753	CABINET BASE EXTENDER	1 EA		

County Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
***** BEGIN SCHEDULE AA ***** ***** (2 ALTERNATES) *****						
0237 AA1	0022000000-M	225	UNCLASSIFIED EXCAVATION	247,000 M3		
0238 AA1	0106000000-M	230	BORROW EXCAVATION	2,500 M3		
0239 AA1	1121000000-M	520	AGGREGATE BASE COURSE	53,100 MTN		
0240 AA1	1275000000-M	600	PRIME COAT	6,320 L		
0241 AA1	1489000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	890 MTN		
0242 AA1	1491000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	3,490 MTN		
0243 AA1	1498000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	8,230 MTN		
0244 AA1	1519000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	7,820 MTN		
0245 AA1	1560000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,925 MTN		
*** OR ***						
0246 AA2	0022000000-M	225	UNCLASSIFIED EXCAVATION	240,000 M3		
0247 AA2	0106000000-M	230	BORROW EXCAVATION	13,000 M3		
0248 AA2	1121000000-M	520	AGGREGATE BASE COURSE	3,410 MTN		
0249 AA2	1489000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	10,750 MTN		
0250 AA2	1491000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	16,750 MTN		
0251 AA2	1498000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	7,980 MTN		
0252 AA2	1519000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	7,870 MTN		
0253 AA2	1560000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	2,915 MTN		

***** END SCHEDULE AA *****

County Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
CULVERT ITEMS						
0254	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12+68.320-Y1-REV)	Lump Sum	L.S.	
0255	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (200+54.650-L-REV)	Lump Sum	L.S.	
0256	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (212+28.000-L-REV)	Lump Sum	L.S.	
0257	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (219+37.800-L-REV)	Lump Sum	L.S.	
0258	8126000000-N	414	CULVERT EXCAVATION, STA ***** (12+11.600-Y16-REV)	Lump Sum	L.S.	
0259	8126000000-N	414	CULVERT EXCAVATION, STA ***** (12+68.320-Y1-REV)	Lump Sum	L.S.	
0260	8126000000-N	414	CULVERT EXCAVATION, STA ***** (200+54.650-L-REV)	Lump Sum	L.S.	
0261	8126000000-N	414	CULVERT EXCAVATION, STA ***** (218+46.294-L-REV)	Lump Sum	L.S.	
0262	8126000000-N	414	CULVERT EXCAVATION, STA ***** (219+37.800-L-REV)	Lump Sum	L.S.	
0263	8133000000-M	414	FOUNDATION CONDITIONING MATER- IAL, BOX CULVERT	1,260 MTN		
0264	8196000000-M	420	CLASS A CONCRETE (CULVERT)	2,214.7 M3		
0265	8245000000-M	425	REINFORCING STEEL (CULVERT)	204,820 KG		
0266	8590000000-M	876	RIP RAP, CLASS ** (II)	40 MTN		
0267	8804000000-N	SP	GENERIC CULVERT ITEM (PRECAST REINF CONC THREE-SIDE D CULVERT @ STA.212+28.000-L-REV)	Lump Sum	L.S.	

County . Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0268	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (221+70.114-L-REV)	Lump Sum	L.S.	
0269	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1,221+70.114-L-REV) (221+70.114 -L-REV)	Lump Sum	L.S.	
0270	8147000000-M	420	REINFORCED CONCRETE DECK SLAB	1,920.9 M2		
0271	8161000000-M	420	GROOVING BRIDGE FLOORS	2,021 M2		
0272	8182000000-M	420	CLASS A CONCRETE (BRIDGE)	262.3 M3		
0273	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (221+70.114-L-REV)	Lump Sum	L.S.	
0274	8217000000-M	425	REINFORCING STEEL (BRIDGE)	22,533 KG		
0275	8238000000-M	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,218 KG		
0276	8280000000-M	440	APPROX KG STRUCTURAL STEEL	292,900 LS		
0277	8364000000-M	SP	HP310X79 STEEL PILES	370 M		
0278	8503000000-M	460	CONCRETE BARRIER RAIL	141.65 M		
0279	8531000000-M	462	100MM SLOPE PROTECTION	1,055 M2		
0280	8650000000-N	SP	POT BEARINGS	Lump Sum	L.S.	
0281	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0282	8706000000-N	SP	EXPANSION JOINT SEALS	Lump Sum	L.S.	

Contract No: C202596

County: Cabarrus

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General