

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+57.00)	Lump Sum	L.S.	
0003	0038000000-E	SP	SHALLOW UNDERCUT	20 CY		
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	40 TON		
0007	0195000000-E	SP	SELECT GRANULAR MATERIAL	20 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	45 SY		
0009	0255000000-E	SP	GENERIC GRADING ITEM EXCAVATE AND STOCKPILE CONTAMINATED SOIL	100 TON		
0010	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	55 TON		
0011	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	170 SY		
0012	0342000000-E	SP	*** SIDE DRAIN PIPE (18")	68 LF		
0013	0342000000-E	SP	*** SIDE DRAIN PIPE (30")	64 LF		
0014	0366000000-E	SP	15" RC PIPE CULVERTS, CLASS III	60 LF		
0015	0384000000-E	SP	30" RC PIPE CULVERTS, CLASS III	172 LF		
0016	0448200000-E	SP	15" RC PIPE CULVERTS, CLASS IV	112 LF		
0017	0588000000-E	SP	18" CS PIPE CULVERTS, 0.064" THICK	12 LF		
0018	0995000000-E	340	PIPE REMOVAL	272 LF		

County Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1121000000-E	520	AGGREGATE BASE COURSE	500 TON		
0020	1220000000-E	545	INCIDENTAL STONE BASE	175 TON		
0021	1275000000-E	600	PRIME COAT	270 GAL		
0022	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1-1/2" TO 3")	2,500 SY		
0023	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	740 TON		
0024	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	275 TON		
0025	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	820 TON		
0026	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	45 TON		
0027	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	50 TON		
0028	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	247 TON		
0029	2253000000-E	840	PIPE COLLARS	1 CY		
0030	2264000000-E	840	PIPE PLUGS	1 CY		
0031	2275000000-E	SP	FLOWABLE FILL	10 CY		
0032	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	11 EA		
0033	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	23 LF		
0034	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	4 EA		
0035	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	4 EA		
0036	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1,700 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2591000000-E	848	4" CONCRETE SIDEWALK	690 SY		
0038	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	11 EA		
0039	2612000000-E	848	6" CONCRETE DRIVEWAY	380 SY		
0040	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	2 EA		
0041	2830000000-N	858	ADJUSTMENT OF MANHOLES	10 EA		
0042	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	12 EA		
0043	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III, SHOP CURVED)	1 EA		
0044	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1 EA		
0045	3649000000-E	876	RIP RAP, CLASS B	5 TON		
0046	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,516 SY		
0047	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	370 LF		
0048	4102000000-N	904	SIGN ERECTION, TYPE E	20 EA		
0049	4108000000-N	904	SIGN ERECTION, TYPE F	4 EA		
0050	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	15 EA		
0051	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	760 SF		
0052	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	723 SF		
0053	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	266 SF		
0054	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0055	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4430000000-N	1130	DRUMS	142 EA		
0057	4435000000-N	1135	CONES	50 EA		
0058	4445000000-E	1145	BARRICADES (TYPE III)	314 LF		
0059	4450000000-N	1150	FLAGGER	2,160 HR		
0060	4480000000-N	1165	TMIA	3 EA		
0061	4510000000-N	SP	LAW ENFORCEMENT	64 HR		
0062	4516000000-N	1180	SKINNY DRUM	100 EA		
0063	4520000000-N	1266	TUBULAR MARKERS (FIXED)	36 EA		
0064	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	125 EA		
0065	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	24,438 LF		
0066	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	1,344 LF		
0067	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,150 LF		
0068	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	48 EA		
0069	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	121 EA		
0070	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	4,240 LF		
0071	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	50 LF		
0072	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	244 LF		
0073	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	47 EA		
0074	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	75 EA		

County · Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	5326200000-E	1510	12" WATER LINE	347.4	LF	
0076	5546000000-E	1515	8" VALVE	3	EA	
0077	5552000000-E	1515	10" VALVE	4	EA	
0078	5709500000-E	1520	10" FORCE MAIN SEWER	351.4	LF	
0079	5773000000-N	SP	UTILITY VAULT	1	EA	
0080	5775000000-E	1525	4' DIA UTILITY MANHOLE	1	EA	
0081	5801000000-E	1530	ABANDON 8" UTILITY PIPE	390	LF	
0082	5802000000-E	1530	ABANDON 10" UTILITY PIPE	269	LF	
0083	5871600000-E	1550	TRENCHLESS INSTALLATION OF 10" IN SOIL	182.5	LF	
0084	5871610000-E	1550	TRENCHLESS INSTALLATION OF 10" NOT IN SOIL	182.5	LF	
0085	5871700000-E	1550	TRENCHLESS INSTALLATION OF 12" IN SOIL	174	LF	
0086	5871710000-E	1550	TRENCHLESS INSTALLATION OF 12" NOT IN SOIL	174	LF	
0087	5888000000-E	SP	GENERIC UTILITY ITEM 10" DI RESTRAINED JOINT WATER PIPE, PC 350	52.1	LF	
0088	5888000000-E	SP	GENERIC UTILITY ITEM 8" DI RESTRAINED JOINT FORCE MAIN SEWER PIPE, PC 350	174.1	LF	
0089	6000000000-E	1605	TEMPORARY SILT FENCE	3,100	LF	
0090	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	365	TON	
0091	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	100	TON	
0092	6012000000-E	1610	SEDIMENT CONTROL STONE	500	TON	

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0094	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0095	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0096	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0097	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0098	6029000000-E	SP	SAFETY FENCE	850 LF		
0099	6030000000-E	1630	SILT EXCAVATION	220 CY .		
0100	6036000000-E	1631	MATTING FOR EROSION CONTROL	7,000 SY		
0101	6042000000-E	1632	1/4" HARDWARE CLOTH	1,000 LF		
0102	6070000000-N	SP	SPECIAL STILLING BASINS	12 EA		
0103	6071010000-E	SP	WATTLE	130 LF		
0104	6071020000-E	SP	POLYACRYLAMIDE (PAM)	35 LB		
0105	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0106	6087000000-E	1660	MOWING	1 ACR		
0107	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0108	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0109	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0110	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0111	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
0112	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0113	6123000000-E	1670	REFORESTATION	0.1 ACR		
0114	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	2 EA		
0115	7252000000-E	1710	MESSENGER CABLE (1/4")	1,175 LF		
0116	7279000000-E	1715	TRACER WIRE	350 LF		
0117	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	80 LF		
0118	7301000000-E	1715	DIRECTIONAL DRILL (*****) (1, 2")	350 LF		
0119	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	1 EA		
0120	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEAVY DUTY)	4 EA		
0121	7372000000-N	1721	GUY ASSEMBLY	6 EA		
0122	7420000000-E	1722	2" RISER WITH WEATHERHEAD	1 EA		
0123	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	2 EA		
0124	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	110 LF		
0125	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	130 LF		
0126	7552000000-N	1731	INTERCONNECT CENTER	2 EA		
0127	7566000000-N	1733	DELINEATOR MARKER	2 EA		
0128	7575180000-N	1735	CABLE TRANSFER	2 EA		
0129	7636000000-N	1745	SIGN FOR SIGNALS	13 EA		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
WALL ITEMS						
0130	8847000000-E	SP	GENERIC RETAINING WALL ITEM SHEET PILE RETAINING WALLS	743 SF		
STRUCTURE ITEMS						
0131	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (17+57.00-L-)	Lump Sum	L.S.	
0132	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+57.00-L-)	Lump Sum	L.S.	
0133	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	265 LF		
0134	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	102 LF		
0135	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	85.5 LF		
0136	8113000000-N	SP	SID INSPECTION	6 EA		
0137	8114000000-N	SP	SPT TESTING	6 EA		
0138	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17+57.00-L-)	Lump Sum	L.S.	
0139	8156000000-E	SP	CONCRETE WEARING SURFACE	9,500 SF		
0140	8161000000-E	420	GROOVING BRIDGE FLOORS	10,234 SF		
0141	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	124.9 CY		
0142	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	151 CY		
0143	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+57.00-L-)	Lump Sum	L.S.	
0144	8217000000-E	425	REINFORCING STEEL (BRIDGE)	40,113 LB		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0145	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	4,157 LB		
0146	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	8,438 LB		
0147	8364000000-E	SP	HP12X53 STEEL PILES	1,065 LF		
0148	8590000000-E	876	RIP RAP, CLASS ** (I)	100 TON		
0149	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	310 TON		
0150	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	345 SY		
0151	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0152	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0153	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	4,227.5 LF		
0154	8867000000-E	SP	GENERIC STRUCTURE ITEM 1'-5" X 3'-6" CONCRETE BARRIER RAIL	445.5 LF		
0155	8897000000-N	SP	GENERIC STRUCTURE ITEM CSL TESTING	1 EA		

0707/Jun09/Q146841.25/D762903010000/E155

Total Amount Of Bid For Entire Project :

Contract No **C202566**

County (ies): **Haywood**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General