

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	395 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	1,065 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	18.88 SMI		
000E	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	66,500 SY		
000E	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (3" TO 4-1/2")	35,400 SY		
0007	1330000000-E	607	INCIDENTAL MILLING	5,965 SY		
000E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	4,275 TON		
000E	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	5,760 TON		
001C	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	8,465 TON		
0011	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	13,360 TON		
0012	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,323 TON		
0013	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	508 TON		
0014	1704000000-E	SP	PATCHING EXISTING PAVEMENT	1,338 TON		
001E	1880000000-E	SP	GENERIC PAVING ITEM JOINT REPAIR	170 TON		
001E	2830000000-N	858	ADJUSTMENT OF MANHOLES	54 EA		
0017	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	51 EA		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
001E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	74,200 LF		
002C	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	99,100 LF		
0021	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	400 LF		
0022	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	880 LF		
0023	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,372 LF		
0024	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	166 EA		
002E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	186,400 LF		
002E	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	500 LF		
0027	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	300 LF		
002E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	716 EA		
002E	6000000000-E	1605	TEMPORARY SILT FENCE	949 LF		
003C	6071010000-E	SP	WATTLE	160 LF		
0031	6084000000-E	1660	SEEDING & MULCHING	13.7 ACR		
0032	6090000000-E	1661	SEED FOR REPAIR SEEDING	485 LB		
0033	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	3 TON		

County : Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	21,000 LF		

0935/Jun13/Q531294.58/D114864110000/E34

Total Amount Of Bid For Entire Project :

**Contract No**     **C202794**

**County (ies):**   **Lee**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

**Contract Officer**

---

**Date**

**Execution of Contract and Bonds  
Approved as to Form:**

---

**Attorney General**