

County : Montgomery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	865 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	465 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	21.5 SMI		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	212,904 SY		
0006	1330000000-E	607	INCIDENTAL MILLING	4,425 SY		
0007	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	7,105 TON		
0008	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	44,135 TON		
0009	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	5,025 TON		
0010	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	754 TON		
0011	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	2,648 TON		
0012	1814000000-E	660	ASPHALT SURFACE TREATMENT, STRAIGHT SEAL	23,748 SY		
0013	2830000000-N	858	ADJUSTMENT OF MANHOLES	1 EA		
0014	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	1 EA		
0015	4510000000-N	SP	LAW ENFORCEMENT	40 HR		
0016	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
0017	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	26,493 LF		
0018	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	24,559 LF		

County : Montgomery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	260,750 LF		
0020	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	30,660 LF		
0021	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	400 LF		
0022	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	12,000 LF		
0023	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	200 LF		
0024	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	469 LF		
0025	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	8 EA		
0026	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	40 EA		
0027	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	1,200 LF		
0028	4775000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (III)	1,900 LF		
0029	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	211,700 LF		
0030	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	3,196 EA		
0031	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0032	6000000000-E	1605	TEMPORARY SILT FENCE	1,368 LF		
0033	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	344 TON		
0034	6012000000-E	1610	SEDIMENT CONTROL STONE	344 TON		
0035	6015000000-E	1615	TEMPORARY MULCHING	13.68 ACR		

County : Montgomery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	6036000000-E	1631	MATTING FOR EROSION CONTROL	130		SY
0037	6042000000-E	1632	1/4" HARDWARE CLOTH	684		LF
0038	6071010000-E	SP	WATTLE	250		LF
0039	6084000000-E	1660	SEEDING & MULCHING	16.64		ACR
0040	6090000000-E	1661	SEED FOR REPAIR SEEDING	700		LB
0041	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	4		TON

1241/Jun14/Q879569.82/D161445110000/E41

Total Amount Of Bid For Entire Project :

Contract No **C202800**

County (ies): **Montgomery**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General