

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (21 + 47.24)	Lump Sum	L.S.	
0003	0036000000-E	225	UNDERCUT EXCAVATION	15,100 CY		
0004	0038000000-E	SP	SHALLOW UNDERCUT	500 CY		
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	500 TON		
0008	0106000000-E	230	BORROW EXCAVATION	361,400 CY		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	2,210 CY		
0010	0192000000-N	260	PROOF ROLLING	20 HR		
0011	0194000000-E	SP	SELECT GRANULAR MATERIAL, CLASS III	18,250 CY		
0012	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	16,900 SY		
0013	0199000000-E	SP	TEMPORARY SHORING	1,647 SF		
0014	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	800 TON		
0015	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	5,567 SY		
0016	0343000000-E	SP	15" SIDE DRAIN PIPE	496 LF		
0017	0344000000-E	SP	18" SIDE DRAIN PIPE	80 LF		
0018	0348000000-E	SP	*** SIDE DRAIN PIPE ELBOWS (15")	10 EA		

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0348000000-E	SP	*** SIDE DRAIN PIPE ELBOWS (18")	2	EA	
002C	0448000000-E	SP	***** RC PIPE CULVERTS, CLASS IV (66")	388	LF	
0021	0448200000-E	SP	15" RC PIPE CULVERTS, CLASS IV	2,528	LF	
0022	0448300000-E	SP	18" RC PIPE CULVERTS, CLASS IV	608	LF	
0023	0448400000-E	SP	24" RC PIPE CULVERTS, CLASS IV	364	LF	
0024	0448500000-E	SP	30" RC PIPE CULVERTS, CLASS IV	248	LF	
002E	0448600000-E	SP	36" RC PIPE CULVERTS, CLASS IV	884	LF	
002E	0995000000-E	340	PIPE REMOVAL	829	LF	
0027	1000000000-E	462	6" SLOPE PROTECTION	1,567	SY	
002E	1077000000-E	SP	#57 STONE	20	TON	
002E	1110000000-E	510	STABILIZER AGGREGATE	4,000	TON	
003C	1121000000-E	520	AGGREGATE BASE COURSE	27,400	TON	
0031	1220000000-E	545	INCIDENTAL STONE BASE	1,000	TON	
0032	1275000000-E	600	PRIME COAT	19,250	GAL	
0033	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	3,850	SY	
0034	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	6,050	SY	
003E	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (4")	2,310	SY	

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 3")	1,430	SY	
0037	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,070	TON	
0038	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	860	TON	
0039	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	7,440	TON	
0040	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	430	TON	
0041	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	11,270	TON	
0042	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	2,970	TON	
0043	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,130	TON	
0044	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	180	TON	
0045	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	500	TON	
0046	2000000000-N	806	RIGHT OF WAY MARKERS	73	EA	
0047	2022000000-E	SP	SUBDRAIN EXCAVATION	1,160	CY	
0048	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	580	CY	
0049	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	3,450	LF	
0050	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	7	EA	
0051	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	42	LF	
0052	2209000000-E	838	ENDWALLS	10.2	CY	

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	2220000000-E	838	REINFORCED ENDWALLS	6.3 CY		
0054	2253000000-E	840	PIPE COLLARS	3.431 CY		
005E	2264000000-E	840	PIPE PLUGS	0.116 CY		
0056	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	84 EA		
0057	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	4.92 CY		
005E	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	16.51 LF		
0059	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	13 EA		
006C	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	8 EA		
0061	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	3 EA		
0062	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0063	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	11 EA		
0064	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	23 EA		
006E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	16 EA		
006E	2396000000-N	840	FRAME WITH COVER, STD 840.54	6 EA		
0067	2440000000-N	852	CONCRETE TRANSITIONAL SECTION FOR CATCH BASIN	8 EA		
006E	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	8 EA		
0069	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	6,540 LF		

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007C	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	7,820 LF		
0071	2556000000-E	846	SHOULDER BERM GUTTER	1,222 LF		
0072	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	290 LF		
0073	2591000000-E	848	4" CONCRETE SIDEWALK	1,480 SY		
0074	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	10 EA		
007E	2612000000-E	848	6" CONCRETE DRIVEWAY	220 SY		
007E	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	1,630 SY		
0077	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	224 LF		
007E	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	1 EA		
007E	2815000000-N	858	ADJUSTMENT OF DROP INLETS	1 EA		
008C	2830000000-N	858	ADJUSTMENT OF MANHOLES	1 EA		
0081	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	1 EA		
0082	2938000000-N	SP	CONVERT EXISTING DROP INLET TO JUNCTION BOX WITH MANHOLE COVER	1 EA		
0083	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	3 EA		
0084	3030000000-E	862	STEEL BM GUARDRAIL	2,250 LF		
008E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	100 LF		
008E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0087	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	3 EA		

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
008E	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	2 EA		
009C	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	12 EA		
0091	3345000000-E	864	REMOVE & RESET EXISTING GUARDRAIL	1,312.5 LF		
0092	3347000000-E	864	REMOVE & RESET EXISTING GUIDERAIL	650 LF		
0093	3375000000-E	SP	REMOVE & STOCKPILE EXISTING GUARDRAIL	656.37 LF		
0094	3389600000-N	865	CABLE GUIDERAIL ANCHOR UNITS	4 EA		
009E	3420000000-E	SP	GENERIC GUARDRAIL ITEM REMOVE EXISTING CABLE GUIDERAIL	540 LF		
009E	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	3,400 LF		
0097	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	230 EA		
009E	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	40 EA		
009E	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	2,404 LF		
010C	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	200 EA		
0101	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	14 EA		
0102	3628000000-E	876	RIP RAP, CLASS I	135 TON		
0103	3649000000-E	876	RIP RAP, CLASS B	860 TON		
0104	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	4,250 SY		

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010E	3659000000-N	SP	PERFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	8 EA		
010E	4048000000-E	902	REINFORCED CONCRETE SIGN FOUNDATIONS	12 CY		
0107	4057000000-E	SP	OVERHEAD FOOTING	60 CY		
010E	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	6,754 LB		
010E	4066000000-E	903	SUPPORTS, SIMPLE STEEL BEAM	2,547 LB		
011C	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	1,017 LF		
0111	4078000000-E	903	SUPPORTS, 2-LB STEEL U-CHANNEL	2 EA		
0112	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (32 + 20.48 -Y2-)	Lump Sum	L.S.	
011E	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (47 + 50 -Y2-)	Lump Sum	L.S.	
0114	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (50 + 00 -Y2-)	Lump Sum	L.S.	
011E	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (77 + 00 -Y2-)	Lump Sum	L.S.	
011E	4102000000-N	904	SIGN ERECTION, TYPE E	51 EA		
0117	4108000000-N	904	SIGN ERECTION, TYPE F	8 EA		
011E	4109000000-N	904	SIGN ERECTION, TYPE *** (OVERHEAD) (A)	2 EA		
011E	4109000000-N	904	SIGN ERECTION, TYPE *** (OVERHEAD) (B)	2 EA		
012C	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	11 EA		

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0121	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	3 EA		
0122	4114000000-N	904	SIGN ERECTION, MILEMARKERS	2 EA		
0123	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (A)	1 EA		
0124	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	1 EA		
012E	4138000000-N	907	DISPOSAL OF SUPPORT, STEEL BEAM	2 EA		
012E	4152000000-N	907	DISPOSAL OF SIGN SYSTEM, STEEL BEAM	1 EA		
0127	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	8 EA		
012E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	504 SF		
012E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	706 SF		
013C	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	566 SF		
0131	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	4 EA		
0132	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	5 EA		
0133	4430000000-N	1130	DRUMS	588 EA		
0134	4445000000-E	1145	BARRICADES (TYPE III)	426 LF		
013E	4450000000-N	1150	FLAGGER	1,920 HR		
013E	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	3 EA		
0137	4480000000-N	1165	TMIA	4 EA		
013E	4485000000-E	1170	PORTABLE CONCRETE BARRIER	3,052 LF		

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
013E	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	2,100 LF		
014C	4510000000-N	SP	LAW ENFORCEMENT	480 HR		
0141	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	192 EA		
0142	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	30,975 LF		
0143	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	15,998 LF		
0144	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	3,914 LF		
014E	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	191 LF		
014E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	765 LF		
0147	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	32 EA		
014E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	104 EA		
014E	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	8,221 LF		
015C	4775000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (IV)	1,156 LF		
0151	4780000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (8") (IV)	346 LF		
0152	4800000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING CHARACTER, TYPE ** (IV)	2 EA		
0153	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (IV)	4 EA		

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0154	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	99,211 LF		
015E	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	1,410 LF		
015E	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	6,797 LF		
0157	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,591 LF		
015E	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	18 EA		
015E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	212 EA		
016C	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (HIGHLY REFLECTIVE ELEMENTS)	1,001 LF		
0161	4847110000-E	1205	POLYUREA PAVEMENT MARKING LINES (8", *****) (HIGHLY REFLECTIVE ELEMENTS)	346 LF		
0162	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	3,990 LF		
016E	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	55 LF		
0164	4880000000-E	1205	CURING COMPOUND REMOVAL, LINES	1,681 LF		
016E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	17 EA		
016E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	822 EA		
0167	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
016E	5325600000-E	1510	6" WATER LINE	162 LF		
016E	5325800000-E	1510	8" WATER LINE	123 LF		
017C	5326200000-E	1510	12" WATER LINE	861 LF		

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0171	5326600000-E	1510	16" WATER LINE	985	LF	
0172	5540000000-E	1515	6" VALVE	2	EA	
0173	5558600000-E	1515	16" VALVE	2	EA	
0174	5571800000-E	1515	8" TAPPING VALVE	2	EA	
0175	5572200000-E	1515	12" TAPPING VALVE	4	EA	
0176	5606000000-E	1515	2" BLOW OFF	1	EA	
0177	5648000000-N	1515	RELOCATE WATER METER	7	EA	
0178	5672000000-N	1515	RELOCATE FIRE HYDRANT	7	EA	
0179	5801000000-E	1530	ABANDON 8" UTILITY PIPE	940	LF	
0180	5804000000-E	1530	ABANDON 12" UTILITY PIPE	1,683	LF	
0181	5815000000-N	1530	REMOVE WATER METER	2	EA	
0182	6000000000-E	1605	TEMPORARY SILT FENCE	30,000	LF	
0183	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	1,200	TON	
0184	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	2,000	TON	
0185	6012000000-E	1610	SEDIMENT CONTROL STONE	2,000	TON	
0186	6015000000-E	1615	TEMPORARY MULCHING	47.5	ACR	
0187	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,250	LB	
0188	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	5	TON	
0189	6024000000-E	1622	TEMPORARY SLOPE DRAINS	2,500	LF	

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
019C	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	40	EA	
0191	6029000000-E	SP	SAFETY FENCE	7,000	LF	
0192	6030000000-E	1630	SILT EXCAVATION	5,910	CY	
0193	6036000000-E	1631	MATTING FOR EROSION CONTROL	7,050	SY	
0194	6037000000-E	SP	COIR FIBER MAT	75	SY	
019E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	160	SY	
019E	6042000000-E	1632	1/4" HARDWARE CLOTH	5,950	LF	
0197	6045000000-E	SP	*** TEMPORARY PIPE (48")	10	LF	
019E	6046000000-E	SP	TEMPORARY PIPE FOR STREAM CROSSING	40	LF	
019E	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	25	SY	
020C	6069000000-E	1638	STILLING BASINS	450	CY	
0201	6071012000-E	SP	COIR FIBER WATTLE	400	LF	
0202	6071020000-E	SP	POLYACRYLAMIDE (PAM)	225	LB	
0203	6071030000-E	SP	COIR FIBER BAFFLE	1,000	LF	
0204	6084000000-E	1660	SEEDING & MULCHING	47.5	ACR	
020E	6087000000-E	1660	MOWING	47.5	ACR	
020E	6090000000-E	1661	SEED FOR REPAIR SEEDING	500	LB	
0207	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	2.25	TON	
020E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	1,500	LB	

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
020E	6108000000-E	1665	FERTILIZER TOPDRESSING	45 TON		
021C	6111000000-E	SP	IMPERVIOUS DIKE	400 LF		
0211	6114500000-N	SP	SPECIALIZED HAND MOWING	25 MHR		
0212	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	75 EA		
0213	6120000000-E	SP	CULVERT DIVERSION CHANNEL	210 CY		
0214	6123000000-E	1670	REFORESTATION	5 ACR		
021E	6126000000-E	SP	STREAMBANK REFORESTATION	0.6 ACR		
021E	6135000000-E	SP	GENERIC EROSION CONTROL ITEM COMPOST BLANKET	20 ACR		
0217	7000000000-E	1705	PEDESTRIAN SIGNAL HEAD (***, ** SECTION) (16", 1 SECTION WITH COUNTDOWN)	2 EA		
021E	7060000000-E	1705	SIGNAL CABLE	7,190 LF		
021E	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	32 EA		
022C	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	9 EA		
0221	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	9 EA		
0222	7252000000-E	1710	MESSENGER CABLE (1/4")	120 LF		
0223	7279000000-E	1715	TRACER WIRE	5,501 LF		
0224	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	6,578 LF		
022E	7300000000-E	1715	UNPAVED TRENCHING (*****) (2, 2")	120 LF		
022E	7301000000-E	1715	DIRECTIONAL DRILL (*****) (1, 2")	1,662 LF		

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0227	7301000000-E	1715	DIRECTIONAL DRILL (***** (2, 2")	1,610 LF		
022E	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	45 EA		
022E	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEA- VY DUTY)	19 EA		
023C	7360000000-N	1720	WOOD POLE	2 EA		
0231	7372000000-N	1721	GUY ASSEMBLY	2 EA		
0232	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0233	7420000000-E	1722	2" RISER WITH WEATHERHEAD	2 EA		
0234	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	5,165 LF		
023E	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	11,760 LF		
023E	7481000000-N	SP	SITE SURVEY	1 EA		
0237	7481200000-N	SP	LUMINAIRE ARM FOR VIDEO SYSTEM	2 EA		
023E	7481240000-N	SP	CAMERA WITHOUT INTERNAL LOOP EMULATOR PROCESSING UNIT	3 EA		
023E	7481260000-N	SP	EXTERNAL LOOP EMULATOR PRO- CESSING UNIT	1 EA		
024C	7484000000-N	SP	MICROWAVE VEHICLE DETECTOR	1 EA		
0241	7516000000-E	1730	COMMUNICATIONS CABLE (**FIBER) (24)	5,445 LF		
0242	7528000000-E	1730	DROP CABLE	695 LF		
0243	7540000000-N	1731	SPLICE ENCLOSURE	5 EA		
0244	7552000000-N	1731	INTERCONNECT CENTER	5 EA		
024E	7566000000-N	1733	DELINEATOR MARKER	13 EA		

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
024E	7568000000-N	SP	FURNISH FIBER-OPTIC RESTORATION KIT	1	EA	
0247	7570000000-N	SP	FURNISH FIBER-OPTIC POWER METER	1	EA	
024E	7572000000-N	SP	FURNISH OPTICAL LIGHT GENERATOR	1	EA	
024E	7588000000-N	SP	METAL POLE WITH SINGLE MAST ARM	9	EA	
025C	7590000000-N	SP	METAL POLE WITH DUAL MAST ARM	4	EA	
0251	7613000000-N	SP	SOIL TEST	13	EA	
0252	7614100000-E	SP	DRILLED PIER FOUNDATION	91	CY	
025E	7624000000-N	1743	SIGNAL PEDESTAL WITH FOUNDATION	1	EA	
0254	7631000000-N	SP	MAST ARM WITH METAL POLE DESIGN	13	EA	
025E	7684000000-N	1750	SIGNAL CABINET FOUNDATION	5	EA	
025E	7686000000-N	SP	CONDUIT ENTRANCE INTO EXISTING FOUNDATION	1	EA	
0257	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	5	EA	
025E	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	32	EA	
025E	7901000000-N	1753	CABINET BASE EXTENDER	5	EA	
026C	7980000000-N	SP	GENERIC SIGNAL ITEM POWDER COAT FOR DOUBLE MAST ARM WITH METAL POLE	4	EA	
0261	7980000000-N	SP	GENERIC SIGNAL ITEM POWDER COAT FOR SINGLE MAST ARM WITH METAL POLE	9	EA	

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
CULVERT ITEMS						
0262	8126000000-N	414	CULVERT EXCAVATION, STA ***** (2 + 81.00-LOOPA-)	Lump Sum	L.S.	
0263	8126000000-N	414	CULVERT EXCAVATION, STA ***** (23 + 32.00-L-)	Lump Sum	L.S.	
0264	8126000000-N	414	CULVERT EXCAVATION, STA ***** (7 + 19.00-RAMPA-)	Lump Sum	L.S.	
0265	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	555 TON		
0266	8196000000-E	420	CLASS A CONCRETE (CULVERT)	1,061.1 CY		
0267	8245000000-E	425	REINFORCING STEEL (CULVERT)	156,652 LB		
WALL ITEMS						
026E	8802030000-E	SP	SEGMENTAL GRAVITY RETAINING WALLS	250 SF		
STRUCTURE ITEMS						
0269	8112730000-N	SP	PDA TESTING	2 EA		
027C	8112740000-N	SP	PDA ASSISTANCE	2 EA		
0271	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	18,961 SF		
0272	8161000000-E	420	GROOVING BRIDGE FLOORS	21,258 SF		
0273	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	264.5 CY		
0274	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (21 + 47.74-L-)	Lump Sum	L.S.	
027E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	37,654 LB		

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0276	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,824 LB		
0277	8274000000-E	430	MODIFIED 63" PRESTRESSED CONC GIRDERS	2,171.71 LF		
027E	8385000000-E	SP	PP ** X **** STEEL PILES (14X0.5)	3,080 LF		
027E	8392000000-N	SP	PIPE PILE PLATES	47 EA		
028C	8393000000-N	SP	PILE REDRIVES	47 EA		
0281	8503000000-E	460	CONCRETE BARRIER RAIL	439.72 LF		
0282	8531000000-E	462	4" SLOPE PROTECTION	1,010 SY		
0283	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0284	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
1525/June07/Q1130498.727/D1295756272000/E284			Total Amount Of Bid For Entire Project :			

Contract No **C202647**

County (ies): **Onslow**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General