

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (11 + 30.50)	Lump Sum	L.S.	
0004	0038000000-E	SP	SHALLOW UNDERCUT	100 CY		
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	150 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	6 CY		
0009	0195000000-E	SP	SELECT GRANULAR MATERIAL	100 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	275 SY		
0011	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	39 TON		
0012	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	125 SY		
0013	0335200000-E	SP	15" DRAINAGE PIPE	48 LF		
0014	0335300000-E	SP	18" DRAINAGE PIPE	224 LF		
0015	0343000000-E	SP	15" SIDE DRAIN PIPE	92 LF		
0016	0995000000-E	340	PIPE REMOVAL	66 LF		
0017	1121000000-E	520	AGGREGATE BASE COURSE	95 TON		
0018	1220000000-E	545	INCIDENTAL STONE BASE	750 TON		
0019	1275000000-E	600	PRIME COAT	70 GAL		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
002C	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	855 TON		
0021	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	345 TON		
0022	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	630 TON		
0023	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	95 TON		
0024	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
002E	2022000000-E	SP	SUBDRAIN EXCAVATION	23 CY		
002E	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	17 CY		
0027	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	100 LF		
002E	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1 EA		
002E	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6 LF		
003C	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0031	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		
0032	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
003E	2738000000-E	SP	GENERIC PAVING ITEM 6" CONCRETE DRIVEWAYS	15 SY		
0034	3030000000-E	862	STEEL BM GUARDRAIL	25 LF		
003E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	75 LF		
003E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0037	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III SHOP CURVED)	2 EA		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2	EA	
003E	3435000000-N	SP	GENERIC GUARDRAIL ITEM TIMBER BOLLARDS	10	EA	
004C	3569000000-E	867	BARBED WIRE FENCE RESET	520	LF	
0041	3574000000-E	867	GENERIC FENCING ITEM WOODEN FENCE RESET	630	LF	
0042	3628000000-E	876	RIP RAP, CLASS I	85	TON	
0043	3649000000-E	876	RIP RAP, CLASS B	5	TON	
0044	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	775	SY	
004E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	39	LF	
004E	4102000000-N	904	SIGN ERECTION, TYPE E	3	EA	
0047	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	9	EA	
004E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	639	SF	
004E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	386	SF	
005C	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	152	SF	
0051	4430000000-N	1130	DRUMS	98	EA	
0052	4435000000-N	1135	CONES	30	EA	
0053	4445000000-E	1145	BARRICADES (TYPE III)	164	LF	
0054	4450000000-N	1150	FLAGGER	2,760	HR	
005E	4507000000-E	SP	WATER FILLED BARRIER	100	LF	
005E	4516000000-N	1180	SKINNY DRUM	50	EA	

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	80	EA	
005E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	23,642	LF	
005E	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	4,230	LF	
006C	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	104	LF	
0061	5888000000-E	SP	GENERIC UTILITY ITEM 12" STEEL ENCASEMENT PIPE	44	LF	
0062	6000000000-E	1605	TEMPORARY SILT FENCE	1,775	LF	
006E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	500	TON	
0064	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	100	TON	
006E	6012000000-E	1610	SEDIMENT CONTROL STONE	175	TON	
006E	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
0067	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
006E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25	TON	
006E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
007C	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
0071	6029000000-E	SP	SAFETY FENCE	1,130	LF	
0072	6030000000-E	1630	SILT EXCAVATION	750	CY	
007E	6036000000-E	1631	MATTING FOR EROSION CONTROL	10,000	SY	
0074	6037000000-E	SP	COIR FIBER MAT	30	SY	

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	200 SY		
007E	6042000000-E	1632	1/4" HARDWARE CLOTH	450 LF		
0077	6071020000-E	SP	POLYACRYLAMIDE (PAM)	30 LB		
007E	6071030000-E	SP	COIR FIBER BAFFLE	375 LF		
007E	6071050000-E	SP	*** SKIMMER (1-1/2")	3 EA		
008C	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0081	6087000000-E	1660	MOWING	1.5 ACR		
0082	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
008E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0084	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
008E	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		
008E	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
0087	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
008E	6123000000-E	1670	REFORESTATION	0.25 ACR		
STRUCTURE ITEMS						
008E	8096000000-E	SP	PILE EXCAVATION IN SOIL	49 LF		
009C	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	102 LF		
0091	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (11 + 30.50-L-)	Lump Sum	L.S.	

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	4,435 SF		
0093	8161000000-E	420	GROOVING BRIDGE FLOORS	4,105 SF		
0094	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	36.6 CY		
009E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (11 + 30.50-L-)	Lump Sum	L.S.	
009E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,482 LB		
0097	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	342,600 LS		
009E	8364000000-E	SP	HP12X53 STEEL PILES	430 LF		
009E	8468000000-E	460	ONE BAR METAL RAIL	299 LF		
010C	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-0" X 1'-6")	314 LF		
0101	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0102	8860000000-N	SP	GENERIC STRUCTURE ITEM REHABILITATION OF EXISTING STRUCTURE	Lump Sum	L.S.	

1154/Jul13/Q412743.35/D429203600000/E102

Total Amount Of Bid For Entire Project :

Contract No **C202323**

County (ies): **Haywood**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General