

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0255000000-E	SP	GENERIC GRADING ITEM INCIDENTAL STONE BASE	563 TON		
0003	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	137,324 SY		
0004	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	34,040 SY		
0005	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1-1/2" TO 3")	3,095 SY		
0006	1330000000-E	607	INCIDENTAL MILLING	3,444 SY		
0007	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	19,636 TON		
0008	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	19,606 TON		
0009	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	2,116 TON		
001C	1839000000-E	660	GENERIC PAVING ITEM ASPHALT SURFACE TREATMENT, MAT COAT, #67 STONE	34,836 SY		
0011	1880000000-E	SP	GENERIC PAVING ITEM 3" PATCHING OF EXISTING PAVE- MENT	100 TON		
0012	1880000000-E	SP	GENERIC PAVING ITEM 8" PATCHING OF EXISTING PAVE- MENT	260 TON		
0013	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
0014	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	105,325 LF		
0015	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	13,674 LF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0016	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	13,915	LF	
0017	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	200	LF	
001E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	54	EA	
001E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	95,871	LF	
002C	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	13,085	LF	
0021	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	34	LF	
0022	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	17	EA	
0023	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,163	EA	
0024	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
002E	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	505	LF	
002E	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	11	EA	
0027	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	3,353	LF	
002E	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	640	LF	

0947/Sep12/Q502870.0/D102773100000/E28

Total Amount Of Bid For Entire Project :

Contract No **C202850**

County (ies): **Guilford**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General