

County : Hyde

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (22 + 60.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	400 CY		
0007	0127000000-N	SP	EMBANKMENT SETTLEMENT GAUGES	4 EA		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	20 CY		
0009	0195000000-E	SP	SELECT GRANULAR MATERIAL	400 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0011	0199000000-E	SP	TEMPORARY SHORING	699 SF		
0012	0241000000-E	SP	GENERIC GRADING ITEM FABRIC FOR EMBANKMENT STABIL- ZATION	450 SY		
0013	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	31 TON		
0014	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	860 SY		
0015	0335200000-E	SP	15" DRAINAGE PIPE	32 LF		
0016	0335300000-E	SP	18" DRAINAGE PIPE	56 LF		
0017	0344000000-E	SP	18" SIDE DRAIN PIPE	24 LF		
0018	0366000000-E	SP	15" RC PIPE CULVERTS, CLASS III	68 LF		

County : Hyde

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0995000000-E	340	PIPE REMOVAL	42	LF	
002C	1121000000-E	520	AGGREGATE BASE COURSE	180	TON	
0021	1220000000-E	545	INCIDENTAL STONE BASE	40	TON	
0022	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,330	TON	
002E	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	830	TON	
0024	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	80	TON	
002E	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	115	TON	
002E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20	TON	
0027	2022000000-E	SP	SUBDRAIN EXCAVATION	22.4	CY	
002E	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	16.8	CY	
002E	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	100	LF	
003C	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1	EA	
0031	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6	LF	
0032	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3	EA	
003E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2	EA	
0034	2396000000-N	840	FRAME WITH COVER, STD 840.54	1	EA	
003E	2556000000-E	846	SHOULDER BERM GUTTER	50	LF	
003E	3030000000-E	862	STEEL BM GUARDRAIL	75	LF	
0037	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	125	LF	

County : Hyde

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
003E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
004C	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0041	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0042	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	512.5 LF		
0043	3382000000-E	862	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)	162.5 LF		
0044	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III MODIFIED)	4 EA		
004E	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	6 EA		
004E	3649000000-E	876	RIP RAP, CLASS B	5 TON		
0047	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	714 SY		
004E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	244 SF		
004E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	192 SF		
005C	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	40 SF		
0051	4430000000-N	1130	DRUMS	90 EA		
0052	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0053	4450000000-N	1150	FLAGGER	960 HR		
0054	4516000000-N	1180	SKINNY DRUM	15 EA		
005E	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM WARNING FLAGS	4 EA		

County : Hyde

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	4609000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TEMPORARY TRAFFIC SIGNAL SYSTEM	270	DAY	
0057	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	40	EA	
005E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,565	LF	
005E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,532	LF	
006C	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	44	LF	
0061	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	15,500	LF	
0062	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	90	LF	
0063	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	4,234	LF	
0064	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	60	LF	
006E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	16	EA	
006E	5325400000-E	1510	4" WATER LINE	165	LF	
0067	5325600000-E	1510	6" WATER LINE	97	LF	
006E	5540000000-E	1515	6" VALVE	2	EA	
006E	5666000000-E	1515	FIRE HYDRANT	1	EA	
007C	5798000000-E	1530	ABANDON *** UTILITY PIPE (4")	235	LF	
0071	5800000000-E	1530	ABANDON 6" UTILITY PIPE	18	LF	
0072	5815500000-N	1530	REMOVE FIRE HYDRANT	1	EA	

County : Hyde

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6000000000-E	1605	TEMPORARY SILT FENCE	2,100 LF		
0074	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	350 TON		
007E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	100 TON		
007E	6012000000-E	1610	SEDIMENT CONTROL STONE	70 TON		
0077	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
007E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0079	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.5 TON		
008C	6024000000-E	1622	TEMPORARY SLOPE DRAINS	600 LF		
0081	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	12 EA		
0082	6029000000-E	SP	SAFETY FENCE	900 LF		
0083	6030000000-E	1630	SILT EXCAVATION	270 CY		
0084	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,865 SY		
008E	6037000000-E	SP	COIR FIBER MAT	300 SY		
008E	6042000000-E	1632	1/4" HARDWARE CLOTH	250 LF		
0087	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	500 SY		
008E	6071010000-E	SP	WATTLE	450 LF		
0089	6071020000-E	SP	POLYACRYLAMIDE (PAM)	50 LB		
009C	6071030000-E	SP	COIR FIBER BAFFLE	175 LF		
0091	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		

County : Hyde

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0093	6087000000-E	1660	MOWING	3 ACR		
0094	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
009E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
009E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0097	6108000000-E	1665	FERTILIZER TOPDRESSING	2 TON		
009E	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
009E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
010C	6123000000-E	1670	REFORESTATION	0.1 ACR		

STRUCTURE ITEMS

0101	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22 + 60.00 -L-)	Lump Sum	L.S.	
0102	8112730000-N	SP	PDA TESTING	2 EA		
0103	8112740000-N	SP	PDA ASSISTANCE	2 EA		
0104	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (22 + 60.00 -L-)	Lump Sum	L.S.	
010E	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	70.8 CY		
010E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22 + 60.00 -L-)	Lump Sum	L.S.	
0107	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	10,760 LB		

County : Hyde

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010E	8329000000-E	SP	12" PRESTRESSED CONC PILES	560 LF		
010E	8333000000-E	SP	16" PRESTRESSED CONC PILES	800 LF		
011C	8393000000-N	SP	PILE REDRIVES	16 EA		
0111	8468000000-E	460	ONE BAR METAL RAIL	232.63 LF		
0112	8517000000-E	460	1'***X ***** CONCRETE PARA- PET (1'-2" X 2'-7 3/4")	247.63 LF		
0113	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	225 TON		
0114	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	251 SY		
011E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
011E	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,853.44 LF		

1230/Aug25/Q58784.55/D499773680000/E116

Total Amount Of Bid For Entire Project :

Contract No **C202661**

County (ies): **Hyde**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General