

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0000900000-N	SP	GENERIC MISCELLANEOUS ITEM TIMBER STEPS	Lump Sum	L.S.	
0004	0000930000-E	SP	GENERIC MISCELLANEOUS ITEM 48" SAFETY RAIL	274 LF		
0005	0000930000-E	SP	GENERIC MISCELLANEOUS ITEM BOARDWALK	60 LF		
0006	0000930000-E	SP	GENERIC MISCELLANEOUS ITEM BOARDWALK POSTS 7-1/2" MIN TIP DIAMETER	330 LF		
0007	0001020000-N	SP	GENERIC MISCELLANEOUS ITEM CONCRETE APPROACH TO BOARDWALK	2 EA		
0008	0001020000-N	SP	GENERIC MISCELLANEOUS ITEM HINGED BOLLARD	3 EA		
0009	0001020000-N	SP	GENERIC MISCELLANEOUS ITEM WOOD BOLLARD	20 EA		
0010	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (26+60.00)	Lump Sum	L.S.	
0011	0043000000-N	226	GRADING	Lump Sum	L.S.	
0012	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0013	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0014	0134000000-E	240	DRAINAGE DITCH EXCAVATION	30 CY		
0015	0195000000-E	SP	SELECT GRANULAR MATERIAL	200 CY		
0016	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,400 SY		
0017	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	70 TON		
0018	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	160 SY		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0335200000-E	SP	15" DRAINAGE PIPE	152 LF		
0020	0335500000-E	SP	30" DRAINAGE PIPE	24 LF		
0021	0335850000-E	SP	*** DRAINAGE PIPE ELBOWS (15")	2 EA		
0022	0366000000-E	SP	15" RC PIPE CULVERTS, CLASS III	56 LF		
0023	0448200000-E	SP	15" RC PIPE CULVERTS, CLASS IV	96 LF		
0024	0448300000-E	SP	18" RC PIPE CULVERTS, CLASS IV	48 LF		
0025	0448500000-E	SP	30" RC PIPE CULVERTS, CLASS IV	76 LF		
0026	0995000000-E	340	PIPE REMOVAL	178 LF		
0027	1121000000-E	520	AGGREGATE BASE COURSE	407 TON		
0028	1220000000-E	545	INCIDENTAL STONE BASE	1,000 TON		
0029	1330000000-E	607	INCIDENTAL MILLING	210 SY		
0030	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	690 TON		
0031	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	370 TON		
0032	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	600 TON		
0033	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	85 TON		
0034	2000000000-N	806	RIGHT OF WAY MARKERS	13 EA		
0035	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	8 EA		
0036	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	2.8 LF		
0037	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	6 EA		
0039	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1 EA		
0040	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	75 LF		
0041	2556000000-E	846	SHOULDER BERM GUTTER	190 LF		
0042	2591000000-E	848	4" CONCRETE SIDEWALK	90 SY		
0043	3030000000-E	862	STEEL BM GUARDRAIL	287.5 LF		
0044	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	12.5 LF		
0045	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	3 EA		
0046	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III, SHOP CURVED)	1 EA		
0047	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0048	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	3 EA		
0049	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1 EA		
0050	3360000000-E	863	REMOVE EXISTING GUARDRAIL	752 LF		
0051	3628000000-E	876	RIP RAP, CLASS I	7 TON		
0052	3635000000-E	876	RIP RAP, CLASS II	10 TON		
0053	3649000000-E	876	RIP RAP, CLASS B	41 TON		
0054	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	2,410 SY		
0055	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	250 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4096000000-N	904	SIGN ERECTION, TYPE D	4 EA		
0057	4102000000-N	904	SIGN ERECTION, TYPE E	6 EA		
0058	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	1 EA		
0059	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	19 EA		
0060	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1 EA		
0061	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	516 SF		
0062	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	112 SF		
0063	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	214 SF		
0064	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	28 DAY		
0065	4430000000-N	1130	DRUMS	50 EA		
0066	4445000000-E	1145	BARRICADES (TYPE III)	200 LF		
0067	4450000000-N	1150	FLAGGER	48 HR		
0068	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,126 LF		
0069	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,342 LF		
0070	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	29 LF		
0071	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,481 LF		
0072	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	29 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	4891000000-E	1205	GENERIC PAVEMENT MARKING ITEM COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE II OR III (4")	1,920 LF		
0074	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	14 EA		
0075	5326200000-E	1510	12" WATER LINE	66 LF		
0076	5691300000-E	1520	8" SANITARY GRAVITY SEWER	110 LF		
0077	5775000000-E	1525	4' DIA UTILITY MANHOLE	2 EA		
0078	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	1 LF		
0079	5801000000-E	1530	ABANDON 8" UTILITY PIPE	70 LF		
0080	5804000000-E	1530	ABANDON 12" UTILITY PIPE	600 LF		
0081	5900000000-E	SP	GENERIC UTILITY ITEM BEDDING MATERIAL, UTILITIES	20 TON		
0082	6000000000-E	1605	TEMPORARY SILT FENCE	2,850 LF		
0083	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	385 TON		
0084	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	80 TON		
0085	6012000000-E	1610	SEDIMENT CONTROL STONE	685 TON		
0086	6015000000-E	1615	TEMPORARY MULCHING	2 ACR		
0087	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0088	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0089	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0090	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	6029000000-E	SP	SAFETY FENCE	500 LF		
0092	6030000000-E	1630	SILT EXCAVATION	70 CY		
0093	6036000000-E	1631	MATTING FOR EROSION CONTROL	7,750 SY		
0094	6037000000-E	SP	COIR FIBER MAT	950 SY		
0095	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	300 SY		
0096	6042000000-E	1632	1/4" HARDWARE CLOTH	555 LF		
0097	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	900 SY		
0098	6070000000-N	SP	SPECIAL STILLING BASINS	24 EA		
0099	6071010000-E	SP	WATTLE	300 LF		
0100	6071020000-E	SP	POLYACRYLAMIDE (PAM)	80 LB		
0101	6071030000-E	SP	COIR FIBER BAFFLE	10 LF		
0102	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
0103	6087000000-E	1660	MOWING	2 ACR		
0104	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0105	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0106	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0107	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0108	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
0109	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		
0110	6123000000-E	1670	REFORESTATION	0.1 ACR		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>WALL ITEMS</b>						
0111	8801000000-E	SP	MSE RETAINING WALLS (10+00.00 -WALL1-)	900 SF		
0112	8801000000-E	SP	MSE RETAINING WALLS (10+00.00 -WALL3-)	900 SF		
0113	8802030000-E	SP	SEGMENTAL GRAVITY RETAINING WALLS (10+00.00 -WALL2-)	250 SF		
<b>STRUCTURE ITEMS</b>						
0114	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (26+60.00 -L-)	Lump Sum	L.S.	
0115	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (26+60.00 -L-)	Lump Sum	L.S.	
0116	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	45 LF		
0117	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	83.7 LF		
0118	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	88.8 LF		
0119	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	89 LF		
0120	8113000000-N	SP	SID INSPECTION	1 EA		
0121	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (26+60.00 -L-)	Lump Sum	L.S.	
0122	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	23,107 SF		
0123	8161000000-E	420	GROOVING BRIDGE FLOORS	16,550 SF		
0124	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	211.6 CY		
0125	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (26+60.00 -L-)	Lump Sum	L.S.	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0126	8217000000-E	425	REINFORCING STEEL (BRIDGE)	51,147 LB		
0127	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	5,811 LB		
0128	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	2,849.72 LF		
0129	8364000000-E	SP	HP12X53 STEEL PILES	300 LF		
0130	8475000000-E	460	TWO BAR METAL RAIL	942.56 LF		
0131	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	533.2 LF		
0132	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 2'-6")	957.81 LF		
0133	8531000000-E	462	4" SLOPE PROTECTION	19 SY		
0134	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	140 TON		
0135	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	155 SY		
0136	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0137	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0138	8860000000-N	SP	GENERIC STRUCTURE ITEM INSTALL 12" DIRJ WATER MAIN	Lump Sum	L.S.	
0139	8897000000-N	SP	GENERIC STRUCTURE ITEM CSL TESTING	1 EA		

1554/Aug29/Q142899.04/D624359570000/E139

Total Amount Of Bid For Entire Project :



**Contract No**     **C202580**

**County (ies):**   **Wake**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General