



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

BEVERLY EAVES PERDUE
GOVERNOR

EUGENE A. CONTI, JR.
SECRETARY

November 9, 2011

Addendum No. 1

RE: Contract ID C202856
WBS # 7CR.10791.36, Etc.
State Funded

Rockingham County

NC-770/87 from NC-14 To SR-1533, NC-87 From NC-65 To NC-770
And 3 Sections of Secondary Roads


November 15, 2011 Letting

To Whom It May Concern:

Reference is made to the proposal furnished to you on this project.

The following revisions have been made to the proposal:

On Page No. 49 a revision was made to the last sentence of the first paragraph on that page within the project special provision entitled '8" Patching by Milling'. Please void Page No. 49 in your proposal and staple the revised Page No. 49 thereto.

Sincerely,


R. A. Garris, PE
Contract Officer

RAG/jag
Attachment

cc: Mr. Jon Nance, PE
Mr. Ron Hancock, PE
Mr. J. M. Mills, PE
Ms. D. M. Barbour, PE
Mr. Art McMillan, PE
Mr. J. V. Barbour, PE
Project File (2)

Mr. R.E. Davenport, PE
Ms. Natalie Roskam, PE
Mr. Larry Strickland
Mr. Ronnie Higgins
Ms. Lori Strickland
Ms. Marsha Sample

8" Patching by Milling will be measured and paid for as the actual number of tons of asphalt plant mix complete in place that has been used to make completed and accepted repairs. The asphalt plant mixed material will be measured by being weighed in trucks on certified platform scales or other certified weighing devices. The above price and payment will be full compensation for all work covered by this provision, including but not limited to removal and disposal of pavement; furnishing and applying tack coat; furnishing, placing, and compacting of asphalt plant mix; furnishing of asphalt binder for plant mix; and furnishing scales.

8" Patching by Milling will be considered a minor item. In the event that the item of 8" Patching by Milling overruns the original bid quantity by more than 100 percent, the provisions of Article 104-5 of the *Standard Specifications* pertaining to revised contract unit price for overrunning minor items will not apply to this item.

Payment will be made under:

Pay Item	Pay Unit
8" Patching of Existing Pavement	Ton

BORROW EXCAVATION AND SHPO DOCUMENTATION FOR BORROW/WASTE

SITES:

(12-18-07)(4-15-08)

R8 R02

Revise the 2006 *Standard Specifications* as follows:

Division 2 Earthwork

Page 2-16, Subarticle 230-1(D), add the words: *The Contractor specifically waives* as the first words of the sentence.

Page 2-17, Article 230-4(B) Contractor Furnished Sources, first paragraph, first sentence replace with the following:

Prior to the approval of any borrow sources developed for use on any project, obtain certification from the State Historic Preservation Officer of the State Department of Cultural Resources certifying that the removal of the borrow material from the borrow sources(s) will have no effect on any known district, site building, structure, or object, architectural and/or archaeological that is included or eligible for inclusion in the National Register of Historic Places.

Division 8 Incidentals

Page 8-9, Article 802-2 General Requirements, add the following as the 1st paragraph:

Prior to the removal of any waste from any project, obtain certification from the State Historic Preservation Officer of the State Department of Cultural Resources certifying that the deposition of the waste material to the proposed waste area will have no effect on any known district, site building, structure, or object, architectural and/or archaeological that is