

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (22+46.50)	Lump Sum	L.S.	
0003	0038000000-E	SP	SHALLOW UNDERCUT	175 CY		
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	350 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	90 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0010	0318000000-E	SP	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	3 TON		
0011	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	8 SY		
0012	0582000000-E	SP	15" CS PIPE CULVERTS, 0.064" THICK	24 LF		
0013	0636000000-E	SP	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	2 EA		
0014	1330000000-E	607	INCIDENTAL MILLING	220 SY		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	115 TON		
0016	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	100 TON		
0017	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	12 TON		
0018	2000000000-N	806	RIGHT OF WAY MARKERS	4 EA		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0020	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0021	2556000000-E	846	SHOULDER BERM GUTTER	51 LF		
0022	3030000000-E	862	STEEL BM GUARDRAIL	50 LF		
0023	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0024	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0025	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0026	3628000000-E	876	RIP RAP, CLASS I	205 TON		
0027	3635000000-E	876	RIP RAP, CLASS II	280 TON		
0028	3649000000-E	876	RIP RAP, CLASS B	1 TON		
0029	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,020 SY		
0030	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	76 LF		
0031	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0032	4102000000-N	904	SIGN ERECTION, TYPE E	1 EA		
0033	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	7 EA		
0034	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	439 SF		
0035	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0036	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0037	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	1,806 LF		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	5325600000-E	1510	6" WATER LINE	381 LF		
0039	6000000000-E	1605	TEMPORARY SILT FENCE	820 LF		
0040	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
0041	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	30 TON		
0042	6012000000-E	1610	SEDIMENT CONTROL STONE	40 TON		
0043	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0044	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0045	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0046	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0047	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0048	6029000000-E	SP	SAFETY FENCE	100 LF		
0049	6030000000-E	1630	SILT EXCAVATION	40 CY		
0050	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,000 SY		
0051	6042000000-E	1632	1/4" HARDWARE CLOTH	145 LF		
0052	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0053	6087000000-E	1660	MOWING	0.5 ACR		
0054	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0055	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0056	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0057	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25 TON		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	6114500000-N	SP	SPECIALIZED HAND MOWING	10 MHR		
0059	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
STRUCTURE ITEMS						
0060	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (22+46.50-L-)	Lump Sum	L.S.	
0061	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22+46.50-L-)	Lump Sum	L.S.	
0062	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (22+46.50-L-)	Lump Sum	L.S.	
0063	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	40.2 CY		
0064	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22+46.50-L-)	Lump Sum	L.S.	
0065	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,418 LB		
0066	8364000000-E	SP	HP12X53 STEEL PILES	360 LF		
0067	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	205.21 LF		
0068	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	310 TON		
0069	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	345 SY		
0070	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0071	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,128.66 LF		

Contract No **C202735**

County (ies): **Davidson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General