

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17 + 68.30)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0106000000-E	230	BORROW EXCAVATION	19,400 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	20 CY		
0008	0195000000-E	SP	SELECT GRANULAR MATERIAL	200 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
001C	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	90 TON		
0011	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	260 SY		
0012	0335200000-E	SP	15" DRAINAGE PIPE	164 LF		
0013	0335400000-E	SP	24" DRAINAGE PIPE	80 LF		
0014	0366000000-E	SP	15" RC PIPE CULVERTS, CLASS III	404 LF		
0015	0378000000-E	SP	24" RC PIPE CULVERTS, CLASS III	56 LF		
0016	0582000000-E	SP	15" CS PIPE CULVERTS, 0.064" THICK	60 LF		
0017	0636000000-E	SP	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	4 EA		
0018	0995000000-E	340	PIPE REMOVAL	244 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1121000000-E	520	AGGREGATE BASE COURSE	809 TON		
0020	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0021	1275000000-E	600	PRIME COAT	578 GAL		
0022	1330000000-E	607	INCIDENTAL MILLING	290 SY		
0023	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,020 TON		
0024	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	860 TON		
0025	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,080 TON		
0026	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	155 TON		
0027	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	7 TON		
0028	2000000000-N	806	RIGHT OF WAY MARKERS	5 EA		
0029	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	10 EA		
0030	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	3.86 LF		
0031	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	1 EA		
0032	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0033	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	7 EA		
0034	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	1 EA		
0035	2535000000-E	846	***X*** CONCRETE CURB (9" X 12")	80 LF		
0036	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	170 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2556000000-E	846	SHOULDER BERM GUTTER	614	LF	
003E	2612000000-E	848	6" CONCRETE DRIVEWAY	10	SY	
003E	2627000000-E	852	4" CONCRETE ISLAND COVERS	140	SY	
004C	3030000000-E	862	STEEL BM GUARDRAIL	220	LF	
0041	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	25	LF	
0042	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
004E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1	EA	
0044	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
004E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3	EA	
004E	3420000000-E	SP	GENERIC GUARDRAIL ITEM STEEL BEAM GUARDRAIL WITH 8' POST	380	LF	
0047	3649000000-E	876	RIP RAP, CLASS B	10	TON	
004E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	485	SY	
004E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	64	LF	
005C	4102000000-N	904	SIGN ERECTION, TYPE E	2	EA	
0051	4108000000-N	904	SIGN ERECTION, TYPE F	2	EA	
005E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	15	EA	
005E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	328	SF	
0054	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	192	SF	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	52	SF	
005E	4430000000-N	1130	DRUMS	50	EA	
0057	4435000000-N	1135	CONES	50	EA	
005E	4445000000-E	1145	BARRICADES (TYPE III)	96	LF	
005E	4450000000-N	1150	FLAGGER	640	HR	
006C	4516000000-N	1180	SKINNY DRUM	50	EA	
0061	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	22	EA	
0062	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,428	LF	
0063	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,428	LF	
0064	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	23	LF	
006E	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	564	LF	
006E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	13,600	LF	
0067	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	96	LF	
006E	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	24	LF	
006E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	18	EA	
007C	5325200000-E	1510	2" WATER LINE	93	LF	
0071	5325600000-E	1510	6" WATER LINE	130	LF	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	5606000000-E	1515	2" BLOW OFF	1 EA		
0073	6000000000-E	1605	TEMPORARY SILT FENCE	4,100 LF		
0074	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	270 TON		
0075	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	440 TON		
0076	6012000000-E	1610	SEDIMENT CONTROL STONE	340 TON		
0077	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0078	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0079	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0080	6024000000-E	1622	TEMPORARY SLOPE DRAINS	300 LF		
0081	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	6 EA		
0082	6029000000-E	SP	SAFETY FENCE	200 LF		
0083	6030000000-E	1630	SILT EXCAVATION	700 CY		
0084	6036000000-E	1631	MATTING FOR EROSION CONTROL	4,000 SY		
0085	6042000000-E	1632	1/4" HARDWARE CLOTH	800 LF		
0086	6071030000-E	SP	COIR FIBER BAFFLE	300 LF		
0087	6084000000-E	1660	SEEDING & MULCHING	3.6 ACR		
0088	6087000000-E	1660	MOWING	2.5 ACR		
0089	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0090	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0092	6108000000-E	1665	FERTILIZER TOPDRESSING	2.25 TON		
0093	6114500000-N	SP	SPECIALIZED HAND MOWING	15 MHR		
0094	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
0095	7060000000-E	1705	SIGNAL CABLE	550 LF		
0096	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	8 EA		
0097	7264000000-E	1710	MESSENGER CABLE (3/8")	270 LF		
0098	7288000000-E	1715	PAVED TRENCHING (*****) (1, 2")	50 LF		
0099	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	1,210 LF		
0100	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	9 EA		
0101	7360000000-N	1720	WOOD POLE	2 EA		
0102	7372000000-N	1721	GUY ASSEMBLY	8 EA		
0103	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0104	7420000000-E	1722	2" RISER WITH WEATHERHEAD	5 EA		
0105	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	480 LF		
0106	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	1,790 LF		
0107	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1 EA		
0108	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	4 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	7948000000-N	SP	TRAFFIC SIGNAL REMOVAL	1 EA		
<b>WALL ITEMS</b>						
0110	8801000000-E	SP	MSE RETAINING WALLS	3,710 SF		
<b>STRUCTURE ITEMS</b>						
0111	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17 + 64.30-L-)	Lump Sum	L.S.	
0112	8112730000-N	SP	PDA TESTING	1 EA		
0113	8112740000-N	SP	PDA ASSISTANCE	1 EA		
0114	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17 + 64.30-L-)	Lump Sum	L.S.	
0115	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	5,370 SF		
0116	8161000000-E	420	GROOVING BRIDGE FLOORS	5,354 SF		
0117	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	76.2 CY		
0118	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17 + 64.30-L-)	Lump Sum	L.S.	
0119	8217000000-E	425	REINFORCING STEEL (BRIDGE)	11,824 LB		
0120	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	687.08 LF		
0121	8364000000-E	SP	HP12X53 STEEL PILES	675 LF		
0122	8387000000-E	SP	PP 18 X 0.50 GALVANIZED STEEL PILES	920 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0123	8393000000-N	SP	PILE REDRIVES	14 EA		
0124	8475000000-E	460	TWO BAR METAL RAIL	263.67 LF		
0125	8517000000-E	460	1'-***X ***** CONCRETE PARA-PET (1'-2" X 2'-10")	139.33 LF		
0126	8517000000-E	460	1'-***X ***** CONCRETE PARA-PET (1'-2" X 3'-6 3/4")	139.33 LF		
0127	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0128	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0129	8990000000-N	SP	CONTRACT TIME	1,500 DOL		

1648/Oct04/Q96322.82/D599271500000/E129

Total Amount Of Bid For Entire Project :



**Contract No**     **C202733**

**County (ies):**   **Wake**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General