

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	2,311 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	1,162 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	23.23 SMI		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	57,067 SY		
0006	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	141,072 SY		
0007	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (0" TO 1-1/2")	2,432 SY		
0008	1330000000-E	607	INCIDENTAL MILLING	4,223 SY		
0009	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,462 TON		
001C	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	23,394 TON		
0011	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	20,353 TON		
0012	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	2,409 TON		
0013	1704000000-E	SP	PATCHING EXISTING PAVEMENT	1,485 TON		
0014	2830000000-N	858	ADJUSTMENT OF MANHOLES	38 EA		
0015	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	10 EA		
0016	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	110,829 LF		
0017	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	161,047 LF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,010 LF		
001S	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	300 LF		
002C	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	350 LF		
0021	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	990 LF		
0022	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	30 EA		
0023	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	134 EA		
0024	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	237,631 LF		
002E	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	810 LF		
002E	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	350 LF		
0027	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	820 LF		
002E	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	18 EA		
002S	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	112 EA		
003C	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	1,632 EA		
0031	6000000000-E	1605	TEMPORARY SILT FENCE	1,839 LF		
0032	6071010000-E	SP	WATTLE	4,630 LF		
0033	6084000000-E	1660	SEEDING & MULCHING	18.39 ACR		
0034	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	2,574 LF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	7456000000-E	1726	LEAD-IN CABLE (***** (18-4)	500 LF		
1536/Dec12/Q783066.62/D125822110000/E35			Total Amount Of Bid For Entire Project :			

Contract No **C202928**

County (ies): **Durham**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)