

County : Franklin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (26+67.50)	Lump Sum	L.S.	
0003	0036000000-E	225	UNDERCUT EXCAVATION	200 CY		
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0106000000-E	230	BORROW EXCAVATION	4,600 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	300 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	10 TON		
0010	0320000000-E	300	FOUNDATION CONDITIONING GEO-TEXTILE	30 SY		
0011	0335200000-E	305	15" DRAINAGE PIPE	36 LF		
0012	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	2 EA		
0013	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	28 LF		
0014	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	390 TON		
0016	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	250 TON		
0017	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	520 TON		
0018	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	60 TON		

County : Franklin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2000000000-N	806	RIGHT OF WAY MARKERS	8 EA		
0020	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY		
0021	2033000000-E	815	SUBDRAIN FINE AGGREGATE	33.6 CY		
0022	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0023	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0024	2077000000-E	815	6" OUTLET PIPE	6 LF		
0025	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0026	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0027	2556000000-E	846	SHOULDER BERM GUTTER	38 LF		
0028	3030000000-E	862	STEEL BM GUARDRAIL	912.5 LF		
0029	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0030	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0031	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0032	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,102 LF		
0033	3635000000-E	876	RIP RAP, CLASS II	260 TON		
0034	3649000000-E	876	RIP RAP, CLASS B	80 TON		
0035	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,280 SY		
0036	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0037	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	82 LF		
0038	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		

County : Franklin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	4102000000-N	904	SIGN ERECTION, TYPE E	1 EA		
0040	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	5 EA		
0041	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	740 SF		
0042	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	116 SF		
0043	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0044	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,790 LF		
0045	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,790 LF		
0046	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	11 EA		
0047	6000000000-E	1605	TEMPORARY SILT FENCE	1,450 LF		
0048	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
0049	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	150 TON		
0050	6012000000-E	1610	SEDIMENT CONTROL STONE	485 TON		
0051	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0052	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0053	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25 TON		
0054	6024000000-E	1622	TEMPORARY SLOPE DRAINS	320 LF		
0055	6029000000-E	SP	SAFETY FENCE	600 LF		
0056	6030000000-E	1630	SILT EXCAVATION	260 CY		
0057	6036000000-E	1631	MATTING FOR EROSION CONTROL	6,000 SY		

County : Franklin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	6037000000-E	SP	COIR FIBER MAT	10 SY		
0059	6042000000-E	1632	1/4" HARDWARE CLOTH	1,300 LF		
0060	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	50 SY		
0061	6070000000-N	1639	SPECIAL STILLING BASINS	8 EA		
0062	6071010000-E	SP	WATTLE	100 LF		
0063	6071020000-E	SP	POLYACRYLAMIDE (PAM)	25 LB		
0064	6071030000-E	1640	COIR FIBER BAFFLE	70 LF		
0065	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0066	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
0067	6087000000-E	1660	MOWING	2 ACR		
0068	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0069	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0070	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0071	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0072	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0073	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	16 EA		
0074	6123000000-E	1670	REFORESTATION	0.25 ACR		

STRUCTURE ITEMS

0075	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (26+67.50-L-)	Lump Sum	L.S.	
------	--------------	----	---	----------	------	--

County : Franklin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	803500000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (26+67.50-L-)	Lump Sum	L.S.	
0077	810800000-E	411	***-*** DIA DRILLED PIERS (4'-6")	152 LF		
0078	811100000-E	411	PERMANENT STEEL CASING FOR ***-*** DIA DRILLED PIER (4'-6")	36 LF		
0079	811300000-N	411	SID INSPECTIONS	2 EA		
0080	811400000-N	411	SPT TESTING	2 EA		
0081	811500000-N	411	CSL TESTING	1 EA		
0082	812100000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (26+67.50-L-)	Lump Sum	L.S.	
0083	818200000-E	420	CLASS A CONCRETE (BRIDGE)	116.3 CY		
0084	821000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (26+67.50-L-)	Lump Sum	L.S.	
0085	821700000-E	425	REINFORCING STEEL (BRIDGE)	31,381 LB		
0086	823800000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	6,599 LB		
0087	836400000-E	450	HP12X53 STEEL PILES	555 LF		
0088	850500000-E	460	VERTICAL CONCRETE BARRIER RAIL	564.81 LF		
0089	860800000-E	876	RIP RAP CLASS II (2'-0" THICK)	700 TON		
0090	862200000-E	876	GEOTEXTILE FOR DRAINAGE	785 SY		
0091	865700000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0092	875320000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	3,106.47 LF		

Contract No **C202747**

County (ies): **Franklin**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General