

County : Greene, Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (14+92.50)	Lump Sum	L.S.	
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (30+70.00)	Lump Sum	L.S.	
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	400 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	20 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	70 SY		
0012	0335200000-E	305	15" DRAINAGE PIPE	68 LF		
0013	0343000000-E	310	15" SIDE DRAIN PIPE	24 LF		
0014	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	92 LF		
0015	1121000000-E	520	AGGREGATE BASE COURSE	50 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,260 TON		
0018	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	1,030 TON		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	125	TON	
0020	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	100	TON	
0021	2022000000-E	815	SUBDRAIN EXCAVATION	22.4	CY	
0022	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8	CY	
0023	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100	LF	
0024	2070000000-N	815	SUBDRAIN PIPE OUTLET	1	EA	
0025	2077000000-E	815	6" OUTLET PIPE	6	LF	
0026	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5	EA	
0027	2355000000-N	840	FRAME WITH GRATE, STD 840.29	4	EA	
0028	2396000000-N	840	FRAME WITH COVER, STD 840.54	1	EA	
0029	2556000000-E	846	SHOULDER BERM GUTTER	70	LF	
0030	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	1	EA	
0031	3030000000-E	862	STEEL BM GUARDRAIL	162.5	LF	
0032	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0033	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	8	EA	
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	8	EA	
0035	3360000000-E	863	REMOVE EXISTING GUARDRAIL	414	LF	
0036	3649000000-E	876	RIP RAP, CLASS B	2.2	TON	
0037	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	517	SY	
0038	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	411	SF	

County : Greene, Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	48	SF	
0040	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94	SF	
0041	4435000000-N	1135	CONES	10	EA	
0042	4445000000-E	1145	BARRICADES (TYPE III)	64	LF	
0043	4450000000-N	1150	FLAGGER	80	HR	
0044	6000000000-E	1605	TEMPORARY SILT FENCE	4,200	LF	
0045	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225	TON	
0046	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	265	TON	
0047	6012000000-E	1610	SEDIMENT CONTROL STONE	310	TON	
0048	6015000000-E	1615	TEMPORARY MULCHING	5	ACR	
0049	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200	LB	
0050	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.75	TON	
0051	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
0052	6029000000-E	SP	SAFETY FENCE	500	LF	
0053	6030000000-E	1630	SILT EXCAVATION	280	CY	
0054	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,800	SY	
0055	6037000000-E	SP	COIR FIBER MAT	10	SY	
0056	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	285	SY	
0057	6042000000-E	1632	1/4" HARDWARE CLOTH	1,125	LF	
0058	6071010000-E	SP	WATTLE	360	LF	

County : Greene, Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0059	6071020000-E	SP	POLYACRYLAMIDE (PAM)	115 LB		
0060	6071030000-E	1640	COIR FIBER BAFFLE	115 LF		
0061	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0062	6084000000-E	1660	SEEDING & MULCHING	6 ACR		
0063	6087000000-E	1660	MOWING	3 ACR		
0064	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0065	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0066	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	125 LB		
0067	6108000000-E	1665	FERTILIZER TOPDRESSING	3.25 TON		
0068	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0069	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
0070	6123000000-E	1670	REFORESTATION	0.1 ACR		

**STRUCTURE ITEMS**

0071	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (30+70.00-L-)	Lump Sum	L.S.	
0072	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+92.50-L-)	Lump Sum	L.S.	
0073	8112730000-N	450	PDA TESTING	2 EA		
0074	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (14+92.50-L-)	Lump Sum	L.S.	

County : Greene, Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (30+70.00-L-)	Lump Sum	L.S.	
0076	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	104.8 CY		
0077	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+92.50-L-)	Lump Sum	L.S.	
0078	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (30+70.00-L-)	Lump Sum	L.S.	
0079	8217000000-E	425	REINFORCING STEEL (BRIDGE)	18,066 LB		
0080	8364000000-E	450	HP12X53 STEEL PILES	1,470 LF		
0081	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	2,800 LF		
0082	8391000000-N	450	STEEL PILE POINTS	16 EA		
0083	8393000000-N	450	PILE REDRIVES	60 EA		
0084	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	571.5 LF		
0085	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	590 TON		
0086	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	650 SY		
0087	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0088	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	2,465 LF		
0089	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	840 LF		
1548/Dec07/Q43851.55/D405656240000/E89			Total Amount Of Bid For Entire Project :			

**Contract No**     **C202748**

**County (ies):**   **Greene/Pitt**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

**Contract Officer**

---

**Date**

**Execution of Contract and Bonds  
Approved as to Form:**

---

**Attorney General**

Signature Sheet (Bid - Acceptance by Department)