

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (15 + 85)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0106000000-E	230	BORROW EXCAVATION	2,600 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	1,110 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	37 TON		
001C	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	10 SY		
0011	0335200000-E	305	15" DRAINAGE PIPE	24 LF		
0012	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	2 EA		
0013	1121000000-E	520	AGGREGATE BASE COURSE	50 TON		
0014	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	700 TON		
0016	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	520 TON		
0017	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	70 TON		
0018	2000000000-N	806	RIGHT OF WAY MARKERS	10 EA		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
002C	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0021	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	330 LF		
0022	2556000000-E	846	SHOULDER BERM GUTTER	25 LF		
0023	2591000000-E	848	4" CONCRETE SIDEWALK	180 SY		
0024	2605000000-N	848	CONCRETE CURB RAMP	2 EA		
002E	3030000000-E	862	STEEL BM GUARDRAIL	200 LF		
002E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	37.5 LF		
0027	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
002E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
002E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
003C	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0031	3649000000-E	876	RIP RAP, CLASS B	2 TON		
0032	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,010 SY		
0033	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	95 LF		
0034	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
003E	4102000000-N	904	SIGN ERECTION, TYPE E	1 EA		
003E	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	1 EA		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	6	EA	
003E	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	2	EA	
0039	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1	EA	
004C	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	465	SF	
0041	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94	SF	
0042	4445000000-E	1145	BARRICADES (TYPE III)	64	LF	
0043	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	6,176	LF	
0044	5325600000-E	1510	6" WATER LINE	657	LF	
004E	5540000000-E	1515	6" VALVE	3	EA	
004E	5649000000-N	1515	RECONNECT WATER METER	1	EA	
0047	5800000000-E	1530	ABANDON 6" UTILITY PIPE	588	LF	
004E	5871400000-E	1550	TRENCHLESS INSTALLATION OF 6" IN SOIL	155	LF	
0049	5871410000-E	1550	TRENCHLESS INSTALLATION OF 6" NOT IN SOIL	155	LF	
005C	6000000000-E	1605	TEMPORARY SILT FENCE	2,010	LF	
0051	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	305	TON	
0052	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	75	TON	
0053	6012000000-E	1610	SEDIMENT CONTROL STONE	325	TON	
0054	6015000000-E	1615	TEMPORARY MULCHING	2.5	ACR	

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
005E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.5 TON		
0057	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
005E	6029000000-E	SP	SAFETY FENCE	700 LF		
005E	6030000000-E	1630	SILT EXCAVATION	170 CY		
006C	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,400 SY		
0061	6037000000-E	SP	COIR FIBER MAT	30 SY		
0062	6042000000-E	1632	1/4" HARDWARE CLOTH	800 LF		
006E	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	45 SY		
0064	6070000000-N	1639	SPECIAL STILLING BASINS	6 EA		
006E	6071010000-E	SP	WATTLE	50 LF		
006E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	10 LB		
0067	6071030000-E	1640	COIR FIBER BAFFLE	100 LF		
006E	6071050000-E	SP	*** SKIMMER (1-1/2")	3 EA		
006E	6084000000-E	1660	SEEDING & MULCHING	2.5 ACR		
007C	6087000000-E	1660	MOWING	2.5 ACR		
0071	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0072	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
007E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0074	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007E	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
007E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	16 EA		
0077	6123000000-E	1670	REFORESTATION	0.15 ACR		
STRUCTURE ITEMS						
007E	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (15 + 85.00-L-)	Lump Sum	L.S.	
007E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15 + 85.00-L-)	Lump Sum	L.S.	
008C	8105540000-E	411	3'-6" DIA DRILLED PIERS IN SOIL	41 LF		
0081	8105640000-E	411	3'-6" DIA DRILLED PIERS NOT IN SOIL	16 LF		
0082	8111400000-E	411	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	24 LF		
0083	8113000000-N	411	SID INSPECTIONS	1 EA		
0084	8115000000-N	411	CSL TESTING	1 EA		
008E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (15 + 85.00-L-)	Lump Sum	L.S.	
008E	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	28.7 CY		
0087	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	62.9 CY		
008E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15 + 85.00-L-)	Lump Sum	L.S.	
008E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	15,679 LB		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
009C	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	1,462	LB	
0091	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,729	LB	
0092	8364000000-E	450	HP12X53 STEEL PILES	280	LF	
0093	8475000000-E	460	TWO BAR METAL RAIL	140.25	LF	
0094	8482000000-E	460	THREE BAR METAL RAIL	140.25	LF	
009E	8517000000-E	460	1'-***X ***** CONCRETE PARA-PET (1'-2" X 2'-7 1/2 ")	147.75	LF	
009E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	410	TON	
0097	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	460	SY	
009E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
009E	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	2,066.75	LF	
<hr/>						
1046/Dec02/Q46015.0/D485154950000/E99			Total Amount Of Bid For Entire Project :			

Contract No **C202749**

County (ies): **Nash**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General

Signature Sheet (Bid - Acceptance by Department)