

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (24 + 50)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	40 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	300 SY		
0009	0220000000-E	SP	ROCK EMBANKMENTS	340 TON		
0010	0223000000-E	275	ROCK PLATING	330 SY		
0011	0241000000-E	SP	GENERIC GRADING ITEM FILTER FABRIC FOR ROCK EMBANKMENT	150 SY		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	30 TON		
0013	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	90 SY		
0014	0343000000-E	310	15" SIDE DRAIN PIPE	96 LF		
0015	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	156 LF		
0016	1077000000-E	SP	#57 STONE	80 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	490 TON		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	345	TON	
002C	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	465	TON	
0021	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	66	TON	
0022	2000000000-N	806	RIGHT OF WAY MARKERS	5	EA	
0023	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2	EA	
0024	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1	EA	
002E	2556000000-E	846	SHOULDER BERM GUTTER	16	LF	
0026	2830000000-N	858	ADJUSTMENT OF MANHOLES	1	EA	
0027	3030000000-E	862	STEEL BM GUARDRAIL	225	LF	
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0029	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
003C	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
0031	3649000000-E	876	RIP RAP, CLASS B	157	TON	
0032	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	972	SY	
0033	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2	EA	
0034	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	77	LF	
003E	4096000000-N	904	SIGN ERECTION, TYPE D	2	EA	
003E	4102000000-N	904	SIGN ERECTION, TYPE E	1	EA	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	16	EA	
003E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	408	SF	
003E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	104	SF	
004C	4430000000-N	1130	DRUMS	27	EA	
0041	4445000000-E	1145	BARRICADES (TYPE III)	80	LF	
0042	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	754	LF	
0043	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,508	LF	
0044	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	9	EA	
004E	6000000000-E	1605	TEMPORARY SILT FENCE	725	LF	
004E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225	TON	
0047	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	100	TON	
004E	6012000000-E	1610	SEDIMENT CONTROL STONE	275	TON	
004E	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
005C	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0051	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	2.25	TON	
0052	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
0053	6029000000-E	SP	SAFETY FENCE	700	LF	
0054	6030000000-E	1630	SILT EXCAVATION	170	CY	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6036000000-E	1631	MATTING FOR EROSION CONTROL	3,000 SY		
005E	6037000000-E	SP	COIR FIBER MAT	20 SY		
0057	6042000000-E	1632	1/4" HARDWARE CLOTH	1,300 LF		
005E	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	655 SY		
005E	6071010000-E	SP	WATTLE	150 LF		
006C	6071020000-E	SP	POLYACRYLAMIDE (PAM)	50 LB		
0061	6071030000-E	1640	COIR FIBER BAFFLE	75 LF		
0062	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		
006E	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0064	6087000000-E	1660	MOWING	1.5 ACR		
006E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
006E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0067	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
006E	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
006E	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
007C	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
0071	6123000000-E	1670	REFORESTATION	0.1 ACR		

STRUCTURE ITEMS

0072	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (24 + 50.00-L-)	Lump Sum	L.S.	
------	--------------	----	--	----------	------	--

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (24 + 50.00-L-)	Lump Sum	L.S.	
0074	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	50.2 CY		
007E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (24 + 50.00-L-)	Lump Sum	L.S.	
007E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	8,582 LB		
0077	8364000000-E	450	HP12X53 STEEL PILES	280 LF		
007E	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	440 LF		
007E	8391000000-N	450	STEEL PILE POINTS	16 EA		
008C	8475000000-E	460	TWO BAR METAL RAIL	245.5 LF		
0081	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (1'-2" X 2'-10")	260.5 LF		
0082	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	245 TON		
0083	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	280 SY		
0084	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
008E	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,430 LF		

0813/Dec05/Q27578.3/D376300110000/E85

Total Amount Of Bid For Entire Project :

Contract No **C202751**

County (ies): **Wake**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General

Signature Sheet (Bid - Acceptance by Department)