



TIP PROJECT: B-4640

STATE OF NORTH CAROLINA
 DIVISION OF HIGHWAYS
 PLAN FOR PROPOSED
 HIGHWAY EROSION CONTROL
SCOTLAND COUNTY

LOCATION: BRIDGE NO. 39 OVER US 74 BUS. AND NC 79 ON US 15-401-501
 TYPE OF WORK: GRADING, DRAINAGE, PAVING AND STRUCTURE




STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	B-4640	EC-1	
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION	

EROSION AND SEDIMENT CONTROL MEASURES

Std. #	Description	Symbol
1630.03	Temporary Silt Ditch	TD
1630.05	Temporary Diversion	TD
1605.01	Temporary Silt Fence	III III III
1606.01	Special Sediment Control Fence	III III III
1622.01	Temporary Berms and Slope Drains	TD
1630.02	Silt Basin Type B	SB
1633.01	Temporary Rock Silt Check Type-A	RS
	Temporary Rock Silt Check Type-A with Matting and Polyacrylamide (PAM)	RS
1633.02	Temporary Rock Silt Check Type-B	RS
	Wattle / Coir Fiber Wattle	W
	Wattle / Coir Fiber Wattle with Polyacrylamide (PAM)	W
1634.01	Temporary Rock Sediment Dam Type-A	SD
1634.02	Temporary Rock Sediment Dam Type-B	SD
1635.01	Rock Pipe Inlet Sediment Trap Type-A	RP
1635.02	Rock Pipe Inlet Sediment Trap Type-B	RP
1630.04	Stilling Basin	SB
1630.06	Special Stilling Basin	SB
	Rock Inlet Sediment Trap:	
1632.01	Type A	A
1632.02	Type B	B
1632.03	Type C	C
	Skimmer Basin	SK
	Tiered Skimmer Basin	SK
	Infiltration Basin	IB

THIS PROJECT CONTAINS
 EROSION CONTROL PLANS
 FOR CLEARING AND
 GRUBBING PHASE OF
 CONSTRUCTION.

GRAPHIC SCALE



ROADSIDE ENVIRONMENTAL UNIT
 DIVISION OF HIGHWAYS
 STATE OF NORTH CAROLINA

THESE EROSION AND SEDIMENT CONTROL PLANS COMPLY
 WITH THE REGULATIONS SET FORTH BY THE
 NCG-010000 GENERAL CONSTRUCTION PERMIT EFFECTIVE AUGUST 3, 2011
 ISSUED BY THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENT AND
 NATURAL RESOURCES DIVISION OF WATER QUALITY.

Prepared In the Office of:
ROADSIDE ENVIRONMENTAL UNIT
 1 South Wilmington St.
 Raleigh, NC 27611
2012 STANDARD SPECIFICATIONS




Roadway Standard Drawings

The following roadway english standards as appear in "Roadway Standard Drawings"- Roadway Design Unit - N. C. Department of Transportation - Raleigh, N. C., dated January 2012 and the latest revision thereto are applicable to this project and by reference hereby are considered a part of these plans.

1604.01 Railroad Erosion Control Detail	1632.01 Rock Inlet Sediment Trap Type A
1605.01 Temporary Silt Fence	1632.02 Rock Inlet Sediment Trap Type B
1606.01 Special Sediment Control Fence	1632.03 Rock Inlet Sediment Trap Type C
1607.01 Gravel Construction Entrance	1633.01 Temporary Rock Silt Check Type A
1622.01 Temporary Berms and Slope Drains	1633.02 Temporary Rock Silt Check Type B
1630.01 Riser Basin	1634.01 Temporary Rock Sediment Dam Type A
1630.02 Silt Basin Type B	1634.02 Temporary Rock Sediment Dam Type B
1630.03 Temporary Silt Ditch	1635.01 Rock Pipe Inlet Sediment Trap Type A
1630.04 Stilling Basin	1635.02 Rock Pipe Inlet Sediment Trap Type B
1630.05 Temporary Diversion	1640.01 Coir Fiber Baffle
1630.06 Special Stilling Basin	1645.01 Temporary Stream Crossing
1631.01 Matting Installation	


PROJECT REFERENCE NO. B-4640	SHEET NO. EC-2
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

WATTLE WITH POLYACRYLAMIDE (PAM) DETAIL




NOTES:

- USE MINIMUM 12 IN. DIAMETER EXCELSIOR WATTLE.
- USE 2 FT. WOODEN STAKES WITH A 2 IN. BY 2 IN. NOMINAL CROSS SECTION.
- ONLY INSTALL WATTLE(S) TO A HEIGHT IN DITCH SO FLOW WILL NOT WASH AROUND WATTLE AND SCOUR DITCH SLOPES AND AS DIRECTED.
- INSTALL A MINIMUM OF 2 UPSLOPE STAKES AND 4 DOWNSLOPE STAKES AT AN ANGLE TO WEDGE WATTLE TO BOTTOM OF DITCH.
- PROVIDE STAPLES MADE OF 0.125 IN. DIAMETER STEEL WIRE FORMED INTO A U SHAPE NOT LESS THAN 12" IN LENGTH.
- INSTALL STAPLES APPROXIMATELY EVERY 1 LINEAR FOOT ON BOTH SIDES OF WATTLE AND AT EACH END TO SECURE IT TO THE SOIL.
- INSTALL MATTING IN ACCORDANCE WITH SECTION 1631 OF THE STANDARD SPECIFICATIONS.
- PRIOR TO POLYACRYLAMIDE (PAM) APPLICATION, OBTAIN A SOIL SAMPLE FROM PROJECT LOCATION, AND FROM OFFSITE MATERIAL, AND ANALYZE FOR APPROPRIATE PAM FLOCCULANT TO BE APPLIED TO EACH WATTLE.
- INITIALLY APPLY 2 OUNCES OF ANIONIC OR NEUTRALLY CHARGED PAM OVER WATTLE WHERE WATER WILL FLOW AND 1 OUNCE OF PAM ON MATTING ON EACH SIDE OF WATTLE. REAPPLY PAM AFTER EVERY RAINFALL EVENT THAT IS EQUAL TO OR EXCEEDS 0.50 IN.




PROJECT REFERENCE NO. B-4640	SHEET NO. EC-2A
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

TEMPORARY ROCK SILT CHECK TYPE 'A' WITH EXCELSIOR MATTING AND POLYACRYLAMIDE (PAM)



PLAN




SECTION A-A

NOTES


USE EXCELSIOR FOR MATTING MATERIAL AND ANCHOR MATTING SECTION AT TOP AND BOTTOM WITH CLASS B STONE.

PRIOR TO POLYACRYLAMIDE (PAM) APPLICATION, OBTAIN A SOIL SAMPLE FROM PROJECT LOCATION, AND FROM OFFSITE MATERIAL, AND ANALYZE FOR APPROPRIATE PAM FLOCCULANT TO BE APPLIED TO EACH ROCK SILT CHECK.

INITIALLY APPLY 3.5 OUNCES OF POLYACRYLAMIDE (PAM) TO TOP OF MATTING SECTION AND AFTER EVERY RAINFALL EVENT THAT EQUALS OR EXCEEDS 0.50 INCHES.



INSET A



SECTION B-B

*T = 12" MIN., 18" MAX.

NOT TO SCALE

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA


PROJECT REFERENCE NO. <i>B-4640</i>	SHEET NO. <i>EC-3</i>
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

SOIL STABILIZATION TIMEFRAMES

<i>SITE DESCRIPTION</i>	<i>STABILIZATION TIME</i>	<i>TIMEFRAME EXCEPTIONS</i>
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HQW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.
SLOPES 3:1 OR FLATTER	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	NONE, EXCEPT FOR PERIMETERS AND HQW ZONES.

PROJECT REFERENCE NO.	SHEET NO.
B-4640	EC-4/CONST.4
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

CLEARING AND GRUBBING
EROSION CONTROL FOR
CONSTRUCTION SHEET 4




NOTE:
PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B
AND TEMPORARY ROCK SILT CHECKS TYPE - A AT
DRAINAGE OUTLETS.


BEGIN TIP PROJECT B-4640
-L- STA 19+50.00

-L-
PI Sta 13+73.06
 $\Delta = 9' 42' 25.9''$ (RT)
D = 1' 29' 22.1"
L = 651.72'
T = 326.64'
R = 3,846.72'

54 x 12 x 3
ID 4.1 F



MATCH LINE -L- STA 27+50.00
SEE SHEET 5



FOR -L- PROFILE, SEE SHEET 6
FOR DETOUR, SEE SHEETS 2B AND 2C
FOR STRUCTURE PLANS, SEE SHEET S-1 TO S-


5/14/99
21-OCT-2011 14:41
R:\Environmental\10393\B4640.EC-pah-4.dgn
mmf:ferdash

5/14/99


PROJECT REFERENCE NO.		SHEET NO.	
B-4640		EC-5/CONST.5	
RW SHEET NO.			
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	

CLEARING AND GRUBBING
EROSION CONTROL FOR
CONSTRUCTION SHEET 5

NOTE:
PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B
AND TEMPORARY ROCK SILT CHECKS TYPE - A AT
DRAINAGE OUTLETS.



SEE SHEET 4
MATCH LINE -L- STA 27+50.00



NOTE:
USE 3:1 SIDE SLOPES FROM
STA 23+30 TO 24+00 -L- DET - LT
AND FROM STA 30+00 TO
31+00 -L- RT

NOTE:
MAINTAIN OPENING
DURING ALL PHASES OF
CONSTRUCTION


FOR -L- PROFILE, SEE SHEET 6
FOR DETOUR, SEE SHEETS 2B AND 2C

21-OCT-2011 14:44
R:\E:\pmm\10111444\10111444.dwg
R:\E:\pmm\10111444\10111444.dwg
R:\E:\pmm\10111444\10111444.dwg

5/14/99

PROJECT REFERENCE NO.		SHEET NO.	
B-4640		EC-6/CONST.2B	
R/W SHEET NO.			
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	

-L DETOUR- PLAN SHEET



-L DETOUR-

PI Sta 11+08.36	PI Sta 13+94.77
$\Delta = 8^{\circ}25'22.7" (RT)$	$\Delta = 8^{\circ}25'22.7" (LT)$
$D = 4'46'28.7"$	$D = 4'46'28.7"$
$L = 176.4'$	$L = 176.4'$
$T = 88.36'$	$T = 88.36'$
$R = 1,200.00'$	$R = 1,200.00'$

BEGIN DETOUR CONSTRUCTION
-L DETOUR- STA 10+59.00



MATCH LINE -L DETOUR- STA 20+50.00
SEE SHEET 2C

FOR -L DETOUR- PROFILE, SEE SHEET 6

R:\E...21-OCT-2011 11:30 am\T...S...S...4640.EC.psh..2B.dgn

PROJECT REFERENCE NO.	SHEET NO.
B-4640	EC-7/CONST.2C
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

-L DETOUR- PLAN SHEET



SEE SHEET 2B
MATCH LINE -L DETOUR- STA 20+50.00

END DETOUR CONSTRUCTION
-L DETOUR- STA 27+03.78


TO RAEFORD →

FIRST PENTECOSTAL HOLINESS CHURCH
DB 760 PG 227

5/14/99
21-OCT-2011 15:32
R:\Environmental\Design\B4640_EC_psh_2C.dgn
Printed at: REN\240378


FOR -L DETOUR- PROFILE, SEE SHEET 7

PROJECT REFERENCE NO.	SHEET NO.
B-4640	EC-8/CONST.4
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER



BEGIN TIP PROJECT B-4640
-L- STA 19+50.00

-L-
 PI Sta 13+73.06
 $\Delta = 9' 42" 25.9" (RT)$
 $D = 1' 29" 22.1"$
 $L = 651.72'$
 $T = 326.64'$
 $R = 3,846.72'$



54 x 12 x 3
 ID 4.1 F



-Y-
 PI Sta 15+02.24
 $\Delta = 20' 34" 53.1" (LT)$
 $D = 2' 30" 00.0"$
 $L = 823.26'$
 $T = 416.11'$
 $R = 2,291.83'$

MATCH LINE -L- STA 27+50.00
 SEE SHEET 5

FOR -L- PROFILE, SEE SHEET 6
 FOR DETOUR, SEE SHEETS 2B AND 2C
 FOR STRUCTURE PLANS, SEE SHEET S-1 TO S-

5/14/99
 21-OCT-2011 14:42
 R:\Environment\B-4640-EC.psh_4.dgn

PROJECT REFERENCE NO.	SHEET NO.
B-4640	EC-9/CONST.5
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER



5/14/99

21-OCT-2011 14:45
 P:\Environment\B-4640\B-4640-EC.psh_5.dgn
 10/29/2011 10:14:45
 10/29/2011 10:14:45

FOR -L- PROFILE, SEE SHEET 6
 FOR DETOUR, SEE SHEETS 2B AND 2C