

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	1,350 CY		
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (13 + 29.00)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	220 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	200 SY		
0008	0314000000-E	SP	SELECT MATERIAL, CLASS ***** (II)	200 TON		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	10 TON		
0010	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	20 SY		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	24 LF		
0012	0344000000-E	310	18" SIDE DRAIN PIPE	32 LF		
0013	0995000000-E	340	PIPE REMOVAL	24 LF		
0014	0996000000-N	350	PIPE CLEAN-OUT	1 EA		
0015	1099500000-E	505	SHALLOW UNDERCUT	50 CY		
0016	1099700000-E	505	CLASS IV SUBGRADE STABILIZA- TION	100 TON		
0017	1121000000-E	520	AGGREGATE BASE COURSE	36 TON		
0018	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	290 TON		
0020	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	180 TON		
0021	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	25 TON		
0022	2000000000-N	806	RIGHT OF WAY MARKERS	12 EA		
0023	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY		
0024	2033000000-E	815	SUBDRAIN FINE AGGREGATE	33.6 CY		
0025	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0026	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0027	2077000000-E	815	6" OUTLET PIPE	6 LF		
0028	3030000000-E	862	STEEL BM GUARDRAIL	25 LF		
0029	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	2 EA		
0030	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350 TL-2)	4 EA		
0031	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0032	3574000000-E	867	GENERIC FENCING ITEM WOOD RAIL FENCE RESET	60 LF		
0033	3649000000-E	876	RIP RAP, CLASS B	8 TON		
0034	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	745 SY		
0035	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	260 SF		
0036	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	304 SF		

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	72	SF	
003E	4430000000-N	1130	DRUMS	56	EA	
003E	4445000000-E	1145	BARRICADES (TYPE III)	32	LF	
004C	4516000000-N	1180	SKINNY DRUM	12	EA	
0041	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,480	LF	
0042	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	9	EA	
0043	6000000000-E	1605	TEMPORARY SILT FENCE	950	LF	
0044	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	170	TON	
004E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	150	TON	
004E	6012000000-E	1610	SEDIMENT CONTROL STONE	145	TON	
0047	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
004E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25	TON	
005C	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
0051	6029000000-E	SP	SAFETY FENCE	100	LF	
0052	6030000000-E	1630	SILT EXCAVATION	270	CY	
0053	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,400	SY	
0054	6037000000-E	SP	COIR FIBER MAT	400	SY	
005E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	30	SY	

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6042000000-E	1632	1/4" HARDWARE CLOTH	70 LF		
0057	6070000000-N	1639	SPECIAL STILLING BASINS	4 EA		
0058	6071010000-E	SP	WATTLE	450 LF		
0059	6071020000-E	SP	POLYACRYLAMIDE (PAM)	115 LB		
0060	6071030000-E	1640	COIR FIBER BAFFLE	40 LF		
0061	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0062	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0063	6087000000-E	1660	MOWING	0.5 ACR		
0064	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0065	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0066	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0067	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0068	6114500000-N	1667	SPECIALIZED HAND MOWING	15 MHR		
0069	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		

---

**STRUCTURE ITEMS**


---

0070	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (13+29.00-L-)	Lump Sum	L.S.	
0071	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+29.00-L-)	Lump Sum	L.S.	

---

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	28.6	LF	
0073	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	21	LF	
0074	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	15.6	LF	
007E	8113000000-N	411	SID INSPECTIONS	2	EA	
007E	8115000000-N	411	CSL TESTING	1	EA	
0077	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (13+29.00-L-)	Lump Sum	L.S.	
007E	8156000000-E	SP	CONCRETE WEARING SURFACE	2,998	SF	
007E	8161000000-E	420	GROOVING BRIDGE FLOORS	3,253	SF	
008C	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	39.6	CY	
0081	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (13+29.00-L-)	Lump Sum	L.S.	
0082	8217000000-E	425	REINFORCING STEEL (BRIDGE)	10,428	LB	
0083	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	894	LB	
0084	8364000000-E	450	HP12X53 STEEL PILES	125	LF	
008E	8468000000-E	460	ONE BAR METAL RAIL	200.07	LF	
008E	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (1'-0" x 2'-0 1/2")	215.17	LF	
0087	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	370	TON	
008E	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	410	SY	

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
009C	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	1,075.83 LF		
1623/Feb08/Q35009.02/D422516250000/E90			Total Amount Of Bid For Entire Project :			

**Contract No.**     **C202782**

**County (ies):**   **Caldwell**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General