

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0000930000-E	SP	GENERIC MISCELLANEOUS ITEM ROCK ANCHORS FOR WIRE MESH	200 LF		
0004	0000960000-E	SP	GENERIC MISCELLANEOUS ITEM REINFORCED SOIL SLOPES WITH GEOCELL FACING	230 SY		
0005	0000960000-E	SP	GENERIC MISCELLANEOUS ITEM WIRE MESH	225 SY		
0006	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+96-L-)	Lump Sum	L.S.	
0007	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0008	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0009	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0010	0098000000-E	SP	PRE-SPLITTING OF ROCK	650 SY		
0011	0106000000-E	230	BORROW EXCAVATION	6,000 CY		
0012	0134000000-E	240	DRAINAGE DITCH EXCAVATION	20 CY		
0013	0195000000-E	265	SELECT GRANULAR MATERIAL	250 CY		
0014	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	350 SY		
0015	0199000000-E	SP	TEMPORARY SHORING	2,080 SF		
0016	0223000000-E	275	ROCK PLATING	1,535 SY		
0017	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	90 TON		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0320000000-E	300	FOUNDATION CONDITIONING GEO-TEXTILE	280	SY	
001E	0335200000-E	305	15" DRAINAGE PIPE	692	LF	
002C	0335300000-E	305	18" DRAINAGE PIPE	58	LF	
0021	0335500000-E	305	30" DRAINAGE PIPE	88	LF	
0022	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	2	EA	
0023	0453000000-E	310	*** PIPE END SECTION (18")	1	EA	
0024	0995000000-E	340	PIPE REMOVAL	90	LF	
002E	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	100	TON	
002E	1121000000-E	520	AGGREGATE BASE COURSE	43	TON	
0027	1220000000-E	545	INCIDENTAL STONE BASE	150	TON	
002E	1275000000-E	600	PRIME COAT	41	GAL	
002E	1330000000-E	607	INCIDENTAL MILLING	225	SY	
003C	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,590	TON	
0031	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	800	TON	
0032	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,040	TON	
0033	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	175	TON	
0034	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	500	TON	
003E	2022000000-E	815	SUBDRAIN EXCAVATION	44.8	CY	

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	2033000000-E	815	SUBDRAIN FINE AGGREGATE	33.6	CY	
0037	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200	LF	
003E	2070000000-N	815	SUBDRAIN PIPE OUTLET	1	EA	
0039	2077000000-E	815	6" OUTLET PIPE	6	LF	
004C	2264000000-E	840	PIPE PLUGS	0.13	CY	
0041	2275000000-E	SP	FLOWABLE FILL	2.29	CY	
0042	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	15	EA	
0043	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	12.5	LF	
0044	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2	EA	
004E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	8	EA	
0046	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1	EA	
0047	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	2	EA	
004E	2396000000-N	840	FRAME WITH COVER, STD 840.54	2	EA	
0049	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	440	LF	
005C	2556000000-E	846	SHOULDER BERM GUTTER	140	LF	
0051	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	650	LF	
0052	2703000000-E	854	CONCRETE BARRIER, TYPE ***** (I)	210	LF	
0053	3030000000-E	862	STEEL BM GUARDRAIL	700	LF	

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	75 LF		
005E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	20 EA		
005E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0057	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
005E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
005E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
006C	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	2 EA		
0061	3360000000-E	863	REMOVE EXISTING GUARDRAIL	377 LF		
0062	3382000000-E	862	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)	87.5 LF		
0063	3387000000-N	862	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (AT-1)	1 EA		
0064	3387000000-N	862	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (B-77)	1 EA		
006E	3435000000-N	SP	GENERIC GUARDRAIL ITEM EXTRA LENGTH GUARDRAIL POST 8' STEEL	22 EA		
006E	3500000000-E	866	WOVEN WIRE FENCE, *** FABRIC (48")	160 LF		
0067	3506000000-E	866	4" TIMBER FENCE POSTS, ***** LONG (8')	10 EA		
006E	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	4 EA		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
006E	3628000000-E	876	RIP RAP, CLASS I	1,500	TON	
007C	3649000000-E	876	RIP RAP, CLASS B	15	TON	
0071	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,600	SY	
0072	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	610	SF	
007E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	80	SF	
0074	4430000000-N	1130	DRUMS	135	EA	
007E	4435000000-N	1135	CONES	25	EA	
007E	4445000000-E	1145	BARRICADES (TYPE III)	264	LF	
0077	4455000000-N	1150	FLAGGER	1,000	DAY	
007E	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	8	EA	
007E	4485000000-E	1170	PORTABLE CONCRETE BARRIER	580	LF	
008C	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	660	LF	
0081	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	1,840	LF	
0082	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	25,896	LF	
008E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	186	LF	
0084	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	920	LF	
008E	6000000000-E	1605	TEMPORARY SILT FENCE	2,500	LF	
008E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	430	TON	

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0087	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	320 TON		
008E	6012000000-E	1610	SEDIMENT CONTROL STONE	570 TON		
008E	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
009C	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0091	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.75 TON		
0092	6024000000-E	1622	TEMPORARY SLOPE DRAINS	300 LF		
0093	6029000000-E	SP	SAFETY FENCE	300 LF		
0094	6030000000-E	1630	SILT EXCAVATION	560 CY		
009E	6036000000-E	1631	MATTING FOR EROSION CONTROL	11,000 SY		
009E	6037000000-E	SP	COIR FIBER MAT	20 SY		
0097	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	50 SY		
009E	6042000000-E	1632	1/4" HARDWARE CLOTH	825 LF		
009E	6070000000-N	1639	SPECIAL STILLING BASINS	12 EA		
010C	6071010000-E	SP	WATTLE	425 LF		
0101	6071020000-E	SP	POLYACRYLAMIDE (PAM)	150 LB		
0102	6071030000-E	1640	COIR FIBER BAFFLE	200 LF		
0103	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		
0104	6084000000-E	1660	SEEDING & MULCHING	4.1 ACR		
010E	6087000000-E	1660	MOWING	3 ACR		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0107	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0108	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	125 LB		
0109	6108000000-E	1665	FERTILIZER TOPDRESSING	3.25 TON		
011C	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0111	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
0112	6123000000-E	1670	REFORESTATION	0.2 ACR		
<b>STRUCTURE ITEMS</b>						
0113	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (17+96.00-L-)	Lump Sum	L.S.	
0114	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+96.00-L-)	Lump Sum	L.S.	
011E	8105660000-E	411	4'-0" DIA DRILLED PIERS IN SO IL	228 LF		
0116	8105660000-E	411	4'-0" DIA DRILLED PIERS NOT IN SOIL	105 LF		
0117	8111600000-E	411	PERMANENT STEEL CASING FOR 4'-0" DIA DRILLED PIER	66.6 LF		
011E	8113000000-N	411	SID INSPECTIONS	6 EA		
0119	8114000000-N	411	SPT TESTING	6 EA		
012C	8115000000-N	411	CSL TESTING	1 EA		
0121	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	9,435 SF		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0122	8161000000-E	420	GROOVING BRIDGE FLOORS	9,396 SF		
0123	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	164.6 CY		
0124	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+96.00-L-)	Lump Sum	L.S.	
0125	8217000000-E	425	REINFORCING STEEL (BRIDGE)	51,702 LB		
0126	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	10,650 LB		
0127	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	1,232.88 LF		
0128	8364000000-E	450	HP12X53 STEEL PILES	920 LF		
0129	8475000000-E	460	TWO BAR METAL RAIL	170.6 LF		
0130	8482000000-E	460	THREE BAR METAL RAIL	170.6 LF		
0131	8517000000-E	460	1'-**"X ***** CONCRETE PARA- PET (1'-2"X2'-6")	178.1 LF		
0132	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	451 TON		
0133	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	500 SY		
0134	8657000000-N	430	ELASTOMERIC BEARINGS (17+96.00-L-)	Lump Sum	L.S.	

0908/Feb06/Q159587.75/D534801330000/E134

Total Amount Of Bid For Entire Project :



**Contract No.**     **C201166**

**County (ies):**    **Jackson**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General