

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0022000000-E	225	UNCLASSIFIED EXCAVATION	31,900 CY		
0005	0036000000-E	225	UNDERCUT EXCAVATION	1,650 CY		
0006	0106000000-E	230	BORROW EXCAVATION	18,000 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	640 CY		
0008	0141000000-E	240	BERM DITCH CONSTRUCTION	500 LF		
0009	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	11,500 SY		
0010	0192000000-N	260	PROOF ROLLING	10 HR		
0011	0195000000-E	265	SELECT GRANULAR MATERIAL	1,500 CY		
0012	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	2,100 SY		
0013	0199000000-E	SP	TEMPORARY SHORING	1,500 SF		
0014	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	470 TON		
0015	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	2,010 SY		
0016	0335200000-E	305	15" DRAINAGE PIPE	492 LF		
0017	0335300000-E	305	18" DRAINAGE PIPE	276 LF		
0018	0335400000-E	305	24" DRAINAGE PIPE	332 LF		
0019	0335500000-E	305	30" DRAINAGE PIPE	104 LF		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
002C	0335700000-E	305	42" DRAINAGE PIPE	48 LF		
0021	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	5 EA		
0022	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (18")	1 EA		
0023	0344000000-E	310	18" SIDE DRAIN PIPE	36 LF		
0024	0354000000-E	310	**** RC PIPE CULVERTS, CLASS ***** (15", V)	756 LF		
002E	0354000000-E	310	**** RC PIPE CULVERTS, CLASS ***** (30", V)	144 LF		
0026	0354000000-E	310	**** RC PIPE CULVERTS, CLASS ***** (60", V)	132 LF		
0027	0354000000-E	310	**** RC PIPE CULVERTS, CLASS ***** (66", V)	120 LF		
002E	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	48 LF		
002E	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	224 LF		
003C	0995000000-E	340	PIPE REMOVAL	794 LF		
0031	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0032	1110000000-E	510	STABILIZER AGGREGATE	500 TON		
0033	1220000000-E	545	INCIDENTAL STONE BASE	1,000 TON		
0034	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	750 TON		
003E	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	13,000 TON		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	360 TON		
0037	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	12,530 TON		
0038	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	780 TON		
0039	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	11,280 TON		
004C	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	1,940 TON		
0041	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	421 TON		
0042	2000000000-N	806	RIGHT OF WAY MARKERS	41 EA		
0043	2020000000-N	806	CONTROL OF ACCESS MARKERS	8 EA		
0044	2022000000-E	815	SUBDRAIN EXCAVATION	67.2 CY		
004E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	33.6 CY		
004E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0047	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
004E	2077000000-E	815	6" OUTLET PIPE	6 LF		
004E	2209000000-E	838	ENDWALLS	4.5 CY		
005C	2220000000-E	838	REINFORCED ENDWALLS	11.9 CY		
0051	2253000000-E	840	PIPE COLLARS	2.225 CY		
0052	2275000000-E	SP	FLOWABLE FILL	3 CY		
0053	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	18 EA		
0054	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	0.52 LF		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	7 EA		
005E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	3 EA		
0057	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	7 EA		
005E	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLET	5 EA		
005E	2538000000-E	846	***.*** CONCRETE CURB & GUTTER (2'-9")	700 LF		
006C	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	8,550 LF		
0061	2556000000-E	846	SHOULDER BERM GUTTER	560 LF		
0062	2619000000-E	850	4" CONCRETE PAVED DITCH	25 SY		
006E	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	1,060 SY		
0064	3030000000-E	862	STEEL BM GUARDRAIL	1,187.5 LF		
006E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
006E	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	4 EA		
0067	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
006E	3360000000-E	863	REMOVE EXISTING GUARDRAIL	927 LF		
006E	3628000000-E	876	RIP RAP, CLASS I	550 TON		
007C	3635000000-E	876	RIP RAP, CLASS II	250 TON		
0071	3649000000-E	876	RIP RAP, CLASS B	120 TON		
0072	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	3,140 SY		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	1,244		LF
0074	4096000000-N	904	SIGN ERECTION, TYPE D	4		EA
007E	4102000000-N	904	SIGN ERECTION, TYPE E	49		EA
007E	4108000000-N	904	SIGN ERECTION, TYPE F	10		EA
0077	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	1		EA
007E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	26		EA
007E	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1		EA
008C	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	270		SF
0081	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	336		SF
0082	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	80		SF
0083	4415000000-N	1115	FLASHING ARROW BOARD	3		EA
0084	4422000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN (SHORT TERM)	90		DAY
008E	4430000000-N	1130	DRUMS	300		EA
008E	4435000000-N	1135	CONES	50		EA
0087	4445000000-E	1145	BARRICADES (TYPE III)	192		LF
008E	4450000000-N	1150	FLAGGER	1,440		HR
008E	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	8		EA
009C	4480000000-N	1165	TMA	2		EA
0091	4485000000-E	1170	PORTABLE CONCRETE BARRIER	400		LF

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	500 LF		
0093	4507000000-E	1170	WATER FILLED BARRIER	52 LF		
0094	4508000000-E	1170	RESET WATER FILLED BARRIER	52 LF		
009E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	339 EA		
009E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	22,313 LF		
0097	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	13,207 LF		
009E	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,099 LF		
009E	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	250 LF		
010C	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	215 LF		
0101	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	722 LF		
0102	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	22 EA		
0103	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	84 EA		
0104	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	89,636 LF		
010E	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	1,970 LF		
010E	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	430 LF		
0107	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	830 LF		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010E	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	18	EA	
010E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	27	EA	
011C	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	19,042	LF	
0111	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	532	LF	
0112	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	310	LF	
0113	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	23	EA	
0114	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	722	EA	
011E	5325600000-E	1510	6" WATER LINE	45	LF	
011E	5326200000-E	1510	12" WATER LINE	890	LF	
0117	5546000000-E	1515	8" VALVE	1	EA	
011E	5558000000-E	1515	12" VALVE	1	EA	
011E	5589200000-E	1515	2" AIR RELEASE VALVE	1	EA	
012C	5648000000-N	1515	RELOCATE WATER METER	5	EA	
0121	5672000000-N	1515	RELOCATE FIRE HYDRANT	6	EA	
0122	5709400000-E	1520	8" FORCE MAIN SEWER	920	LF	
0123	5709500000-E	1520	10" FORCE MAIN SEWER	40	LF	
0124	6000000000-E	1605	TEMPORARY SILT FENCE	4,915	LF	
012E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	1,165	TON	

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0126	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	800 TON		
0127	6012000000-E	1610	SEDIMENT CONTROL STONE	440 TON		
012E	6015000000-E	1615	TEMPORARY MULCHING	40 ACR		
0129	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,300 LB		
013C	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	6.5 TON		
0131	6024000000-E	1622	TEMPORARY SLOPE DRAINS	945 LF		
0132	6029000000-E	SP	SAFETY FENCE	300 LF		
013E	6030000000-E	1630	SILT EXCAVATION	5,770 CY		
0134	6036000000-E	1631	MATTING FOR EROSION CONTROL	29,250 SY		
013E	6037000000-E	SP	COIR FIBER MAT	180 SY		
013E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	4,830 SY		
0137	6042000000-E	1632	1/4" HARDWARE CLOTH	875 LF		
013E	6071012000-E	SP	COIR FIBER WATTLE	3,780 LF		
013E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	1,420 LB		
014C	6071030000-E	1640	COIR FIBER BAFFLE	1,730 LF		
0141	6071050000-E	SP	*** SKIMMER (1-1/2")	17 EA		
0142	6084000000-E	1660	SEEDING & MULCHING	36 ACR		
014E	6087000000-E	1660	MOWING	20 ACR		
0144	6090000000-E	1661	SEED FOR REPAIR SEEDING	450 LB		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
014E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1.25 TON		
014E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	800 LB		
0147	6108000000-E	1665	FERTILIZER TOPDRESSING	23.5 TON		
014E	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
014E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	75 EA		
015C	6123000000-E	1670	REFORESTATION	0.5 ACR		
0151	7060000000-E	1705	SIGNAL CABLE	6,942 LF		
0152	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	56 EA		
0153	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	8 EA		
0154	7204000000-N	1705	LOUVER	2 EA		
015E	7264000000-E	1710	MESSENGER CABLE (3/8")	3,010 LF		
015E	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	2,270 LF		
0157	7300100000-E	1715	UNPAVED TRENCHING FOR TEMP- ORARY LEAD-IN	2,460 LF		
015E	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	23 EA		
015E	7360000000-N	1720	WOOD POLE	8 EA		
016C	7372000000-N	1721	GUY ASSEMBLY	22 EA		
0161	7408000000-E	1722	1" RISER WITH WEATHERHEAD	2 EA		
0162	7420000000-E	1722	2" RISER WITH WEATHERHEAD	5 EA		
0163	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	6,482 LF		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0164	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	15,717	LF	
016E	7576000000-N	SP	METAL STRAIN SIGNAL POLE	12	EA	
016E	7613000000-N	SP	SOIL TEST	12	EA	
0167	7614100000-E	SP	DRILLED PIER FOUNDATION	84	CY	
016E	7636000000-N	1745	SIGN FOR SIGNALS	20	EA	
016E	7684000000-N	1750	SIGNAL CABINET FOUNDATION	2	EA	
017C	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	2	EA	
0171	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1	EA	
0172	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	12	EA	
017E	7901000000-N	1753	CABINET BASE EXTENDER	2	EA	
0957/Jan31/Q390510.695/D680730012000/E173			Total Amount Of Bid For Entire Project :			

Contract No. **C202786**

County (ies): **Johnston**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General