

County : Swain, Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1330000000-E	607	INCIDENTAL MILLING	1,572	SY	
0003	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	95	TON	
0004	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	7	TON	
0005	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	662	SF	
0006	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	480	SF	
0007	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	46	SF	
0008	4415000000-N	1115	FLASHING ARROW BOARD	6	EA	
0009	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	3	EA	
0010	4430000000-N	1130	DRUMS	96	EA	
0011	4445000000-E	1145	BARRICADES (TYPE III)	16	LF	
0012	4455000000-N	1150	FLAGGER	152	DAY	
0013	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1	EA	
0014	4470000000-N	1160	RESET TEMPORARY CRASH CUSHION	15	EA	
0015	4480000000-N	1165	TMA	2	EA	
0016	4485000000-E	1170	PORTABLE CONCRETE BARRIER	1,120	LF	
0017	4500000000-E	1170	RESET PORTABLE CONCRETE BAR- RIER	13,480	LF	
0018	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,650	LF	
0019	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	464	LF	

County : Swain, Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
002C	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	1 EA		
0021	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (HIGHLY REFLECTIVE ELEMENTS)	7,995 LF		
0022	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	48 EA		
0023	8161000000-E	420	GROOVING BRIDGE FLOORS	119,494 SF		
0024	8573000000-E	SP	LATEX MODIFIED CONC OVERLAY	573 CY		
002E	8580000000-E	SP	PLACING & FINISHING OF LATEX MODIFIED CONC OVERLAY	11,163 SY		
002E	8664000000-E	SP	SHOTCRETE REPAIRS	662 CF		
0027	8678000000-E	SP	EPOXY RESIN INJECTION	284 LF		
002E	8692000000-N	SP	FOAM JOINT SEALS	Lump Sum	L.S.	
002E	8860000000-N	SP	GENERIC STRUCTURE ITEM BRIDGE JACKING	Lump Sum	L.S.	
003C	8860000000-N	SP	GENERIC STRUCTURE ITEM UNDER STRUCTURE WORK PLATFORM	Lump Sum	L.S.	
0031	8881000000-E	SP	GENERIC STRUCTURE ITEM LATEX MOD CONC OVERLAY, VERY EARLY STRENGTH	175 CY		
0032	8893000000-E	SP	GENERIC STRUCTURE ITEM HYDRO-DEMOLITION OF BRIDGE DECK	14,552 SY		
0033	8893000000-E	SP	GENERIC STRUCTURE ITEM PLACING & FINISHING OF LATEX MOD CONC OVERLAY, VERY EARLY STRENGTH	3,389 SY		
0034	8893000000-E	SP	GENERIC STRUCTURE ITEM SCARIFYING BRIDGE DECK	14,552 SY		

Contract No. **C202972**

County (ies): **Haywood, Swain**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General