

County : Alleghany

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0003	0015000000-N	205	SEALING ABANDONED WELLS	1 EA		
0004	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (16+30.00)	Lump Sum	L.S.	
0005	0057000000-E	226	UNDERCUT EXCAVATION	50 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	4,200 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	40 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0010	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	100 SY		
0011	0199000000-E	SP	TEMPORARY SHORING	78.2 SF		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	20 TON		
0013	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	60 SY		
0014	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	128 LF		
0015	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	32 LF		
0016	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	2 EA		
0017	0995000000-E	340	PIPE REMOVAL	58 LF		
0018	1099500000-E	505	SHALLOW UNDERCUT	100 CY		

County : Alleghany

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	100 TON		
0020	1121000000-E	520	AGGREGATE BASE COURSE	141 TON		
0021	1220000000-E	545	INCIDENTAL STONE BASE	75 TON		
0022	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	260 TON		
0023	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	290 TON		
0024	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	35 TON		
0025	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	10 TON		
0026	2000000000-N	806	RIGHT OF WAY MARKERS	15 EA		
0027	2022000000-E	815	SUBDRAIN EXCAVATION	36 CY		
0028	2033000000-E	815	SUBDRAIN FINE AGGREGATE	27 CY		
0029	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0030	2077000000-E	815	6" OUTLET PIPE	6 LF		
0031	2132000000-N	816	CONCRETE PAD FOR SHOULDER DRAIN PIPE OUTLET	1 EA		
0032	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0033	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0034	2556000000-E	846	SHOULDER BERM GUTTER	40 LF		
0035	3030000000-E	862	STEEL BM GUARDRAIL	287.5 LF		
0036	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	3 EA		
0037	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		

County : Alleghany

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0039	3360000000-E	863	REMOVE EXISTING GUARDRAIL	687 LF		
0040	3580000000-E	866	GENERIC FENCING ITEM 3 STRAND BARBED WIRE FENCE WITH POSTS (TEMPORARY)	200 LF		
0041	3649000000-E	876	RIP RAP, CLASS B	140 TON		
0042	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,135 SY		
0043	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	48 SF		
0044	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0045	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	20 SF		
0046	4430000000-N	1130	DRUMS	51 EA		
0047	4445000000-E	1145	BARRICADES (TYPE III)	32 LF		
0048	4455000000-N	1150	FLAGGER	720 DAY		
0049	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
0050	4480000000-N	1165	TMA	1 EA		
0051	4485000000-E	1170	PORTABLE CONCRETE BARRIER	200 LF		
0052	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	12 EA		
0053	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	11,944 LF		
0054	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	10 EA		
0055	6000000000-E	1605	TEMPORARY SILT FENCE	1,450 LF		
0056	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	270 TON		

County : Alleghany

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	250 TON		
0058	6012000000-E	1610	SEDIMENT CONTROL STONE	225 TON		
0059	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0060	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0061	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25 TON		
0062	6024000000-E	1622	TEMPORARY SLOPE DRAINS	270 LF		
0063	6029000000-E	SP	SAFETY FENCE	200 LF		
0064	6030000000-E	1630	SILT EXCAVATION	400 CY		
0065	6036000000-E	1631	MATTING FOR EROSION CONTROL	3,000 SY		
0066	6037000000-E	SP	COIR FIBER MAT	350 SY		
0067	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	150 SY		
0068	6042000000-E	1632	1/4" HARDWARE CLOTH	250 LF		
0069	6070000000-N	1639	SPECIAL STILLING BASINS	4 EA		
0070	6071010000-E	SP	WATTLE	260 LF		
0071	6071020000-E	SP	POLYACRYLAMIDE (PAM)	100 LB		
0072	6071030000-E	1640	COIR FIBER BAFFLE	115 LF		
0073	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		
0074	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
0075	6087000000-E	1660	MOWING	1 ACR		
0076	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		

County : Alleghany

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0077	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0078	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0079	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0080	6114500000-N	1667	SPECIALIZED HAND MOWING	20 MHR		
0081	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		
0082	6123000000-E	1670	REFORESTATION	0.2 ACR		

STRUCTURE ITEMS

0083	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+30.00-L-)	Lump Sum	L.S.	
0084	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	28 LF		
0085	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	26 LF		
0086	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	18 LF		
0087	8113000000-N	411	SID INSPECTIONS	1 EA		
0088	8115000000-N	411	CSL TESTING	1 EA		
0089	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	48.6 CY		
0090	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+30.00-L-)	Lump Sum	L.S.	
0091	8217000000-E	425	REINFORCING STEEL (BRIDGE)	14,144 LB		
0092	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,419 LB		

County : Alleghany

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	8364000000-E	450	HP12X53 STEEL PILES	385 LF		
0094	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	250.51 LF		
0095	8590000000-E	876	RIP RAP, CLASS ** (I)	65 TON		
0096	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	387 TON		
0097	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	502 SY		
0098	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0099	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	605 LF		
0100	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	770 LF		

1552/Mar09/Q48108.26/D435694250000/E100

Total Amount Of Bid For Entire Project :

Contract No. C202811

County (ies): Alleghany

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General