

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0015000000-N	205	SEALING ABANDONED WELLS	1 EA		
0006	0022000000-E	225	UNCLASSIFIED EXCAVATION	87,000 CY		
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (76+15.21)	Lump Sum	L.S.	
0008	0036000000-E	225	UNDERCUT EXCAVATION	1,400 CY		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	1,537 CY		
0010	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	17,250 SY		
0011	0163000000-E	250	REMOVAL OF EXISTING CONCRETE PAVEMENT	7,600 SY		
0012	0195000000-E	265	SELECT GRANULAR MATERIAL	2,000 CY		
0013	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	14,600 SY		
0014	0199000000-E	SP	TEMPORARY SHORING	2,500 SF		
0015	0223000000-E	275	ROCK PLATING	2,000 SY		
0016	0255000000-E	SP	GENERIC GRADING ITEM EXCAVATION, HAULING, AND DISPOSAL OF CONTAMINATED SOIL	100 TON		
0017	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	1,620 TON		
0018	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	6,170 SY		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	033500000-E	305	*** DRAINAGE PIPE (8")	24 LF		
0020	033520000-E	305	15" DRAINAGE PIPE	1,396 LF		
0021	033530000-E	305	18" DRAINAGE PIPE	1,416 LF		
0022	033540000-E	305	24" DRAINAGE PIPE	328 LF		
0023	033550000-E	305	30" DRAINAGE PIPE	12 LF		
0024	033560000-E	305	36" DRAINAGE PIPE	100 LF		
0025	034300000-E	310	15" SIDE DRAIN PIPE	336 LF		
0026	034400000-E	310	18" SIDE DRAIN PIPE	32 LF		
0027	036600000-E	310	15" RC PIPE CULVERTS, CLASS III	752 LF		
0028	037200000-E	310	18" RC PIPE CULVERTS, CLASS III	1,396 LF		
0029	037800000-E	310	24" RC PIPE CULVERTS, CLASS III	216 LF		
0030	038400000-E	310	30" RC PIPE CULVERTS, CLASS III	632 LF		
0031	039000000-E	310	36" RC PIPE CULVERTS, CLASS III	196 LF		
0032	044820000-E	310	15" RC PIPE CULVERTS, CLASS IV	4,688 LF		
0033	044830000-E	310	18" RC PIPE CULVERTS, CLASS IV	848 LF		
0034	044840000-E	310	24" RC PIPE CULVERTS, CLASS IV	376 LF		
0035	058200000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	420 LF		
0036	058800000-E	310	18" CS PIPE CULVERTS, 0.064" THICK	152 LF		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	0594000000-E	310	24" CS PIPE CULVERTS, 0.064" THICK	20 LF		
0038	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	8 EA		
0039	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (18", 0.064")	2 EA		
0040	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (24", 0.064")	1 EA		
0041	0973100000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B IN SOIL (15", 0.5")	72 LF		
0042	0995000000-E	340	PIPE REMOVAL	4,450 LF		
0043	1000000000-E	462	6" SLOPE PROTECTION	150 SY		
0044	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0045	1099500000-E	505	SHALLOW UNDERCUT	4,000 CY		
0046	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	7,600 TON		
0047	1220000000-E	545	INCIDENTAL STONE BASE	300 TON		
0048	1231000000-E	560	SHOULDER BORROW	4,200 CY		
0049	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	340 SY		
0050	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/4")	29,600 SY		
0051	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	22,250 TON		
0052	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,200 TON		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	12,400 TON		
0054	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	950 TON		
0055	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	15,800 TON		
0056	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	900 TON		
0057	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	2,675 TON		
0058	1577000000-E	620	POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX	80 TON		
0059	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	100 TON		
0060	1839140000-E	661	ULTRA-THIN BONDED WEARING COURSE	1,500 TON		
0061	1839200000-E	661	APPLICATION OF ULTRATHIN HOT MIX ASPHALT	42,300 SY		
0062	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CONCRETE)	20,000 LF		
0063	2000000000-N	806	RIGHT OF WAY MARKERS	197 EA		
0064	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
0065	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		
0066	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0067	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0068	2077000000-E	815	6" OUTLET PIPE	6 LF		
0069	2253000000-E	840	PIPE COLLARS	2.5 CY		
0070	2264000000-E	840	PIPE PLUGS	1 CY		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	2275000000-E	SP	FLOWABLE FILL	12 CY		
0072	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	150 EA		
0073	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	47.57 LF		
0074	2354000000-N	840	FRAME WITH GRATE, STD 840.22	2 EA		
0075	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	32 EA		
0076	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	9 EA		
0077	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	10 EA		
0078	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	19 EA		
0079	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	11 EA		
0080	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	26 EA		
0081	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	35 EA		
0082	2396000000-N	840	FRAME WITH COVER, STD 840.54	7 EA		
0083	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	1 EA		
0084	2440000000-N	852	CONCRETE TRANSITIONAL SECTION FOR CATCH BASIN	3 EA		
0085	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLET	7 EA		
0086	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	4,300 LF		
0087	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	13,450 LF		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0088	2556000000-E	846	SHOULDER BERM GUTTER	2,470 LF		
0089	2591000000-E	848	4" CONCRETE SIDEWALK	7,700 SY		
0090	2605000000-N	848	CONCRETE CURB RAMP	59 EA		
0091	2612000000-E	848	6" CONCRETE DRIVEWAY	825 SY		
0092	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	1,925 SY		
0093	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	150 LF		
0094	2830000000-N	858	ADJUSTMENT OF MANHOLES	15 EA		
0095	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	15 EA		
0096	3030000000-E	862	STEEL BM GUARDRAIL	12,637.5 LF		
0097	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	162.5 LF		
0098	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0099	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0100	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	2 EA		
0101	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	2 EA		
0102	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0103	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0104	3360000000-E	863	REMOVE EXISTING GUARDRAIL	8,136 LF		
0105	3435000000-N	SP	GENERIC GUARDRAIL ITEM EXTRA LENGTH GUARDRAIL POSTS (8' STEEL)	16 EA		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106	3500000000-E	866	WOVEN WIRE FENCE, *** FABRIC (48")	7,420 LF		
0107	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	490 EA		
0108	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	90 EA		
0109	3533000000-E	866	CHAIN LINK FENCE, *** FABRIC (60")	780 LF		
0110	3539000000-E	866	METAL LINE POSTS FOR *** CHAIN LINK FENCE (60")	70 EA		
0111	3545000000-E	866	METAL TERMINAL POSTS FOR *** CHAIN LINK FENCE (60")	10 EA		
0112	3557000000-E	866	ADDITIONAL BARBED WIRE	1,000 LF		
0113	3563000000-E	SP	TEMP *** WOVEN WIRE FENCE, COMPLETE W/POSTS (48")	2,400 LF		
0114	3579000000-N	866	GENERIC FENCING ITEM DOUBLE GATES, 48" HIGH, 6" WIDE, 12' OPENING (TEMPORARY)	1 EA		
0115	3628000000-E	876	RIP RAP, CLASS I	23 TON		
0116	3649000000-E	876	RIP RAP, CLASS B	1,010 TON		
0117	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	6,525 SY		
0118	4048000000-E	902	REINFORCED CONCRETE SIGN FOUNDATIONS	15 CY		
0119	4054000000-E	902	PLAIN CONCRETE SIGN FOUNDATIONS	2 CY		
0120	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	9,774 LB		
0121	4066000000-E	903	SUPPORTS, SIMPLE STEEL BEAM	3,723 LB		
0122	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	1,222 LF		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0123	4078000000-E	903	SUPPORTS, 2-LB STEEL U-CHANNEL	2 EA		
0124	4102000000-N	904	SIGN ERECTION, TYPE E	68 EA		
0125	4108000000-N	904	SIGN ERECTION, TYPE F	11 EA		
0126	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	12 EA		
0127	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	4 EA		
0128	4114000000-N	904	SIGN ERECTION, MILEMARKERS	2 EA		
0129	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (A)	4 EA		
0130	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (B)	1 EA		
0131	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	9 EA		
0132	4138000000-N	907	DISPOSAL OF SUPPORT, STEEL BEAM	8 EA		
0133	4152000000-N	907	DISPOSAL OF SIGN SYSTEM, STEEL BEAM	6 EA		
0134	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	82 EA		
0135	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	1,246 SF		
0136	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	1,228 SF		
0137	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	695 SF		
0138	4415000000-N	1115	FLASHING ARROW BOARD	4 EA		
0139	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	4 EA		



County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0140	4430000000-N	1130	DRUMS	600 EA		
0141	4445000000-E	1145	BARRICADES (TYPE III)	560 LF		
0142	4455000000-N	1150	FLAGGER	1,050 DAY		
0143	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	8 EA		
0144	4470000000-N	1160	RESET TEMPORARY CRASH CUSHION	6 EA		
0145	4480000000-N	1165	TMA	2 EA		
0146	4485000000-E	1170	PORTABLE CONCRETE BARRIER	7,380 LF		
0147	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	9,110 LF		
0148	4510000000-N	SP	LAW ENFORCEMENT	48 HR		
0149	4516000000-N	1180	SKINNY DRUM	200 EA		
0150	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	3,660 EA		
0151	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	140 LF		
0152	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	2,279 LF		
0153	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,073 LF		
0154	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	7 EA		
0155	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	165 EA		
0156	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	2,115 LF		
0157	4800000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING CHARACTER, TYPE ** (IV)	6 EA		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0158	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	250,345	LF	
0159	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	571	LF	
0160	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	6,186	LF	
0161	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	5,807	LF	
0162	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	60	EA	
0163	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	345	EA	
0164	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (HIGHLY REFLECTIVE ELEMENTS)	64,643	LF	
0165	4847100000-E	1205	POLYUREA PAVEMENT MARKING LINES (6", *****) (HIGHLY REFLECTIVE ELEMENTS)	21,785	LF	
0166	4847120000-E	1205	POLYUREA PAVEMENT MARKING LINES (12", *****) (HIGHLY REFLECTIVE ELEMENTS)	3,153	LF	
0167	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	119,373	LF	
0168	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	760	LF	
0169	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	22	LF	
0170	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	88	EA	
0171	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	619	EA	
0172	5015000000-E	1401	120' HIGH MOUNT STANDARD	3	EA	
0173	5020000000-N	1401	PORTABLE DRIVE UNIT	1	EA	
0174	5025000000-E	SP	HIGH MOUNT FOUNDATIONS	24.6	CY	

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0175	5030000000-N	1403	HIGH MOUNT LUMINAIRES ***** (750W HPS)	24 EA		
0176	5050000000-N	1404	LIGHT STANDARD, TYPE MTLT ***** (45' SA, 15' ARM)	14 EA		
0177	5070000000-N	1405	STANDARD FOUNDATION ***** (R1)	10 EA		
0178	5070000000-N	1405	STANDARD FOUNDATION ***** (R2)	4 EA		
0179	5080000000-N	1406	LIGHT STANDARD LUMINAIRES, TYPE ***** (RDW 250W HPS, FLAT GLASS, MC3)	14 EA		
0180	5120000000-N	1407	ELECTRIC SERVICE POLE **** ***** (30' CLASS 4)	1 EA		
0181	5125000000-E	1407	ELECTRIC SERVICE LATERAL ***** (3 #1/0 USE)	100 LF		
0182	5145000000-N	1408	LIGHT CONTROL EQUIPMENT, TYPE RW ***** (240/480 VOLT)	1 EA		
0183	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (2")	200 LF		
0184	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (3")	115 LF		
0185	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (4")	155 LF		
0186	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (2")	460 LF		
0187	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (3")	55 LF		
0188	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (4")	120 LF		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0189	5170000000-E	1410	** #8 W/G FEEDER CIRCUIT (2)	380 LF		
0190	5180000000-E	1410	** #4 W/G FEEDER CIRCUIT (2)	1,235 LF		
0191	5205000000-E	1410	** #8 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	3,830 LF		
0192	5215000000-E	1410	** #4 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	3,165 LF		
0193	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC18)	16 EA		
0194	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0195	5325200000-E	1510	2" WATER LINE	1,395 LF		
0196	5325600000-E	1510	6" WATER LINE	1,009 LF		
0197	5325800000-E	1510	8" WATER LINE	495 LF		
0198	5326200000-E	1510	12" WATER LINE	982 LF		
0199	5536000000-E	1515	2" VALVE	4 EA		
0200	5540000000-E	1515	6" VALVE	8 EA		
0201	5546000000-E	1515	8" VALVE	5 EA		
0202	5558000000-E	1515	12" VALVE	3 EA		
0203	5571600000-E	1515	6" TAPPING VALVE	1 EA		
0204	5571800000-E	1515	8" TAPPING VALVE	1 EA		
0205	5606000000-E	1515	2" BLOW OFF	2 EA		
0206	5648000000-N	1515	RELOCATE WATER METER	60 EA		
0207	5649000000-N	1515	RECONNECT WATER METER	3 EA		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0208	5672000000-N	1515	RELOCATE FIRE HYDRANT	11 EA		
0209	5691300000-E	1520	8" SANITARY GRAVITY SEWER	1,979 LF		
0210	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	60 EA		
0211	5775000000-E	1525	4' DIA UTILITY MANHOLE	9 EA		
0212	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	29 LF		
0213	5815000000-N	1530	REMOVE WATER METER	1 EA		
0214	5816000000-N	1530	ABANDON UTILITY MANHOLE	3 EA		
0215	5828000000-N	1530	REMOVE UTILITY MANHOLE	1 EA		
0216	6000000000-E	1605	TEMPORARY SILT FENCE	25,000 LF		
0217	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	1,850 TON		
0218	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	7,210 TON		
0219	6012000000-E	1610	SEDIMENT CONTROL STONE	4,200 TON		
0220	6015000000-E	1615	TEMPORARY MULCHING	25 ACR		
0221	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	900 LB		
0222	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	5.5 TON		
0223	6024000000-E	1622	TEMPORARY SLOPE DRAINS	2,000 LF		
0224	6029000000-E	SP	SAFETY FENCE	500 LF		
0225	6030000000-E	1630	SILT EXCAVATION	9,600 CY		
0226	6036000000-E	1631	MATTING FOR EROSION CONTROL	50,000 SY		
0227	6037000000-E	SP	COIR FIBER MAT	300 SY		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0228	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	5,625 SY		
0229	6042000000-E	1632	1/4" HARDWARE CLOTH	10,000 LF		
0230	6071020000-E	SP	POLYACRYLAMIDE (PAM)	1,350 LB		
0231	6071030000-E	1640	COIR FIBER BAFFLE	2,020 LF		
0232	6071050000-E	SP	*** SKIMMER (1-1/2")	23 EA		
0233	6084000000-E	1660	SEEDING & MULCHING	25 ACR		
0234	6087000000-E	1660	MOWING	15 ACR		
0235	6090000000-E	1661	SEED FOR REPAIR SEEDING	250 LB		
0236	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.75 TON		
0237	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	425 LB		
0238	6108000000-E	1665	FERTILIZER TOPDRESSING	12.75 TON		
0239	6114500000-N	1667	SPECIALIZED HAND MOWING	40 MHR		
0240	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	100 EA		
0241	6890000000-E	SP	CONCRETE STEPS	10 CY		
0242	6895000000-E	SP	HANDRAIL ON STEPS	30 LF		
0243	7048500000-E	1705	PEDESTRIAN SIGNAL HEAD (16", 1 SECTION W/COUNTDOWN)	34 EA		
0244	7060000000-E	1705	SIGNAL CABLE	17,130 LF		
0245	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	84 EA		
0246	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	10 EA		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0247	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	7 EA		
0248	7252000000-E	1710	MESSENGER CABLE (1/4")	5,510 LF		
0249	7264000000-E	1710	MESSENGER CABLE (3/8")	2,520 LF		
0250	7279000000-E	1715	TRACER WIRE	4,810 LF		
0251	7288000000-E	1715	PAVED TRENCHING (***** (1, 2")	150 LF		
0252	7288000000-E	1715	PAVED TRENCHING (***** (2, 2")	10 LF		
0253	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	6,220 LF		
0254	7300000000-E	1715	UNPAVED TRENCHING (***** (2, 2")	460 LF		
0255	7300000000-E	1715	UNPAVED TRENCHING (***** (4, 2")	70 LF		
0256	7300100000-E	1715	UNPAVED TRENCHING FOR TEMP- ORARY LEAD-IN	2,440 LF		
0257	7301000000-E	1715	DIRECTIONAL DRILL (***** (1, 2")	2,120 LF		
0258	7301000000-E	1715	DIRECTIONAL DRILL (***** (2, 2")	1,880 LF		
0259	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	49 EA		
0260	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEA- VY DUTY)	43 EA		
0261	7360000000-N	1720	WOOD POLE	17 EA		
0262	7372000000-N	1721	GUY ASSEMBLY	50 EA		
0263	7396000000-E	1722	1/2" RISER WITH WEATHERHEAD	2 EA		
0264	7408000000-E	1722	1" RISER WITH WEATHERHEAD	4 EA		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0265	7420000000-E	1722	2" RISER WITH WEATHERHEAD	23 EA		
0266	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	6 EA		
0267	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	10,030 LF		
0268	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	29,180 LF		
0269	7516000000-E	1730	COMMUNICATIONS CABLE (**FIBER) (12)	13,400 LF		
0270	7552000000-N	1731	INTERCONNECT CENTER	7 EA		
0271	7564000000-N	1732	FIBER-OPTIC TRANSCEIVER, DROP & REPEAT	7 EA		
0272	7566000000-N	1733	DELINEATOR MARKER	15 EA		
0273	7568000000-N	SP	FURNISH FIBER-OPTIC RESTORA- TION KIT	1 EA		
0274	7570000000-N	SP	FURNISH FIBER-OPTIC POWER ME- TER	1 EA		
0275	7572000000-N	SP	FURNISH OPTICAL LIGHT GENERA- TOR	1 EA		
0276	7574000000-N	SP	FURNISH FIBER-OPTIC TRANSCEIV- ER	1 EA		
0277	7575142060-N	SP	MODIFY RADIO INSTALLATION	1 EA		
0278	7588000000-N	SP	METAL POLE WITH SINGLE MAST ARM	16 EA		
0279	7590000000-N	SP	METAL POLE WITH DUAL MAST ARM	4 EA		
0280	7613000000-N	SP	SOIL TEST	20 EA		
0281	7614100000-E	SP	DRILLED PIER FOUNDATION	160 CY		
0282	7631000000-N	SP	MAST ARM WITH METAL POLE DE- SIGN	20 EA		



County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0283	7636000000-N	1745	SIGN FOR SIGNALS	18	EA	
0284	7642200000-N	1743	TYPE II PEDESTAL WITH FOUNDATION	16	EA	
0285	7684000000-N	1750	SIGNAL CABINET FOUNDATION	6	EA	
0286	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	6	EA	
0287	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	45	EA	
0288	7901000000-N	1753	CABINET BASE EXTENDER	6	EA	
0289	7980000000-N	SP	GENERIC SIGNAL ITEM PROTECTIVE GREEN COATING FOR DOUBLE MAST ARM WITH METAL POLE	4	EA	
0290	7980000000-N	SP	GENERIC SIGNAL ITEM PROTECTIVE GREEN COATING FOR SINGLE MAST ARM WITH METAL POLE	16	EA	
0291	7980000000-N	SP	GENERIC SIGNAL ITEM PROTECTIVE GREEN COATING FOR TYPE II PEDESTAL WITH FOUNDATION	16	EA	

**WALL ITEMS**

0292	8801000000-E	SP	MSE RETAINING WALLS	964	SF	
------	--------------	----	---------------------	-----	----	--

**STRUCTURE ITEMS**

0293	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (76+15.21-L-)	Lump Sum	L.S.	
0294	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1, 76+15.21-L-)	Lump Sum	L.S.	

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0295	8112730000-N	450	PDA TESTING	3 EA		
0296	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (76+15.21-L-)	Lump Sum	L.S.	
0297	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	16,152 SF		
0298	8161000000-E	420	GROOVING BRIDGE FLOORS	13,057 SF		
0299	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	322.1 CY		
0300	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (76+15.21-L-)	Lump Sum	L.S.	
0301	8217000000-E	425	REINFORCING STEEL (BRIDGE)	31,895 LB		
0302	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,864 LB		
0303	8265000000-E	430	54" PRESTRESSED CONCRETE GIRDERS	2,277.46 LF		
0304	8364000000-E	450	HP12X53 STEEL PILES	2,835 LF		
0305	8393000000-N	450	PILE REDRIVES	63 EA		
0306	8475000000-E	460	TWO BAR METAL RAIL	449.29 LF		
0307	8517000000-E	460	1'-***"X ***** CONCRETE PARAPET (1'-5" X 2'-6")	464.64 LF		
0308	8531000000-E	462	4" SLOPE PROTECTION	785 SY		
0309	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0310	8892000000-E	SP	GENERIC STRUCTURE ITEM ARCHITECTURAL CONCRETE SURFACE TREATMENT	6,470 SF		

**Contract No.**     **C202815**

**County (ies):**    **Burke**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General

Signature Sheet (Bid - Acceptance by Department)