

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (16+08.00 -L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	600 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	76.9 CY		
0008	0195000000-E	SP	SELECT GRANULAR MATERIAL	500 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	600 SY		
001C	0223000000-E	SP	ROCK PLATING	560 SY		
0011	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	20 TON		
0012	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	40 SY		
0013	0343000000-E	SP	15" SIDE DRAIN PIPE	52 LF		
0014	0354000000-E	SP	**** RC PIPE CULVERTS, CLASS ***** (15", V)	32 LF		
001E	0582000000-E	SP	15" CS PIPE CULVERTS, 0.064" THICK	32 LF		
0016	0636000000-E	SP	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	2 EA		
0017	0995000000-E	340	PIPE REMOVAL	50 LF		
0018	1121000000-E	520	AGGREGATE BASE COURSE	80 TON		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1220000000-E	545	INCIDENTAL STONE BASE	300	TON	
0020	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	480	TON	
0021	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	590	TON	
0022	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	260	TON	
0023	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	66	TON	
0024	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	30	TON	
002E	2000000000-N	806	RIGHT OF WAY MARKERS	5	EA	
002E	2022000000-E	SP	SUBDRAIN EXCAVATION	44.8	CY	
0027	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	33.6	CY	
002E	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	200	LF	
0029	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1	EA	
003C	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6	LF	
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2	EA	
0032	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2	EA	
0033	2556000000-E	846	SHOULDER BERM GUTTER	320	LF	
0034	2738000000-E	SP	GENERIC PAVING ITEM 6" CONCRETE DRIVEWAYS	200	SY	
003E	3030000000-E	862	STEEL BM GUARDRAIL	450	LF	
003E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III SHOP CURVED)	1 EA		
003E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
003E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	3 EA		
004C	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0041	3360000000-E	863	REMOVE EXISTING GUARDRAIL	748 LF		
0042	3551000000-E	866	METAL GATE POSTS FOR *** CHAIN LINK FENCE, SINGLE GATE 48" SINGLE GATE	2 EA		
004E	3564000000-E	866	SINGLE GATES, *** HIGH, *** WIDE, *** OPENING (48", 14", 14")	1 EA		
0044	3628000000-E	876	RIP RAP, CLASS I	82 TON		
004E	3649000000-E	876	RIP RAP, CLASS B	1 TON		
004E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,425 SY		
0047	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	100 LF		
004E	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
004E	4102000000-N	904	SIGN ERECTION, TYPE E	5 EA		
005C	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	7 EA		
0051	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	493 SF		
0052	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	139 SF		
005E	4430000000-N	1130	DRUMS	15 EA		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4445000000-E	1145	BARRICADES (TYPE III)	136	LF	
005E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,640	LF	
005E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,640	LF	
0057	6000000000-E	1605	TEMPORARY SILT FENCE	715	LF	
005E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	270	TON	
005E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	120	TON	
006C	6012000000-E	1610	SEDIMENT CONTROL STONE	345	TON	
0061	6015000000-E	1615	TEMPORARY MULCHING	2.5	ACR	
0062	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
006E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.5	TON	
0064	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
006E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
006E	6029000000-E	SP	SAFETY FENCE	200	LF	
0067	6030000000-E	1630	SILT EXCAVATION	450	CY	
006E	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,000	SY	
006E	6037000000-E	SP	COIR FIBER MAT	20	SY	
007C	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	2,355	SY	
0071	6042000000-E	1632	1/4" HARDWARE CLOTH	210	LF	

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	6070000000-N	SP	SPECIAL STILLING BASINS	12	EA	
0073	6071030000-E	SP	COIR FIBER BAFFLE	145	LF	
0074	6071050000-E	SP	*** SKIMMER (1-1/2")	2	EA	
007E	6084000000-E	1660	SEEDING & MULCHING	3	ACR	
007E	6087000000-E	1660	MOWING	3	ACR	
0077	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
007E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
007E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75	LB	
008C	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75	TON	
0081	6114500000-N	SP	SPECIALIZED HAND MOWING	10	MHR	
0082	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18	EA	
STRUCTURE ITEMS						
008E	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (16+08.00-L-)	Lump Sum	L.S.	
0084	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+08.00-L-)	Lump Sum	L.S.	
008E	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	84	LF	
008E	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	113	LF	

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0087	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	83.1 LF		
008E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (16+08.00-L-)	Lump Sum	L.S.	
008E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	139.6 CY		
009C	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+08.00-L-)	Lump Sum	L.S.	
0091	8217000000-E	425	REINFORCING STEEL (BRIDGE)	36,406 LB		
0092	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	6,180 LB		
009E	8364000000-E	SP	HP12X53 STEEL PILES	340 LF		
0094	8475000000-E	460	TWO BAR METAL RAIL	600.5 LF		
009E	8517000000-E	460	1'-***"X ***** CONCRETE PARA- PET (1'-2" X 2'-11")	615.5 LF		
009E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	530 TON		
0097	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	760 SY		
009E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
009E	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	3,688.5 LF		
010C	8897000000-N	SP	GENERIC STRUCTURE ITEM CSL TESTING	1 EA		

1137/Mar14/Q71948.5/D428294860000/E100

Total Amount Of Bid For Entire Project :

Contract No **C202738**

County (ies): **Davidson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General