

County : Granville, Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1330000000-E	607	INCIDENTAL MILLING	4,190	SY	
0003	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	482.9	TON	
0004	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	35	TON	
0005	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	240	SF	
0006	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	856	SF	
0007	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	58	SF	
0008	4415000000-N	1115	FLASHING ARROW BOARD	2	EA	
0009	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	3	EA	
0010	4430000000-N	1130	DRUMS	125	EA	
0011	4435000000-N	1135	CONES	50	EA	
0012	4445000000-E	1145	BARRICADES (TYPE III)	80	LF	
0013	4455000000-N	1150	FLAGGER	40	DAY	
0014	4480000000-N	1165	TMA	3	EA	
0015	4510000000-N	SP	LAW ENFORCEMENT	320	HR	
0016	4516000000-N	1180	SKINNY DRUM	125	EA	
0017	4726100000-E	1205	HEATED-IN-PLACE THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	8	EA	
0018	4726110000-E	1205	HEATED-IN-PLACE THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	9	EA	

County : Granville, Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4800000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING CHARACTER, TYPE ** (II)	8 EA		
0020	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (II)	6 EA		
0021	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	14,000 LF		
0022	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	16 EA		
0023	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	15 EA		
0024	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (HIGHLY REFLECTIVE ELEMENTS)	14,000 LF		
0025	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	57 EA		
0026	8161000000-E	420	GROOVING BRIDGE FLOORS	66,953 SF		
0027	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,400 LB		
0028	8660000000-E	SP	CONCRETE REPAIRS	67 CF		
0029	8664000000-E	SP	SHOTCRETE REPAIRS	267 CF		
0030	8678000000-E	SP	EPOXY RESIN INJECTION	227 LF		
0031	8692000000-N	SP	FOAM JOINT SEALS	Lump Sum	L.S.	
0032	8860000000-N	SP	GENERIC STRUCTURE ITEM BRIDGE JACKING	Lump Sum	L.S.	
0033	8860000000-N	SP	GENERIC STRUCTURE ITEM CLEANING & PAINTING EXISTING BEARING PLATES	Lump Sum	L.S.	
0034	8881000000-E	SP	GENERIC STRUCTURE ITEM LATEX MOD CONC OVERLAY VERY EARLY STRENGTH	371 CY		

County : Granville, Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	8889000000-E	SP	GENERIC STRUCTURE ITEM BEAM REPAIR	3,432	LB	
003E	8892000000-E	SP	GENERIC STRUCTURE ITEM CLASS II CONCRETE DECK REPAIR FOR EPOXY/ASPHALT OVERLAY	1,056	SF	
0037	8892000000-E	SP	GENERIC STRUCTURE ITEM PLACEMENT OF EPOXY OVERLAY	9,503	SF	
003E	8893000000-E	SP	GENERIC STRUCTURE ITEM HYDRO-DEMOLITION OF BRIDGE DECK	8,333	SY	
003E	8893000000-E	SP	GENERIC STRUCTURE ITEM PLACE & FINISH LATEX MOD CONC OVERLAY VERY EARLY STRENGTH	8,333	SY	
004C	8893000000-E	SP	GENERIC STRUCTURE ITEM SCARIFYING BRIDGE DECK	8,333	SY	
0041	8897000000-N	SP	GENERIC STRUCTURE ITEM BEARING REPLACEMENT IN KIND	41	EA	

0830/Mar15/Q148048.9/D240972310000/E41

Total Amount Of Bid For Entire Project :

**Contract No.**     **C202995**

**County (ies):**   **Granville & Durham**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General