

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (16+17.00 -L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	223 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	2,500 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA-TION	2,600 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE-RIAL, MINOR STRUCTURES	18 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEO-TEXTILE	82 SY		
0012	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	64 LF		
0013	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	2 EA		
0014	1099500000-E	505	SHALLOW UNDERCUT	175 CY		
0015	1099700000-E	505	CLASS IV SUBGRADE STABILIZA-TION	350 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0017	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (0" TO 1-1/2")	340 SY		
0018	1330000000-E	607	INCIDENTAL MILLING	270 SY		

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	150 TON		
0020	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	100 TON		
0021	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	220 TON		
0022	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	25 TON		
0023	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
0024	2022000000-E	815	SUBDRAIN EXCAVATION	56 CY		
0025	2033000000-E	815	SUBDRAIN FINE AGGREGATE	42 CY		
0026	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	250 LF		
0027	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0028	2077000000-E	815	6" OUTLET PIPE	6 LF		
0029	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0030	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0031	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0032	2556000000-E	846	SHOULDER BERM GUTTER	10 LF		
0033	3420000000-E	SP	GENERIC GUARDRAIL ITEM PAINTED GALVANIZED STEEL BEAM GUARDRAIL	75 LF		
0034	3435000000-N	SP	GENERIC GUARDRAIL ITEM PAINTED GALVANIZED ADDITIONAL GUARDRAIL POSTS	5 EA		
0035	3435000000-N	SP	GENERIC GUARDRAIL ITEM PAINTED GALVANIZED ANCHOR UNITS, TYPE 350	4 EA		

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3435000000-N	SP	GENERIC GUARDRAIL ITEM PAINTED GALVANIZED ANCHOR UNITS, TYPE III	4 EA		
0037	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	1,200 LF		
0038	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	60 EA		
0039	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	60 EA		
0040	3557000000-E	866	ADDITIONAL BARBED WIRE	500 LF		
0041	3575000000-E	SP	GENERIC FENCING ITEM REMOVE & RESET ELECTRIC FENCE	1,150 LF		
0042	3578000000-N	SP	GENERIC FENCING ITEM REMOVE & RESET METAL GATES	5 EA		
0043	3649000000-E	876	RIP RAP, CLASS B	10 TON		
0044	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	486 SY		
0045	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	366 SF		
0046	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	104 SF		
0047	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0048	5326600000-E	1510	16" WATER LINE	155 LF		
0049	5810000000-E	1530	ABANDON 16" UTILITY PIPE	155 LF		
0050	6000000000-E	1605	TEMPORARY SILT FENCE	1,200 LF		
0051	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
0052	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	60 TON		
0053	6012000000-E	1610	SEDIMENT CONTROL STONE	100 TON		

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
0055	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0056	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25	TON	
0057	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
0058	6029000000-E	SP	SAFETY FENCE	100	LF	
0059	6030000000-E	1630	SILT EXCAVATION	130	CY	
0060	6036000000-E	1631	MATTING FOR EROSION CONTROL	3,700	SY	
0061	6037000000-E	SP	COIR FIBER MAT	10	SY	
0062	6042000000-E	1632	1/4" HARDWARE CLOTH	435	LF	
0063	6071030000-E	1640	COIR FIBER BAFFLE	100	LF	
0064	6071050000-E	SP	*** SKIMMER (1-1/2")	1	EA	
0065	6084000000-E	1660	SEEDING & MULCHING	3	ACR	
0066	6087000000-E	1660	MOWING	3	ACR	
0067	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0068	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0069	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0070	6108000000-E	1665	FERTILIZER TOPDRESSING	1	TON	
0071	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	
0072	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18	EA	
0073	7279000000-E	1715	TRACER WIRE	42	LF	

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	7301000000-E	1715	DIRECTIONAL DRILL (***** (2, 2"))	40 LF		
STRUCTURE ITEMS						
0075	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+17.00-L-)	Lump Sum	L.S.	
0076	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (16+17.00-L-)	Lump Sum	L.S.	
0077	8156000000-E	SP	CONCRETE WEARING SURFACE	1,700 SF		
0078	8161000000-E	420	GROOVING BRIDGE FLOORS	2,300 SF		
0079	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	36 CY		
0080	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+17.00-L-)	Lump Sum	L.S.	
0081	8217000000-E	425	REINFORCING STEEL (BRIDGE)	4,814 LB		
0082	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	382 LB		
0083	8384000000-E	450	HP14X73 STEEL PILES	400 LF		
0084	8475000000-E	460	TWO BAR METAL RAIL	96.5 LF		
0085	8517000000-E	460	1'-****X ***** CONCRETE PARA- PET (1'-2" x 2'-10")	111.5 LF		
0086	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	35 TON		
0087	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	39 SY		
0088	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	613.25 LF		
0090	8892000000-E	SP	GENERIC STRUCTURE ITEM 18" STEEL SHEET PILES	1,125 SF		
1437/Mar15/Q30799.25/D390885880000/E90			Total Amount Of Bid For Entire Project :			

Contract No. **C202776**

County (ies): **Mecklenburg**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General